

QUOTATION

AMPS

AQUIFER MAINTENANCE & PERFORMANCE SYSTEMS, INC.

7146 Haverhill Road N. • West Palm Beach, FL 33407 • 561-494-2844

February 18, 2016

City of Delray Beach
200 SW 6th Street
Delray Beach, FL 33444
Attn: Ryan Lingholm

Re: FLOWMETER REPLACEMENT

AMPS, Inc. appreciates the opportunity to submit the following proposal for your review based on our existing contract #2012-2540 with Martin County Utilities for your review:

- | | |
|--|---------------------|
| 1) 20 – 8" Water Specialties flowmeter model VF32-D 150 psi vertical downflow
Propeller meter, for cast iron or fabricated tee. Includes Flowcom model
FC101-02 battery powered LDC register. 2-wire 4-20m A output. Direct mount
Configuration (\$3.155/each) Line item 41 | \$ 63,100.00 |
| 2) 5 – 6" Water Specialties flowmeter model VF32-D 150 psi vertical downflow
Propeller meter, for cast iron or fabricated tee. Includes Flowcom model FC101-02
Battery powered LDC register. 2-wire 4-20m A output. Direct mount configuration
(\$3.025/each) Line item 41 | 15,125.00 |
| 3) Setup, remove existing flowmeter, install new flowmeter, run all wiring &
Conduit to RTU for remote signaling; program, calibrate & certify each meter.
Verify readings remotely and on site approximately 12-14 hours per well
(\$85/hour) Line item 22 | 29,750.00 |
| 4) Freight charges not to exceed Line item 41 | 225.00 |
| TOTAL: | \$108,200.00 |

If you have any questions about the above information or if we may be of any further assistance please don't hesitate to call. Thank you.

Sincerely,

Jim Murray

Jim Murray
President

**FOR YOUR TOTAL PUMP & WELL FIELD NEEDS
ABOVE QUOTATION GOOD FOR 30 DAYS.**