

SCOPE OF WORK


THE FOLLOWING DRAWINGS ILLUSTRATE THE PROPOSED SCOPE OF WORK FOR 917 N.E. 8TH AVE. TO BE APPROVED BY THE CITY OF DELRAY BEACH:

- REMOVAL OF EXISTING TREES
- INSTALLATION NEW LANDSCAPE PLANTINGS
- INSTALLATION OF NEW IRRIGATION SYSTEM
- INSTALLATION OF NEW HARDSCAPE
- INSTALLATION OF NEW FRONT ENTRY DRIVEWAY
- INSTALLATION OF NEW LANDSCAPE LIGHTING

07.01.2022 TAC REV 2  
04.22.2022 TAC REV 1  
10.15.2021  
10.20.2021

SHEET INDEX	
LANDSCAPE DRAWINGS	DRAWING NOTES
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	LCVR COVER PAGE
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L001 GENERAL SITE NOTES
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L100 TREE DISPOSITION NOTES
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L101 TREE DISPOSITION NOTES
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L102 TREE DISPOSITION SCHEDULE & MITIGATION CALCULATIONS
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L103 TREE REFERENCE IMAGES
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L104 TREE DISPOSITION PLAN
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L200 DEMOLITION PLAN & NOTES
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L300 MATERIALS PLAN & NOTES
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L400 GRADING PLAN & NOTES
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L500 LAYOUT PLAN & NOTES
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L600 DETAILS
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L700 PLANTING SCHEDULE & NOTES
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L700A LANDSCAPE CALCULATION / FOUNDATION PLANTING SCHEDULE
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L700B LANDSCAPE REQUIREMENTS
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L701 TREE & PALM PLANTING PLAN
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L702 UNDERSTORY PLANTING PLAN
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L703 PLANTING DETAILS
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L704 PLANTING DETAILS
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L800 IRRIGATION NOTES, SCHEDULE & DETAILS
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L801 IRRIGATION DETAILS
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L803 IRRIGATION PLAN
<div><div><div>07</div><div>01</div><div>2022</div><div>TAC REV 2</div></div><div><div>04</div><div>22</div><div>2022</div><div>TAC REV 1</div></div><div><div>10</div><div>15</div><div>2021</div><div></div></div><div><div>10</div><div>20</div><div>2021</div><div></div></div></div>	L900 LIGHTING PLAN, SCHEDULE, CALCS. & SPECS.

LOCATION MAP






**NIELSEN**  
landscape architects

357 cypress drive, 10  
tequesta, fl 33469  
561.402.9414

www.nielsenlandarch.com

917 N.E. 8TH AVE. GARDEN

SEAL (S TYLER NIELSEN - LA6667067)



07.01.2022

COVER PAGE	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2

LCVR

SITework GENERAL NOTES

1. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL WORK BY THE SUBCONTRACTORS.
2. CONTRACTOR SHALL VERIFY ALL CONDITIONS AT JOB SITE AND NOTIFY LANDSCAPE ARCHITECT AND GENERAL CONTRACTOR OF DIMENSIONAL ERRORS, OMISSIONS OR DISCREPANCIES BEFORE BEGINNING ANY WORK.
3. CONTRACTOR TO OBTAIN ALL NECESSARY PERMITS PRIOR TO CONSTRUCTION. ALL CONTRACTORS MUST COMPLY WITH PERMIT REQUIREMENTS, LOCAL, STATE AND FEDERAL JURISDICTIONS AND GOVERNING BODIES/AGENCIES RULES AND REGULATIONS AND LAND USE APPROVAL CONDITIONS AT ALL TIMES.
4. WORK PERFORMED WITHOUT APPROVAL OF LOCAL, STATE AND FEDERAL JURISDICTIONS AND GOVERNING BODIES/AGENCIES AND/OR NOT IN COMPLIANCE WITH SPECIFICATIONS AND/OR DRAWINGS IS SUBJECT TO REMOVAL AT CONTRACTOR'S EXPENSE.
5. ALL WORK SHALL CONFORM TO THE APPROPRIATE AGENCIES. CONTRACTOR SHALL VERIFY LOCATION OF ALL EXISTING UTILITIES, LINES AND STRUCTURES PRIOR TO EXCAVATION OR TRENCHING. DAMAGE SHALL BE REPAIRED BY THE CONTRACTOR AT NO COST TO THE OWNER. THE LANDSCAPE ARCHITECT ASSUMES NO RESPONSIBILITY FOR UTILITIES OR STRUCTURES NOT SHOWN ON THE DRAWINGS. CONTRACTOR IS TO VERIFY THE EXACT LOCATION OF UTILITIES PRIOR TO CONSTRUCTION AND NOTIFY THE LANDSCAPE ARCHITECT OF ANY DISCREPANCIES. CONTRACTOR SHALL USE EXTREME CAUTION WHEN WORKING OVER OR NEAR EXISTING GAS AND ELECTRICAL LINES.
6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESETTING ALL LAND MONUMENTS DISRUPTED BY CONSTRUCTION ACTIVITIES OR NEGLIGENCE ON THE PART OF THE CONTRACTOR. RESETS SHALL BE PERFORMED UNDER THE SUPERVISION OF A REGISTERED LAND SURVEYOR AND MONUMENT RECORDS MUST BE FILED AS REQUIRED BY STATUTE FOR ALL MONUMENTS.
7. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONARY MEASURES NECESSARY TO PROTECT EXISTING IMPROVEMENTS FROM DAMAGE AND ALL SUCH IMPROVEMENTS AND STRUCTURES DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED OR RECONSTRUCTED SATISFACTORY TO THE LANDSCAPE ARCHITECT AT THE CONTRACTOR'S EXPENSE.
8. ALL BARRICADING AND TEMPORARY TRAFFIC CONTROL DEVICES OR METHODS USED DURING CONSTRUCTION SHALL BE IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL JURISDICTIONS AND GOVERNING BODIES/AGENCIES STANDARDS. PROVIDE ADEQUATE TIME FOR REVIEW AND APPROVAL BY THE ABOVE JURISDICTIONS PRIOR TO COMMENCEMENT.
9. THE LANDSCAPE ARCHITECT IS NOT RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES UTILIZED OR FOR SAFETY PRECAUTIONS OR PROBLEMS IN CONNECTION WITH THE WORK. THE LANDSCAPE ARCHITECT WILL NOT BE RESPONSIBLE FOR THE CONTRACTOR'S FAILURE TO CARRY OUT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. CONTRACT DOCUMENTS INCLUDE THE CONSTRUCTION DOCUMENT DRAWING SET/TECHNICAL SPECIFICATIONS MANUAL/LASIS.
10. CONTRACTOR TO VERIFY ALL QUANTITIES. IN CASE OF ANY DISCREPANCIES, GRAPHICALLY SHOWN MATERIAL QUANTITIES SHALL TAKE PRECEDENCE.
11. A SYSTEM OF DIAGRAMMATIC SYMBOLS, HATCHES AND NOTATIONS IS USED IN THESE DRAWINGS. REVIEW NOTATIONS CAREFULLY, NOTIFY LANDSCAPE ARCHITECT AND REQUEST CLARIFICATION OF ANY UNCLEAR NOTATION OR DISCREPANCY PRIOR TO COMMENCING WORK.

SITework GENERAL NOTES CONTINUED

1. PROVIDE SLEEVES AS REQUIRED FOR DRAINAGE, IRRIGATION AND ELECTRICAL LINES. IRRIGATION AND ELECTRICAL SLEEVES AND SUBSURFACE DRAINAGE SYSTEMS SHALL BE CONSTRUCTED PRIOR TO PAVING AND LANDSCAPE WORK. UTILITY SLEEVES ARE REQUIRED IN ALL PLANT BEDS ISOLATED BY PAVEMENT OR ANY OTHER STRUCTURES.
2. SPECIAL CONSIDERATION IS GIVEN TO THE DESIGN AND INTENDED RELATIONSHIP BETWEEN ARCHITECTURE, PLANTING AREAS AND PAVING SYSTEMS. PAVEMENT JOINTING, PAVERS, STONE, FINISHES AND GRADES HAVE BEEN STRICTLY COORDINATED IN THE CONTRACT DOCUMENTS. CONSTRUCTION OF THESE SYSTEMS SHALL BE STRICTLY COORDINATED.
3. VEHICLES, EQUIPMENT, AND/OR MATERIALS SHALL NOT BE PARKED OR STORED IN AREAS OF EXISTING VEGETATION, INCLUDING WITHIN THE DRIPLINE OF EXISTING TREES TO REMAIN.
4. CONSTRUCTION WASTE-INCLUDING BUT NOT LIMITED TO: PLANT MATERIAL, BUILDING MATERIALS, DEMOLISHED MATERIALS, PACKAGING, LEFTOVER PAINT AND CONCRETE SLURRY-SHOULD BE PROPERLY REUSED, RECYCLED, DISPOSED OF LEGALLY OFF-SITE OR IN DESIGNATED WASH-OUT AREAS DETERMINED BY THE GENERAL CONTRACTOR.
5. RECYCLING AND TRASH BINS TO BE PROVIDED ON SITE. SEPARATE BINS FOR CARDBOARD, CO-MINGLED, AND OTHER RECYCLABLE/REUSABLE MATERIALS IDENTIFIED BY THE LOCAL JURISDICTION SHALL BE MAINTAINED. ALL BINS TO BE WILDLIFE-PROOF.
6. ON-SITE FUEL STORAGE FOR CONSTRUCTION EQUIPMENT IS DISCOURAGED. CONSTRUCTION EQUIPMENT USED ON SITE TO BE CHECKED REGULARLY TO ASSURE CONTAMINATION CONCERNS FROM OILS AND GREASES ARE ELIMINATED. NO TOXIC MATERIALS SHALL BE STORED ON-SITE.
7. GENERAL CONTRACTOR TO KEEP ALL ITEMS IMPLEMENTED BY LANDSCAPE ARCHITECT IN PROPER WORKING ORDER THROUGHOUT THE DURATION OF THE PROJECT.
8. THE CONSTRUCTION SITE TO BE INSPECTED ON A MONTHLY BASIS BY LANDSCAPE ARCHITECT AND/OR CIVIL ENGINEER TO ASSURE THAT THE SILT FENCE AND MUD TRACKING PAD ARE PROPERLY IN PLACE AND FUNCTIONING AS DESIGNED.
9. GREEN BUILDING PRACTICES SHALL BE EMPLOYED TO THE EXTENT FEASIBLE. SUCH PRACTICES INCLUDE: CARPOOLING/VANPOOLING TO JOB SITE, MINIMIZING MATERIALS PACKING BEFORE ARRIVAL TO JOB SITE, REDUCING MATERIAL/RESOURCE INEFFICIENCIES BY COORDINATING WORK.
10. THE PROJECT LIMIT OF CONSTRUCTION AND ALL EXISTING VEGETATION TO REMAIN IS TO BE CLEARLY DEFINED BY STURDY, WEATHERPROOF FENCING AT A MINIMUM OF FOUR (4) FEET HIGH.
11. WATERPROOFING OF SUBGRADE AND OTHER ARCHITECTURAL SPACES BELOW AND/OR ADJACENT TO IMPROVEMENTS DESIGNED BY THE LANDSCAPE ARCHITECT IS TO BE ADEQUATELY DESIGNED AND DETAILED BY OTHERS TO PERMANENTLY REPEL ALL WATER SOURCES INCLUDING, BUT NOT LIMITED TO: PRECIPITATION, STORM WATER RUNOFF, GROUND WATER, IRRIGATION, ROOF RUNOFF, GROUND WATER, AND PLUMBING LEAKS.
12. STRUCTURAL DESIGN TO SUPPORT IMPROVEMENTS DESIGNED BY THE LANDSCAPE ARCHITECT AND LOCATED ABOVE, BELOW, AND/OR ADJACENT TO SUBGRADE AND OTHER ARCHITECTURAL SPACES IS THE RESPONSIBILITY OF THE STRUCTURAL ENGINEER. THE STRUCTURAL DESIGN SHOULD BE ADEQUATELY DESIGNED TO SUPPORT ALL POSSIBLE LOADS INCLUDING, BUT NOT LIMITED TO: BACKFILL, COMPACTION, PLANTINGS, HARDSCAPES, RETAINING AND FREESTANDING SITE WALLS, AND CONSTRUCTION MATERIALS/EQUIPMENT/ACTIVITY.

SOIL EROSION CONTROL NOTES

1. PRIOR TO BEGINNING ANY EARTH CHANGE, THE CONTRACTOR SHALL INSTALL AND MAINTAIN ALL SESC MEASURES AS SHOWN ON THE CONTRACT DOCUMENTS AND AS REQUIRED BY ANY GOVERNING AGENCIES.
2. ALL SESC MEASURES TO BE MAINTAINED DAILY.
3. THE CONTRACTOR TO CONDUCT ALL EXCAVATION, FILLING, GRADING, AND CLEANUP OPERATIONS IN A MANNER SUCH THAT SEDIMENT, GENERATED BY WIND OR WATER IS NOT DISCHARGED INTO ANY STORM SEWER, DRAINAGE DITCH, RIVER, LAKE, AIR, OR UNDERGROUND UTILITY SYSTEM. STAGE WORK TO MINIMIZE THE AREA OF EXPOSED SOIL, THEREBY REDUCING THE OPPORTUNITY FOR SOIL EROSION.
4. WATER FROM TRENCHES AND OTHER EXCAVATION TO BE PUMPED INTO A FILTRATION BAG TO REMOVE SEDIMENTS FROM THE WATER.
5. NORTH AMERICAN GREEN SC-150 OR EQUIVALENT EROSION CONTROL FABRIC IS REQUIRED ON ALL DISTURBED SLOPES GREATER THAN 3:1 UNTIL PROJECT AREA IS REVEGETATED PER THE PLANTING PLAN.
6. PROVIDE POSITIVE DRAINAGE AWAY FROM ALL STRUCTURES.
7. CONTRACTOR TO PROVIDE ONSITE WATERING TO REDUCE FUGITIVE DUST LEAVING THE SITE DURING CONSTRUCTION.
8. SOIL EROSION CONTROL MEASURES TO BE PROVIDED FOR ALL EXISTING AND PROPOSED DRAINAGE STRUCTURES WITHIN THE PROJECT LIMITS.
9. CONSTRUCTION STAGING AND PHASING SHALL OCCUR, WHERE APPLICABLE, TO MINIMIZE SOIL DISTURBANCE TIME.
10. BEST MANAGEMENT PRACTICES (BMPs) SHALL BE ADJUSTED AS NEEDED TO MEET ANY OTHER UNFORESEEN CONDITIONS.
11. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR INSTALLING A MUD TRACKING PAD/WASHING PAD AT THE CONSTRUCTION ENTRANCES TO MINIMIZE MUD DETACHMENT FROM TRUCK TIRES. 1-1/2 INCH SCREENED ROCK TO BE PLACED ON MIRAFI 140-N FILTER FABRIC. ADDITIONAL CLEAN GRAVEL TO BE ADDED THROUGHOUT THE DURATION OF CONSTRUCTION AS NEEDED.
12. CONTRACTOR SHALL ABIDE BY THE LOCAL, STATE AND FEDERAL JURISDICTIONS AND GOVERNING BODIES/AGENCIES CONSTRUCTION MANAGEMENT PLAN REQUIREMENTS.
13. RESEED AS INDICATED IN SEEDING NOTES.





**NIELSEN**  
landscape architects


357 cypress drive, 10  
tequesta, fl 33469  
561.402.9414

www.nielsenlandarch.com

917 N.E. 8TH AVE. GARDEN

917 N.E. 8TH AVENUE | DELRAY BEACH, FLORIDA 33483

SEAL (S TYLER NIELSEN - LA6667067)



07.01.2022

GENERAL SITE NOTES	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2

L001



CONTRACTOR QUALIFICATIONS

- CONTRACTOR MUST BE A LICENSED LANDSCAPE CONTRACTOR.
- CONTRACTOR MUST HAVE A MINIMUM OF 10 YEARS OF PROVEN EXPERIENCE RELOCATING LARGE SPECIMEN TREES AND PALMS IN SOUTH FLORIDA.
- CONTRACTOR MUST HAVE PROVEN EXPERIENCE RELOCATING TREES AND PALMS OF THE SAME SPECIES AND SIZE AS THOSE TO BE RELOCATED FOR THE CURRENT PROJECT.
- CONTRACTOR MUST HAVE A CERTIFIED ARBORIST ON STAFF

CONTRACTOR REQUIREMENTS

- CONTRACTOR MUST VISIT THE JOBSITE AND INSPECT ALL TREES AND PALMS TO BE RELOCATED AS WELL AS EXISTING SITE CONDITIONS AND RESTRICTIONS PRIOR TO PREPARING BID.
- CONTRACTOR MUST VERIFY AND ENSURE THAT ALL TREES AND PALMS IDENTIFIED ON THE PLANS AND THOSE TAGGED ON THE JOBSITE CORRESPOND AS TO NUMBER AND DESCRIPTION. ANY DISCREPANCIES MUST BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT IMMEDIATELY, PRIOR TO PREPARING BID.
- CONTRACTOR MUST CONDUCT ALL WORK ASSOCIATED WITH RELOCATION AND MAINTENANCE OF TREES AND PALMS TO BE RELOCATED. NO WORK IS TO BE SUBCONTRACTED WITHOUT PRIOR WRITTEN CONSENT OF THE OWNER AND/OR LANDSCAPE ARCHITECT.
- CONTRACTOR MUST DESIGNATE A COMPETENT, ENGLISH-SPEAKING SUPERVISOR OR FOREMAN OVERSEE AND DIRECT ALL RELOCATION AND MAINTENANCE ACTIVITIES AS OUTLINED IN THESE SPECIFICATIONS.
- CONTRACTOR MUST SCHEDULE ROOT PRUNING TO PROVIDE THE MAXIMUM POSSIBLE TIME FOR NEW ROOT GROWTH. EVEN TREES AND PALMS THAT TYPICALLY DO NOT REQUIRE LONG (OR ANY) ROOT PRUNING WILL BENEFIT FROM MORE ROOT PRUNING TIME; THEREFORE, ALL TREES AND PALMS TO BE RELOCATED MUST BE ROOT PRUNED. CONTRACTOR MUST PROVIDE A ROOT PRUNE SCHEDULE FOR EACH TREE OR PALM TO BE RELOCATED AS AN ATTACHMENT TO THE BID.
- CONTRACTOR MUST CALL SUNSHINE 811 TO HAVE ALL UNDERGROUND UTILITIES LOCATED UNDER OR IN THE VICINITY OF THE CURRENT OF FUTURE LOCATIONS OF ALL TREES AND PALMS TO BE RELOCATED PRIOR TO WORK COMMENCING.
- CONTRACTOR MUST VERIFY WITH THE GENERAL CONTRACTOR THE ABSENCE OF ANY UNDERGROUND CONSTRUCTION OR OBSTRUCTIONS (E.G., BULKHEADS, SEPTIC SYSTEMS, ETC.) IN THE CURRENT AND FUTURE LOCATIONS OF ALL TREES AND PALMS TO BE RELOCATED.
- CONTRACTOR MUST ALERT THE LANDSCAPE ARCHITECT OF ANY TREES OR PALMS THAT WILL NOT SUCCESSFULLY RELOCATE DUE TO POOR HEALTH PRIOR TO BEGINNING ROOT PRUNING.
- CONTRACTOR MUST FLAG ALL PROPOSED TRANSPLANT LOCATION FOR THE LANDSCAPE ARCHITECT'S APPROVAL A MINIMUM OF 15 DAYS PRIOR TO RELOCATION.
- CONTRACTOR MUST ENSURE THAT ALL TREES AND PALMS TO BE RELOCATED ARE INSTALLED AT THE CORRECT GRADE OR ELEVATION, ACCORDING TO THE GRADING PLAN.
- CONTRACTOR MUST BE ENSURE THAT ALL ROOT FLARES ARE EXPOSED AFTER RELOCATION.
- CONTRACTOR MUST REMOVE ALL RESIDUAL ROOTS, STUMPS, AND PORTIONS THEREOF AND BACKFILL PITS FROM WHICH RELOCATED TREES AND PALMS WERE REMOVED WITH CLEAN FILL FLUSH WITH THE SURROUNDING GRADE.
- CONTRACTOR MUST BE REPAIR ANY DAMAGE TO OTHER PLANTS, LAWN, HARDSCAPES, OR NEW CONSTRUCTION WITHIN THE RELOCATION AREA AT CONTRACTOR'S EXPENSE. HARDSCAPES INCLUDE BUT ARE NOT LIMITED TO CURBS, WALKS, ROADS, FENCES, SITE FURNISHINGS, ETC.
- CONTRACTOR MUST PHOTOGRAPHICALLY DOCUMENT NEW ROOT GROWTH FOLLOWING EACH ROOT PRUNE AND SUBMIT THIS DOCUMENTATION TO THE LANDSCAPE ARCHITECT. THE PURPOSE OF THIS REQUIREMENT IS TO ENSURE THAT SUFFICIENT ROOT GROWTH HAS OCCURRED PRIOR TO THE SECOND AND SUBSEQUENT ROOT PRUNES AND FOLLOWING THE FINAL ROOT PRUNE PRIOR TO RELOCATION.
- CONTRACTOR MUST INSTALL AND MAINTAIN PROTECTION FENCING AROUND EACH TREE AND PALM TO BE RELOCATED BOTH DURING ROOT PRUNING AND AFTER RELOCATION. PROTECTION FENCING MUST CONSIST OF GALVANIZED WELDED WIRE FABRIC OR PLASTIC MESH ATTACHED TO 4" X 4" POSTS INSERTED AROUND THE PERIMETER OF THE DRIPLINE OF THE TREE OR PALM. PROTECTION FENCING MUST BE PLUMB, TAUT, AND STURDY AT ALL TIMES AND MUST REMAIN IN PLACE THROUGHOUT THE ROOT PRUNING AND WARRANTY PERIODS, OR AS DIRECTED BY THE LANDSCAPE ARCHITECT.
- CONTRACTOR MUST OBTAIN ALL NECESSARY OR REQUIRED PERMITS FOR THE RELOCATION AND TRANSPORTATION OF THE TREES AND PALMS TO BE RELOCATED.
- CONTRACTOR MUST GUARANTEE ALL RELOCATED TREES AND PALMS FOR ONE YEAR FROM THE DATE OF RELOCATION TO THE FINAL LOCATION. GUARANTEE MUST INCLUDE TREE HEALTH AND SETTLING.
- CONTRACTOR MUST PROVIDE ALL MATERIAL NECESSARY TO PERFORM THE WORK COVERED HEREIN, INCLUDING BUT NOT LIMITED TO BACKFILL MATERIAL, PROTECTION FENCING, FLAGGING, ADDITIVES AND SUPPLEMENTS, TEMPORARY IRRIGATION, BURLAP, WIRE, SHRINK WRAP, AND ALL NECESSARY TOOLS AND EQUIPMENT.

TREE ROOT PRUNING SPECIFICATIONS

- ALL TREES AND PALMS TO BE RELOCATED MUST BE WATERED DAILY FOR AT LEAST 2-3 DAYS PRIOR TO ANY ROOTS BEING CUT TO ENSURE THAT THEY ARE FULLY HYDRATED. EACH WATERING MUST THOROUGHLY SATURATE THE ROOTBALL TO ITS FULL DEPTH.
- EACH TREE AND PALMS MUST THEN BE WATERED EVERY OTHER DAY, NOT RELYING ON RAIN, DURING THE ENTIRE ROOT PRUNING PROCESS EITHER BY A TEMPORARY IRRIGATION SYSTEM OR BY HAND. EACH WATERING MUST THOROUGHLY SATURATE THE ROOTBALL TO ITS FULL DEPTH.
- TREE AND PALM RELOCATION ACTIVITIES MUST BE SCHEDULED SO THAT REMOVAL AND REPLANTING TAKE PLACE IN THE SAME 24-HOUR PERIOD. NO TREES OR PALMS MAY BE "STOCKPILED" ONSITE OR OFFSITE FOR ANY PERIOD OF TIME WITHOUT PRIOR WRITTEN APPROVAL OF THE LANDSCAPE ARCHITECT. WHEN ALLOWED, APPROVAL FOR THE METHOD OF "STOCKPIILING" MUST BE OBTAINED FROM THE LANDSCAPE ARCHITECT.
- ALL DIGGING IN THE ROOT ZONE DURING THE ROOT PRUNE PROCESS MUST BE DONE BY HAND; NO MACHINERY WILL BE ALLOWED. PRUNING OF ROOTS MUST BE DONE BY HAND WITH CLEAN, SHARP TOOLS. DO NOT PAINT CUT ROOTS WITH TREE PAINT OR ANY KIND OF SEALANT.
- MYCORRHIZA (ROOTS® TRANSPLANT OR EQUIVALENT) MUST BE INCORPORATED INTO THE BACKFILL SOIL PRIOR TO BACKFILLING AS PER MANUFACTURER'S RECOMMENDATIONS.
- AFTER EACH ROOT PRUNE, EACH SECTION OF ROOTBALL THAT IS PRUNED MUST BE WRAPPED WITH BLACK PLASTIC AND THE TRENCH BACKFILLED WITH ORIGINAL EXCAVATED SOIL. A TREE RING WITH A MINIMUM HEIGHT OF 6" MUST BE CONSTRUCTED 6-12" OUTSIDE THE OUTERMOST EDGE OF THE ROOTBALL AND AROUND THE ENTIRE PERIMETER OF THE ROOTBALL TO DIRECT IRRIGATION WATER AND ANY ADDED SUPPLEMENTS DOWN INTO THE ROOTBALL DURING ROOT REGENERATION.
- ONCE THE TREE RING IS CONSTRUCTED AFTER EACH ROOT PRUNE, A HIGH-PHOSPHORUS ROOT STIMULANT MUST BE LIBERALLY APPLIED TO THE SURFACE OF THE ROOTBALL AND THOROUGHLY WATERED IN TO ENCOURAGE NEW ROOT GROWTH.
- PRIOR TO ANY ROOTS BEING CUT, ALL MAJOR ROOTS MUST BE IDENTIFIED TO DETERMINE THE ROOTBALL DIAMETER BASED ON THE RELATIVE LOCATION AND SIZE OF THE ROOTS.
- MANY TREE RELOCATION SPECIFICATIONS USE "GENERAL RULES" TO CALCULATE MINIMUM ROOTBALL DIAMETER, SUCH AS MULTIPLYING THE DIAMETER AT BREAST HEIGHT (DBH) OF THE TREE BY A FACTOR OF 10 OR ALLOWING A MINIMUM OF 9"-12" OF ROOTBALL FOR EVERY 1" OF TREE CALIPER. OTHERS LIST UNREALISTIC MINIMUM SIZES FOR THE ROOTBALLS OF VARIOUS TREE CALIPERS OR OTHERS LIST UNREALISTIC MINIMUM SIZES FOR THE ROOTBALLS OF VARIOUS TREE CALIPERS OR HEIGHTS. IN MANY CASES, SUCH APPROACHES RESULT IN ROOTBALLS THAT ARE EITHER TOO LARGE OR TOO SMALL FOR A GIVEN TREE. THE FOLLOWING TABLE LIST MINIMUM ROOTBALL DIAMETERS BASED ON REAL-WORLD EXPERIENCE OF TREE RELOCATION SPECIALISTS IN SOUTH FLORIDA.

.CALIPER (inches)	MIN. ROOTBALL DIA. (feet)	CALIPER (inches)	MIN. ROOTBALL DIA. (feet)
1-4	3	12-14	8
4-5	4	15-17	10
6-7	5	18-24	12-15
8-9	6	25-30	15-25
10-11	7	30+	as needed

- WHENEVER POSSIBLE, ROOTBALLS MUST BE CIRCULAR IN SHAPE WITH AN EQUAL DISTANCE FROM THE TRUNK TO THE EDGE OF ROOTBALL ALL AROUND.
- MINIMUM ROOTBALL DEPTH MUST BE 24"-36" FOR ALL TREES TO BE RELOCATED, WITH THE ACTUAL DEPTH TO BE DETERMINED ONLY AFTER A THOROUGH EXAMINATION OF ALL ROOTS DURING THE INITIAL ROOT INSPECTION AND BASED ON THE ABSENCE OF MAJOR ROOTS AT THE BOTTOM OF THE ROOTBALL. ROOTBALLS DEEPER THAN 36" MAY BE REQUIRED FOR LARGE SPECIMEN TREES, DEPENDING ON THE RELATIVE LOCATIONS AND DEPTHS OF THE MAJOR ROOTS AS OBSERVED DURING THE INITIAL ROOT INSPECTION.
- AS A GENERAL RULE, MINIMUM ROOT PRUNE TIME FOR TREES WITH A DBH OF LESS THAN 10" IS 12 WEEKS. THE FIRST ROOT PRUNE MUST BE ON TWO OPPOSING SIDES OF THE ROOTBALL, WITH THE SECOND ROOT PRUNE ON ONE OF THE OTHER TWO SIDES DONE A MINIMUM OF 6 WEEKS LATER, AND A THIRD ROOT PRUNE ON THE LAST SIDE DONE A MINIMUM OF 3 WEEKS AFTER THAT. THE SECOND AND THIRD ROOT PRUNES MAY ONLY BE DONE WHEN HEALTHY NEW ROOT GROWTH FROM EARLIER ROOT PRUNES IS EVIDENT (SEE SECTION 2.14 ABOVE FOR SPECIFICATIONS ON PHOTOGRAPHICALLY DOCUMENTING NEW ROOT GROWTH DURING THE ROOT PRUNE PROCESS). MORE TIME MAY BE NEEDED DURING THE COOLER MONTHS OF THE YEAR.
- AS A GENERAL RULE, MINIMUM ROOT PRUNE TIME FOR TREES WITH A DBH OF 10" OR GREATER IS 24 WEEKS. THE FIRST ROOT PRUNE MUST BE ON TWO OPPOSING SIDES OF THE ROOTBALL, WITH THE SECOND ROOT PRUNE ON ONE OF THE OTHER TWO SIDES DONE A MINIMUM OF 12 WEEKS LATER, AND A THIRD ROOT PRUNE ON THE LAST SIDE DONE A MINIMUM OF 6 WEEKS AFTER THAT. THE SECOND AND THIRD ROOT PRUNES MAY ONLY BE DONE WHEN HEALTHY NEW ROOT GROWTH FROM EARLIER ROOT PRUNES IS EVIDENT (SEE SECTION 2.14 ABOVE FOR SPECIFICATIONS ON PHOTOGRAPHICALLY DOCUMENTING NEW ROOT GROWTH DURING THE ROOT PRUNE PROCESS). MORE TIME MAY BE NEEDED DURING THE COOLER MONTHS OF THE YEAR.
- CERTAIN HARDWOOD TREES AND GYMNOSPERMS REQUIRE LONGER ROOT PRUNING TIMES. THESE INCLUDE, BUT ARE NOT LIMITED TO, THE FOLLOWING:
  - AVOCADO (PERSEA AMERICANA)
  - BLACK OLIVE (BUCIDA BUCERAS)
  - BRIDALVEIL (CAESALPINIA GRANADILLO)
  - CASSIAS (ALL SPECIES OF CASSIA)
  - LIGNUM VITAE (GUA/ACUM SANCTUM & G. OFFICINALE)
  - PODOCARPUS (PODOCARPUS SP.)
  - LIVE OAK (QUERCUS VIRGINIANA)
  - MAHOGANY (SWIETENIA MAHAGONI)
  - MANGO (MANGIFERA INDICA)

PALM ROOT PRUNING SPECIFICATIONS

- THE FOLLOWING TABLE LISTS MINIMUM ROOTBALL DIAMETERS FOR VARIOUS SPECIES OF PALMS BASED ON REAL-WORLD EXPERIENCE OF RELOCATION SPECIALISTS IN SOUTH FLORIDA.

PALM SPECIES	ROOTBALL SPECIFICATIONS
SABAL/CABBAGE PALM	36" diameter
QUEEN & FOXTAIL PALMS	12" from trunk in all directions
ROYAL & COCONUT PALMS	18-24" from trunk in all directions
CANARY DATE PALM	24" from trunk in all directions
SLOW-GROWING PALMS	24" from trunk in all directions

- PALM ROOTBALL MUST BE A MINIMUM OF 24" DEEP, WHENEVER POSSIBLE, ROOTBALLS MUST BE CIRCULAR IN SHAPE WITH AN EQUAL DISTANCE FROM THE TRUNK TO THE EDGE OF THE ROOTBALL ALL AROUND.
- AS A GENERAL RULE, MINIMUM ROOT PRUNE TIME FOR PALMS IS 6-8 WEEKS. THE FIRST ROOT PRUNE MUST BE ON TWO OPPOSING SIDES OF THE ROOTBALL, WITH THE SECOND ROOT PRUNE ON ONE OF THE OTHER TWO SIDES DONE A MINIMUM OF 3-4 WEEKS LATER, AND A THIRD ROOT PRUNE ON THE LAST SIDE DONE A MINIMUM OF 4.5-6 WEEKS AFTER THAT. THE SECOND AND THIRD ROOT PRUNES MAY ONLY BE DONE WHEN HEALTHY NEW ROOT GROWTH FROM EARLIER ROOT PRUNES IS EVIDENT (SEE SECTION 2.14 ABOVE FOR SPECIFICATIONS ON PHOTOGRAPHICALLY DOCUMENTING NEW ROOT GROWTH DURING THE ROOT PRUNE PROCESS). MORE TIME MAY BE NEEDED DURING THE COOLER MONTHS OF THE YEAR.
- CERTAIN PALMS, IN PARTICULAR THOSE THAT ARE SLOW GROWING, REQUIRE LONGER ROOT PRUNING TIME. THESE INCLUDE, BUT ARE NOT LIMITED TO, THE FOLLOWING.

- ALL SPECIES OF ARCHONTOPHOENIX
- ALL SPECIES OF CORYPHA
- AMERICAN OIL PALMS (ALL SPECIES OF ATTALEA)
- BISMARCK PALM (BISMARCKIA NOBILIS)
- CUBAN & CARIBBEAN COPERNICIA
- CUBAN BELLY PALM (GASTROCOCOS CRISPA)
- GINGERBREAD/DOUM PALMS (ALL SPECIES OF HYPHAENE)
- PALMYRA PALMS (ALL SPECIES OF BORASSUS)
- SATAKE PALM (SATAKENTIA LIUKIUENSIS)
- SAW PALMETTO (SERENOA REPENS)
- SILVER PALM (COCOTHRIXINAX ARGENTATA)
- ZOMBIE PALM (ZOMBIA ANTILLARUM)

FOR THESE PALMS, THE MINIMUM ROOT PRUNING TIME IS 4-6 MONTHS OR GREATER. ONLY WHEN SUFFICIENT NEW ROOT GROWTH HAS TAKEN PLACE FOLLOWING AN EARLIER ROOT PRUNE CAN THE NEXT ROOT PRUNE BE DONE, AND ONLY WHEN SUFFICIENT NEW ROOT GROWTH HAS TAKEN PLACE FOLLOWING THE FINAL ROOT PRUNE MAY THE TREE BE RELOCATED (SEE SECTION 2.14 ABOVE FOR SPECIFICATIONS ON PHOTOGRAPHICALLY DOCUMENTING NEW ROOT GROWTH DURING THE ROOT PRUNE PROCESS).

TREE CANOPY PRUNING SPECIFICATIONS

- PRIOR TO RELOCATION, THE CANOPY OF EACH TREE TO BE RELOCATED MUST BE SELECTIVELY PRUNED TO REMOVE CROSSING DEAD, DISEASED, BROKEN, AND LOW HANGING BRANCHES THAT MAY INTERFERE WITH CONSTRUCTION ACTIVITIES, OR THAT MAY INTERFERE OR RESTRICT STRAPPING OR LIFTING THE TREE DURING RELOCATION.
- FOR TREES BEING RELOCATED ONSITE, THE CANOPY MAY BE SELECTIVELY THINNED AND REDUCED BY NO MORE THAN 1/3 OF THE OVERALL CANOPY MASS, AT THE DIRECTION OF THE LANDSCAPE ARCHITECT; HOWEVER, THE BASIC SHAPE, FORM, AND CHARACTER OF THE TREES MUST BE PRESERVED.
- FOR TREES BEING RELOCATED OFFSITE, THE CANOPY MUST BE PRUNED, AT THE DIRECTIONS OF THE LANDSCAPE ARCHITECT, TO FIT ON THE TRAILER FOR TRANSPORT. EVERY EFFORT MUST BE MADE TO RETAIN AS MANY BRANCHES AS POSSIBLE. TO THE WIDEST LOAD WIDTH ALLOWABLE BY THE FLORIDA DEPARTMENT OF TRANSPORTATION. CONTRACTOR MUST OBTAIN ALL NECESSARY PERMITS AND ESCORTS TO TRANSPORT WIDE LOADS, PER FLORIDA LAW.
- ALL CANOPY PRUNING MUST BE CONDUCTED FOLLOWING ANSI A-300 TREE PRUNING STANDARDS AND BEST MANAGEMENT PRACTICES.
- ALL DEBRIS GENERATED DURING CANOPY PRUNING MUST BE REMOVED OFFSITE AND DISPOSED.

PALM CANOPY PRUNING SPECIFICATIONS

- IT IS WELL KNOW THAT SOME PALMS SURVIVE RELOCATION BETTER WHEN ALL OF THE LEAVES ARE REMOVED (E.G., CABBAGE PALM, SABAL PALMETTO), AND THAT OTHER PALMS BENEFIT FROM HAVING THEIR LEAVES CUT IN HALF DURING RELOCATION (E.G., COCONUT PALM, COCOS NUCIFERA). BOTH OF THESE HORTICULTURAL PRACTICES, WHILE TRUE, ARE ONLY APPLICABLE WHEN PALMS ARE NOT ROOT PRUNED. LEAVES DO NOT NEED TO BE CUT IN HALF OR REMOVED FROM PALMS THAT ARE ADEQUATELY ROOT PRUNED. ON OCCASION WHEN SUFFICIENT ROOT PRUNING TIME IS NOT AVAILABLE, PALMS TO BE RELOCATED MAY HAVE THEIR LEAVES CUT IN HALF OR REMOVED ENTIRELY AT THE DIRECTION OF THE LANDSCAPE ARCHITECT.
- PALMS LEAVES MUST BE TIED UP WITH 2-PLY BIODEGRADABLE TWINE PRIOR TO RELOCATION TO PREVENT MECHANICAL DAMAGE DURING THE RELOCATION PROCESS.
- PALM TRUNKS SHALL ONLY BE 'CLEANED UP' ACCORDING TO THE LANDSCAPE ARCHITECT'S SPECIFICATIONS SPECIFIC TO EACH PALM.



917 N.E. 8TH AVE. GARDEN

917 N.E. 8TH AVENUE | DELRAY BEACH, FLORIDA 33483

SEAL (S TYLER NIELSEN - LA6667067)



07.01.2022

TREE DISPOSITION NOTES	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2

L100

TREES PROTECTION NOTES

- CONTRACTOR TO PROTECT ALL EXISTING TREES PRIOR TO THE DEMOLITION OF THE EXISTING STRUCTURE.
- UPON COMPLETION OF OF SITE DEMOLITION, CONTRACTOR TO RELOCATE ALL SPECIFIED TREES AND PALMS FOR RELOCATION. CONTRACTOR TO REINSTALL TREE PROTECTION FENCE AROUND RELOCATED AND EXISTING TREES.
- FENCING AT A MINIMUM FOUR (4) FEET HEIGHT INSTALLED NO CLOSER TO THE TREE TRUNK THAN ITS DRIPLINE. THIS FENCE SHALL BE MAINTAINED IN WORKING ORDER DURING ALL PHASES OF CONSTRUCTION. MAINTAIN TREE PROTECTION ZONES FREE OF WEEDS AND TRASH.
- THE PROJECT LIMIT OF CONSTRUCTION AND ALL EXISTING VEGETATION TO REMAIN IS TO BE CLEARLY DEFINED BY STURDY, WEATHERPROOF FENCING AT A MINIMUM OF FOUR (4) FEET HIGH.
- STURDY TEMPORARY BARRIERS SHALL BE INSTALLED AROUND ALL TREE PROTECTION ZONES. BARRIERS SHALL BE A MINIMUM OF FOUR FEET HIGH, AND SHALL BE CONSTRUCTED OF CONTINUOUS CHAIN LINK FENCE WITH METAL POSTS AT EIGHT-FOOT SPACING, OR OF TWO-BY-FOUR INCH POSTS WITH THREE EQUALLY SPACED TWO-BY-FOUR RAILS. POSTS MAY BE SHIFTED TO AVOID ROOTS.

MAINTENANCE SPECIFICATIONS


- ALL RELOCATED TREES AND PALMS MUST BE MAINTAINED FOR ONE YEAR FROM THE DATE OF RELOCATION TO THEIR FINAL LOCATIONS.
- CONTRACTOR MUST MAINTAIN ALL RELOCATED TREES AND PALMS FOR ONE FULL YEAR FROM THE DATE OF RELOCATION TO THE FINAL LOCATION.
- WHENEVER POSSIBLE, EACH TREE AND PALM MUST BE WATERED BY A PERMANENT AUTOMATIC IRRIGATION SYSTEM FOLLOWING RELOCATION. EACH WATERING MUST THOROUGHLY SATURATE THE ROOTBALL TO ITS FULL DEPTH; THIS WILL REQUIRE 25-50 GALLONS OF WATER FOR SMALL TREES AND PALMS DEPENDING ON ROOTBALL SIZE, WHILE LARGE TREES WILL REQUIRE A MINIMUM OF 10 GALLONS PER FOOT OF ROOTBALL DIAMETER (I.E., A 10' DIAMETER ROOTBALL WILL REQUIRE A MINIMUM OF 100 GALLONS PER WATERING EVENT).WATERING FREQUENCY MUST BE EVERY DAY FOR THE FIRST TWO WEEKS, EVERY OTHER DAY FOR THE NEXT THREE WEEKS, AND EVERY THIRD DAY FOR THE NEXT 6-8 WEEKS.
- WHEN AN AUTOMATIC IRRIGATION SYSTEM IS NOT POSSIBLE, CONTRACTOR IS RESPONSIBLE FOR HAND WATERING RELOCATED TREES AND PALMS THROUGHOUT THE MAINTENANCE PERIOD AND UNTIL FINAL ACCEPTANCE BY THE LANDSCAPE ARCHITECT AND/OR CLIENT.
- IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION. A HIGH-PHOSPHORUS ROOT STIMULANT MUST BE APPLIED TO THE SURFACE OF THE ROOTBALL AT THE RECOMMENDED LABEL RATE AND WATERED IN WITH A DRENCH CONSISTING OF A SYSTEMIC INSECTICIDE AND A CONTACT ROOT ROT FUNGICIDE, FOLLOWING LABEL INSTRUCTIONS, AS INITIAL PREVENTATIVE MAINTENANCE.
- EVERY THREE MONTHS THEREAFTER, A HIGH-PHOSPHORUS ROOT STIMULANT MUST BE APPLIED TO THE SURFACE OF THE ROOTBALL AT THE RECOMMENDED LABEL RATE AND WATERED IN WITH A DRENCH CONSISTING OF A SYSTEMIC INSECTICIDE AND A BROAD-SPECTRUM SYSTEMIC FUNGICIDE, FOLLOWING LABEL INSTRUCTIONS, AS CONTINUING PREVENTATIVE MAINTENANCE.
- IRRIGATION AND BRACING MUST BE CHECKED AND EACH TREE OR PALM THOROUGHLY INSPECTED FOR SIGNS OF STRESS, DISEASE, OR PEST PROBLEMS ON A MONTHLY BASIS.
- IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION AND EVERY THREE MONTHS THEREAFTER, A HIGH-QUALITY, SLOW-RELEASE 15-2-15 GRANULAR FERTILIZER MUST BE APPLIED, AT THE RECOMMENDED LABEL RATE, SPREAD EVENLY ACROSS THE SURFACE OF THE ROOTBALL.
- IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION AND EVERY THREE MONTHS THEREAFTER A HIGH-QUALITY, SLOW-RELEASE 15-2-15 GRANULAR FERTILIZER MUST BE APPLIED, AT THE RECOMMENDED LABEL RATE, SPREAD EVENLY ACROSS THE SURFACE OF THE ROOTBALL.
- FOLIAR FEED FOUR TIMES PER YEAR.
- STRING MUST BE REMOVED FROM THE TIED UP LEAVES IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION IF THE PALM WAS ROOT PRUNED OR WITHIN 30-45 DAYS AFTER RELOCATION ON THE OCCASION THE LANDSCAPE ARCHITECT APPROVED RELOCATION WITHOUT ROOT PRUNING DUE TO TIME CONSTRAINTS.
- IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION AND EVERY THREE MONTHS THEREAFTER A HIGH-QUALITY, SLOW-RELEASE 8-4-12 GRANULAR PALM FERTILIZER WITH MINORS MUST BE APPLIED. AT THE RECOMMENDED LABEL RATE, SPREAD EVENLY ACROSS THE SURFACE OF THE ROOTBALL.
- FOLIAR FEED PALMS SIX TIMES PER YEAR.

RELOCATION SPECIFICATIONS

- LANDSCAPE CONTRACTOR TO FLAG ALL PROPOSED PLANT LOCATIONS FOR LANDSCAPE ARCHITECT'S APPROVAL PRIOR TO INSTALLATION. NOTIFY LANDSCAPE ARCHITECT A MINIMUM OF 15 DAYS PRIOR TO REVIEW.
- ALL TREES AND PALMS TO BE RELOCATED MUST BE WATERED DAILY FOR AT LEAST 5 DAYS PRIOR TO ANY RELOCATION TO ENSURE THAT THEY ARE FULLY HYDRATED. EACH WATERING MUST THOROUGHLY SATURATE THE ROOTBALL TO ITS FULL DEPTH.
- ALL ROOTBALLS MUST BE WRAPPED IN BURLAP AND THE TIGHTLY WIRE-WRAPPED (USING REDLINE HORSE WIRE OR EQUIVALENT) TO KEEP THE ENTIRE ROOTBALL INTACT DURING RELOCATION. TREES AND PALMS GROWING IN LIMESTONE MUST BE DUG AND RELOCATED WITH THE ROOT ATTACHED TO A SECTION OF ROCK AS PART OF THE ROOTBALL SUCH THAT THE ROOTS REMAIN INTACT, ROOTBALLS COMING FROM SAND OR SANDY SOIL MAY ALSO NEED TO BE BOXED PRIOR TO RELOCATION, AT THE DISCRETION OF THE LANDSCAPE ARCHITECT.
- TREES AND PALMS BEING RELOCATED OFFSITE MUST HAVE THEIR ENTIRE ROOTBALLS THOROUGHLY AND TIGHTLY WRAPPED WITH PLASTIC SHRINK WRAP ON THE OUTSIDE OF THE WIRE WRAP, AND THE ENTIRE TREE OR PALM (INCLUDING CANOPY, TRUNK, AND ROOTBALL) MUST BE COVERED WITH A BREATHABLE TARP (E.G., SHADE CLOTH) DURING TRANSPORT.
- NEW PLANTING PITS FOR RELOCATED TREES AND PALMS MUST BE PREPARED PRIOR TO LIFTING THE PALM OR TREE FROM ITS CURRENT LOCATION AND MUST BE AT LEAST 3-4 FEET WIDER THAN THE ROOTBALL AND THE SAME DEPTH AS THE ROOTBALL, SUCH THAT THE FINAL ELEVATION OF THE TOP OF THE ROOTBALL IS AT OR SLIGHTLY ABOVE (NO MORE THAN 2" HIGHER) FINAL GRADE.
- TREES AND PALMS TO BE RELOCATED MUST BE LIFTED BY THE ROOTBALL ONLY, USING APPROPRIATELY SIZED (LENGTH AND STRENGTH) LIFTING STRAPS OR CHAINS. DURING LIFTING, THE TREE OR PALM MUST BE BALANCED IN A MORE-OR-LESS UPRIGHT POSITION, WITH THE STRAP THE TRUNK USED ONLY FOR BALANCING AND MANEUVERING THE TREE OR PALM INTO A POSITION. NO CHAINS MAY BE USED AROUND OR AGAINST THE TRUNK AT ANY TIME. AT NO TIME SHALL 100% OF THE WEIGHT OF THE TREE OR PALM BE ON THE STRAP ATTACHED TO THE TRUNK. TRUNKS MUST BE HEAVILY PADDED WITH 30-60 LAYERS (DEPENDING ON SIZE AND WEIGHT) OF BURLAP BENEATH THE BALANCING STRAP.
- TREES AND PALMS MUST BE LIFTED WITH A CRANE OR BACKHOE APPROPRIATELY SIZED FOR THE SIZE AND WEIGHT OF THE TREE OR PALM AND LIFTED OR CARRIED DIRECTLY TO THE FINAL INSTALL LOCATION OR TRANSPORT TRAILER.
- ONCE LIFTING BEINGS, ANY UNCUT ROOTS UNDER OR AROUND THE ROOTBALL THAT MAY YET REMAIN MUST BE IMMEDIATELY SEVERED WITH HAND PRUNING TOOLS TO MINIMIZE TEARING AND ROOT DAMAGE.
- AGRIFORM PLANTING TABLETS (OR APPROVED EQUIVALENT) MUST BE EVENLY DISTRIBUTED AROUND THE PERIMETER OF THE PLANTING PIT AT THE RATE OF 2 TABLETS PER 1" TRUNK CALIPER PRIOR TO BACKFILLING.
- MYCORRHIZA (ROOTS® TRANSPLANT OR EQUIVALENT) MUST BE INCORPORATED INTO THE BACKFILL SOIL PRIOR TO BACKFILLING.
- RELOCATED TREES AND PALMS MUST BE CENTERED IN THE PLANTING PIT, AND THE PIT BACKFILLED USING A 1:1 MIXTURE OF EXISTING SOIL AND 80:20 (DOT SAND:MUCK) SOIL MIX THOROUGHLY BLENDED TOGETHER. DO NOT USE MUDDY SOIL AS BACKFILL.
- SMALL TREES AND PALMS MUST BE FIRMLY BRACED USING A MINIMUM OF FOUR 4"X 4" WOODEN BRACES ATTACHED TO 2" X 4" WOODEN BATTENS HELD IN PLACE WITH TWO STEEL BANDS. LARGER TREES MAY REQUIRE 6"X 6" WOODEN POSTS OR EVEN TELEPHONE POLES TO PROVIDE SUFFICIENT BRACING STRENGTH TO PREVENT TOPPLING DURING WIND EVENTS. A SUFFICIENT NUMBER OF BATTENS MUST BE STRATEGICALLY PLACED AROUND THE TRUNK SUCH THAT THE STEEL BANDS NEVER CONTACT THE TRUNK. NO BURLAP IS TO REMAIN UNDER THE WOODEN BATTENS ON TREES DURING BRACING, BUT SEVERAL LAYERS OF BURLAP SHOULD BE LEFT UNDER THE WOODEN BATTENS WHEN BRACING PALMS. NAILS SHALL NEVER BE DRIVEN DIRECTLY INTO THE TRUNK DURING BRACING. BRACING MUST REMAIN IN PLACE FOR A MINIMUM OF ONE YEAR.
- A TREE RING WITH A MINIMUM HEIGHT OF 6" MUST BE CONSTRUCTED 6-12" OUTSIDE THE OUTERMOST EDGE OF THE ROOTBALL AND AROUND THE ENTIRE PERIMETER OF THE ROOTBALL TO DIRECT IRRIGATION WATER AND ANY SUPPLEMENTS THAT ARE ADDED DOWN INTO THE ROOTBALL DURING ROOT REGENERATION.
- ONCE THE TREE RING IS CONSTRUCTED, A HIGH-PHOSPHORUS ROOT STIMULANT MUST BE LIBERALLY APPLIED TO THE SURFACE AND THOROUGHLY WATERED IN.
- ROOTBALLS MUST BE A THOROUGHLY WATERED IN USING A HOSE AND JOHNSON BAR INSERTED TO THE VERY BOTTOM OF THE ROOTBALL AND SWUNG BACK AND FORTH TO PREVENT FORMATION OF AIR POCKETS. THE JOHNSON BAR TECHNIQUE MUST BE REPEATED AT LEAST ONCE MORE WITHIN 6" OF THE TRUNK. MULCH MUST NOT BE APPLIED OR ALLOWED TO ACCUMULATE DIRECTLY AGAINST THE TRUNK.
- ORGANIC MULCH (MELALEUCA IS PREFERRED) MUST BE APPLIED WITHIN 48 HOURS OF RELOCATION AT A DEPTH OF 3-4" OVER THE ENTIRE TOP OF THE ROOTBALL FROM THE TREE RING TO WITHIN 6" OF THE TRUNK. MULCH MUST NOT BE APPLIED OR ALLOWED TO ACCUMULATE DIRECTLY AGAINST THE TRUNK.
- PITS FROM WHICH THE RELOCATED TREES AND PALMS WERE REMOVED MUST BE CLEANED OFF ALL RESIDUAL ROOTS, STUMPS, AND PORTIONS THEREOF AND BACKFILLED WITH CLEAN FILL FLUSH WITH THE SURROUNDING GRADE.
- RESTORE THE SURFACE WITH MATERIAL TO MATCH ADJACENT AREAS, MATERIAL TO BE APPROVED BY LANDSCAPE ARCHITECT. CONTRACTOR TO PROVIDE A MINIMUM OF ONE YEAR WARRANTY ON SETTLING AND PLANT MATERIAL FROM THE SUBSTANTIAL COMPLETION.
- MULTI-TRUNK TREES AND PALMS MUST BE RELOCATED AS ONE UNIT WITH A SINGLE ROOTBALL.
- PLANTING PITS FOR EDIBLE DATE PALMS (PHOENIX DACTYLIFERA) MUST BE BACKFILLED WITH PURE DOT SILICA SAND.

WARRANTY NOTES


- ALL RELOCATED TREES AND PALMS MUST BE GUARANTEED FOR ONE YEAR FROM THE DATE OF RELOCATION TO THEIR FINAL LOCATIONS.
- IF A TREE OR PALM DIES WITHIN THE 1-YEAR WARRANTY PERIOD, IT MUST BE REMOVED AND REPLACED AT CONTRACTOR'S EXPENSE.
- IF A TREE OR PALM PERFORMS POORLY WITHIN THE 1-YEAR WARRANTY PERIOD, IT MUST BE REMOVED AND REPLACED AT CONTRACTOR'S EXPENSE. THE DECISION TO REPLACE BASED ON POOR HEALTH IS AT THE DISCRETION OF THE LANDSCAPE ARCHITECT.
- IF A TREE OR PALM SETTLES TO AN UNHEALTHY DEPTH WITHIN THE 1-YEAR WARRANTY PERIOD, AS DEEMED BY THE BY THE LANDSCAPE ARCHITECT, IT MUST BE RAISED TO THE CORRECT GRADE AT CONTRACTOR'S EXPENSE.



917 N.E. 8TH AVE. GARDEN

917 N.E. 8TH AVENUE | DELRAY BEACH, FLORIDA 33483

SEAL (S TYLER NIELSEN - LA6667067)




07.01.2022

TREE DISPOSITION NOTES	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2

L101





TREE DISPOSITION SCHEDULE

Project Address: 917 NE 8TH AVE.							Parcel ID (12434609160040080):
Removal							
Tree #	Common Name	Scientific Name	Height	Spread	DBH	Condition Rating < 50%	Comments
NA	NA	NA	NA	NA	NA		
						Condition Rating ≥ 50%	
2	FRANGIPANI	PLUMERIA OBTUSA	20	18	11	90%	
6	ROYAL POINCIANA	DELONIX REGIA	30	65	24	80%	
7	JACARANDA	JACARANDA MIMOSIFOLIA	30	55	20	60%	
10	LOQUAT	ERIOBOTRYA JAPONICA	25	20	6	75%	
11	MANGO	MANGIFERA INDICA	35	30	13	80%	
12	MANGO	MANGIFERA INDICA	35	50	32	80%	

Trees with Condition Rating < 50% to be Removed: 0 Trees  
Total DBHs of Trees with Condition Rating ≥ 50% to be Removed: 106 DBH inches (6 TREES REMOVED)

Palm #	Common Name	Scientific Name	Height	Spread	Clear Trunk	Condition Rating < 50%	Comments
16	COCONUT PALM	COCOS NUCIFERA	28		3	22	35%
						Condition Rating ≥ 50%	
1	COCONUT PALM	COCOS NUCIFERA	20	16	10	90%	
3	CHRISTMAS PALM (2X)	ADONIDIA MERRILLII	20	8	12	80%	
4	QUEEN PALM	SYAGRUS ROMANZOFFIANUM	25	16	12	75%	
5	QUEEN PALM	SYAGRUS ROMANZOFFIANUM	30	16	24	75%	
8	CHRISTMAS PALM (3X)	ADONIDIA MERRILLII	20	6	12	75%	
9	COCONUT PALM	COCOS NUCIFERA	20	18	10	80%	
13	COCONUT PALM	COCOS NUCIFERA	25	16	12	60%	
14	COCONUT PALM	COCOS NUCIFERA	25	22	4	90%	
15	COCONUT PALM	COCOS NUCIFERA	35	20	25	80%	
17	CABBAGE PALM	SABAL PALMETTO	30	10	22	80%	

Total Numbers of Palms with Condition Rating < 50% to be Removed: 1 Palm  
Total Heights of Palms with Condition Rating ≥ 50% to be Removed: 250 feet in height (11 PALMS REMOVED)

MITIGATION CALCULATIONS

Mitigation		
Tree Replacement Calculations*		
New Trees	Caliper (CAL)	Calipers Provided
15 of Tabebuia Bahamensis	15 X 4 inch CAL	60
12 of Caesalpinia Granadillo	12 X 4 inch CAL	48

Replacement for Trees (Removed, Condition Rating ≥ 50%): 108 CAL (27 Trees)  
Replacement for Tree-for-Tree basis: 0 Trees

Palm Replacement Calculations **		
New Palms	Overall Height	Clear Trunk
9 of Thrinax Radiata	16 x 9 = 144	8 x 9 = 72
10 of Thrinax Radiata	17 x 10 = 170	9 x 10 = 90
10 of Thrinax Radiata	18 x 10 = 180	10 x 10 = 100

Replacement for Palms (Removed, Condition Rating ≥ 50%): 494 total heights (29 Palms)  
Replacement for Palm-for-Palm basis: 0 Palms

Requirements of Vegetation Removal (Sec. 4.6.19 (E)(5))

\* **TREE**  
\*Staff recommends at least 4" CAL trees for mitigation as required.  
Trees with condition rating of ≥ 50%: Total DBHs of trees shall be replaced with equivalent # of CAL inches of replacement trees.  
Trees with condition rating of < 50%: Required to be mitigated on a tree-for-tree basis (16' OH X 6' 5T X 8' CT X 7' SPR for others & 12' OH for SF & Duplex)  
  
\*\* **Palm**  
Palms with condition rating of ≥ 50%: Replaced with one palm of equal overall heights (OH) or 16 ft OH, whichever is greater  
Palms with condition rating of < 50%: Required to be mitigated on a palm-for-palm basis (16' OH X 8 CT for others & 12' OH X 6' CT for SF & Duplex)

In Lieu Fee for TREE (Sec. 4.6.19.(E)(5)(d))

DBH 0 to 8"	\$450
DBH 9" to 12"	\$650
DBH 13" to 18"	\$850
DBH 19" and greater	\$1,000

Example: In-lieu-fee for a 21" DBH tree: (\$450 x 8") + (\$650 x 4") + (\$850 x 6") + (\$1,000 x 3") = \$3,600 + \$2,600 + \$5,100 + \$3,000 = \$14,300

For trees with a condition rating of between 25 percent and 50 percent, the in-lieu fee shall be calculated at 50 percent of the above escalating scale.


In-lieu-fee for a palm: \$75 per one foot grey trunk or clear trunk

MITIGATION NOTE

THE 11 PALMS & 6 TREE PROPOSED FOR REMOVAL ON-SITE WILL BE MITIGATED WITH 21 NEW PALMS & 27 NEW TREES.



REFERENCE IMAGERY




SEAL (S TYLER NIELSEN - LA6667067)









TREE REFERENCE IMAGES	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2






TREE DISPOSITION LEGEND

-  PALM TO BE REMOVED
-  TREE TO BE REMOVED
-  PALM TO BE RELOCATED
-  TREE TO BE RELOCATED
-  PALM TO BE PRESERVED
-  TREE TO BE PRESERVED

917 N.E. 8TH AVE. GARDEN

917 N.E. 8TH AVENUE | DELRAY BEACH, FLORIDA 33483

SEAL (S TYLER NIELSEN - LA6667067)




07.01.2022

TREE DISPOSITION SCHEDULE


#	BOTANICAL NAME	ACTION
1	COCOS NUCIFERA	REMOVE
2	PLUMERIA OBTUSA	REMOVE
3	ADONIDIA MERRILLII	REMOVE
4	SYAGRUS ROMANZOFFIANUM	REMOVE
5	SYAGRUS ROMANZOFFIANUM	REMOVE
6	DELONIX REGIA	REMOVE
7	JACARANDA MIMOSIFOLIA	REMOVE
8	ADONIDIA MERRILLII	REMOVE
9	COCOS NUCIFERA	REMOVE
10	ERIOBOTRYA JAPONICA	REMOVE
11	MANGIFERA INDICA	REMOVE
12	MANGIFERA INDICA	REMOVE
13	COCOS NUCIFERA	REMOVE
14	COCOS NUCIFERA	REMOVE
15	COCOS NUCIFERA	REMOVE
16	COCOS NUCIFERA	REMOVE
17	SABAL PALMETTO	REMOVE

TREE DISPOSITION PLAN

DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2



L104



MATERIALS NOTES

1. CONTRACTOR TO VERIFY ALL QUANTITIES. IN CASE OF ANY DISCREPANCIES, GRAPHICALLY SHOWN MATERIAL QUANTITIES SHALL TAKE PRECEDENCE.
2. ALL CONSTRUCTION AND MATERIALS NOT SPECIFICALLY ADDRESSED IN THE CONTRACT DOCUMENTS OR SPECIFICATIONS SHALL BE IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL JURISDICTIONS AND GOVERNING BODIES/AGENCIES STANDARDS.
3. THE CONTRACTOR SHALL PROVIDE A FULL-SCALE MOCKUP AND RECEIVE APPROVAL FROM THE LANDSCAPE ARCHITECT FOR ALL SYSTEMS BEFORE BEGINNING CONSTRUCTION OF PAVEMENT.
4. EXPANSION JOINTS SHALL BE PROVIDED WHERE FLATWORK MEETS VERTICAL STRUCTURES, SUCH AS WALLS, CURBS, STEPS, AND OTHER HARDSCAPE ELEMENTS. EXPANSION JOINTS SHALL ALSO BE PROVIDED AT MATERIAL CHANGES. EXPANSION JOINT MATERIALS/METHODS SHALL BE SUBMITTED TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.
5. CONTROL JOINTS SHOULD BE SPACED NO GREATER THAN TEN (10) LINEAR FEET MAXIMUM, UNLESS OTHERWISE SPECIFIED. EXPANSION JOINTS SHOULD BE SPACED NO GREATER THAN FORTY (40) LINEAR FEET MAXIMUM, UNLESS OTHERWISE SPECIFIED. CONTRACTOR SHALL ADVISE ON OTHER JOINTS AS NEEDED TO MINIMIZE CRACKING. THIS INFORMATION SHALL BE SUBMITTED TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.
6. CONTROL JOINTS SHALL BE PROVIDED AS SPECIFIED IN THE CONTRACT DOCUMENTS. CONTROL JOINT MATERIALS, METHODS AND RECOMMENDATIONS ON ADDITIONAL CONTROL JOINTS TO MINIMIZE CRACKING SHALL BE SUBMITTED TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL.
7. ALL STEPS SHALL HAVE TWELVE (12) INCH TREADS AND SIX (6) INCH RISERS, UNLESS OTHERWISE SPECIFIED.
8. HOLD TOP OF WALLS AND FENCES LEVEL, UNLESS OTHERWISE SPECIFIED.
9. CONTRACTOR SHALL NOT INSTALL WORK LOCATED ON TOP OF ARCHITECTURAL STRUCTURES WITHOUT FIRST REVIEWING ARCHITECTURAL DRAWINGS.
10. SAMPLES OF SPECIFIED MATERIALS SHALL BE SUBMITTED TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO ORDERING FOR JOB.


MATERIALS LEGEND

- PLANTING AREA TYPICAL
- ZOYSIA SOD
- BASALT PAVERS W/ GRAVEL JOINTS
- DOMINICAN CORAL STONE FLAGGING
- WATER

SEAL (S TYLER NIELSEN - LA6667067)




MATERIALS PLAN	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2



L300








917 N.E. 8TH AVE. GARDEN

917 N.E. 8TH AVENUE | DELRAY BEACH, FLORIDA 33483

SEAL (S TYLER NIELSEN - LA6667067)




07.01.2022

LAYOUT NOTES

- LAYOUT AND VERIFY DIMENSIONS PRIOR TO CONSTRUCTION. NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES. LANDSCAPE ARCHITECT TO REVIEW AND APPROVE ALL LAYOUTS CONTAINED IN THE CONSTRUCTION DOCUMENTS PRIOR TO CONSTRUCTION.
- WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. DO NOT SCALE DIMENSIONS FROM REDUCED DRAWINGS.
- DIMENSIONS REFERRED TO AS "EQUAL" INDICATE SPACING WHICH IS EQUIDISTANT MEASURED TO THE CENTERLINES.
- MEASUREMENTS ARE TO THE FINISHED FACE OF BUILDINGS, WALLS, OR OTHER FIXED SITE IMPROVEMENTS. DIMENSIONS TO CENTERLINES ARE IDENTIFIED AS SUCH.
- INSTALL INTERSECTING ELEMENTS AT 90-DEGREE ANGLES, UNLESS OTHERWISE INDICATED. MAINTAIN HORIZONTAL ALIGNMENT OF ADJACENT ELEMENTS AS INDICATED IN CONTRACT DOCUMENTS.
- SPECIAL CONSIDERATION IS GIVEN TO THE DESIGN AND INTENDED RELATIONSHIP BETWEEN ARCHITECTURE, PLANTING AREAS AND PAVING SYSTEMS. PAVEMENT JOINTING, PAVERS, STONE, FINISHES AND GRADES HAVE BEEN STRICTLY COORDINATED IN THE CONTRACT DOCUMENTS. CONSTRUCTION OF THESE SYSTEMS SHALL BE STRICTLY COORDINATED.

LAYOUT PLAN

DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2



L500



PLANTING NOTES

1. PLANT MATERIAL IS TO BE HEALTHY SPECIMENS FREE FROM DISEASE OR DAMAGE, AND IS TO BE MAINTAINED IN EXCELLENT CONDITION WHILE ON THE JOBSITE. LANDSCAPE ARCHITECT SHALL INSPECT PLANT MATERIAL UPON ARRIVAL TO JOBSITE AND WILL REJECT PLANT MATERIAL THAT DOES NOT MEET THE STANDARDS DESCRIBED WITHIN THE CONTRACT DOCUMENTS.
2. THE LANDSCAPE ARCHITECT WILL PERIODICALLY INSPECT PLANT MATERIAL STOCKPILED AND/OR PLANTED ON SITE DURING THE COURSE OF CONSTRUCTION. PLANT MATERIAL NOT MEETING THE STANDARDS CONTAINED WITHIN CONTRACT DOCUMENTS SHALL BE REPLACED AT NO COST TO THE OWNER.
3. PROVIDE MATCHING SIZES AND FORMS FOR EACH PLANT OF THE SAME SPECIES UNLESS OTHERWISE INDICATED.
4. CONTRACTOR TO VERIFY ALL QUANTITIES. IN CASE OF DISCREPANCIES, GRAPHICALLY SHOWN QUANTITIES SHALL TAKE PRECEDENCE.
5. ALL MATERIALS USED SHALL CONFORM TO THE GUIDELINES ESTABLISHED BY THE CURRENT AMERICAN STANDARDS FOR NURSERY STOCK, PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
6. ALL PLANT MATERIAL SHALL BE INSTALLED PLUMB AND PER THE SPECIFICATIONS CONTAINED WITHIN THE CONTRACT DOCUMENTS. ANY NECESSARY STAKING AND/OR OTHER SUPPORTS MATERIALS/METHODS SHALL BE SUBMITTED TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.
7. THE CONTRACTOR SHALL PRUNE EXISTING AND/OR NEW TREES ONLY PER LANDSCAPE ARCHITECT DIRECTION.
8. THE CONTRACTOR SHALL STAKE THE LOCATIONS OF ALL TREES AND B&B SHRUBS FOR LANDSCAPE ARCHITECT REVIEW AND APPROVAL, PRIOR TO INSTALLATION.
9. ALL ROOT-WRAPPING MATERIALS THAT ARE NOT BIO-DEGRADABLE SHALL BE REMOVED FROM THE ROOT BALL. ROOT BALLS SHALL BE FREE OF WEEDS.
10. SPECIFIED PLANT MATERIAL SIZES SHALL BE CONSIDERED MINIMUM SIZES.
11. FINISH GRADE OF PLANTING BEDS SHALL BE ONE (1) INCH BELOW ADJACENT FLATWORK, UNLESS SPECIFIED OTHERWISE.
12. MULCH OR PLANTING BED DRESSING SHALL BE PLACED IN ALL PLANTING AREAS AS SPECIFIED. MULCH OR PLANTING BED DRESSING SHALL NOT BE PLACED WITHIN SIX (6) INCHES OF TREE TRUNKS. MULCHING SHOULD BE REPEATED ANNUALLY DURING THE AUTUMN TO A THREE (3) INCH DEPTH.
13. ALL PLANT MATERIAL SHOULD RECEIVE AN ORGANIC FERTILIZER IN LIMITED APPLICATION FOLLOWING INSTALLATION. TYPE AND APPLICATION RATE AND METHOD OF APPLICATION TO BE SPECIFIED BY THE CONTRACTOR AND APPROVED BY THE LANDSCAPE ARCHITECT.
14. EXCESS FERTILIZER SHALL BE DISPOSED OF PROPERLY OFF-SITE. IT SHALL NOT BE DISPOSED OF IN STORM DRAINS AND/OR DRYWELLS.
15. STOCKPILED PLANT MATERIAL TO BE PLACED IN THE SHADE AND PROPERLY HAND-WATERED UNTIL PLANTED.
16. MINI-NUGGET TYPE DECORATIVE BARK MULCH WILL BE USED TO RETURN NUTRIENTS TO THE SOIL, REDUCE MAINTENANCE AND MINIMIZE EVAPORATION FOR AREAS APPROXIMATE TO THE RESIDENCE. LARGER SHREDDED BARK MULCH WILL BE USED FOR STEEP AREAS SO SLOUGHING IS LESS LIKELY TO OCCUR.
17. PRESERVE & PROTECT ALL EXISTING VEGETATION INDICATED TO REMAIN AT ALL TIMES.
18. ALL VEGETATION PROPOSED FOR OUTSIDE THE BUILDING ENVELOPE TO BE NATIVE UNLESS OTHERWISE NOTED. PLANTING THAT OCCURS OUTSIDE THE BUILDING ENVELOPE IS FOR RESTORATION PURPOSES ONLY OR IS SPECIFIC TO UTILITIES RESTORATION.
19. SIX (6) INCH PLANT MIX SHALL BE PROVIDED FOR ALL LAWN, TURF, AND NATIVE PLANTING ZONES. 18 INCH PLANT MIX SHALL BE PROVIDED FOR ALL PERENNIAL PLANTING BEDS UNLESS OTHERWISE NOTED.
20. ALL PLANT MATERIAL SHALL BE FLORIDA GRADE #1 OR BETTER AS OUTLINED IN GRADES AND STANDARDS FOR NURSERY PLANTS, PARTS I AND II OF THE LATEST EDITION, PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTRE AND CONSUMER SERVICES.

PLANTING SCHEDULE (PLEASE SEE CHART BELOW FOR FOUNDATION LANDSCAPE QUANTITIES)

ABR.	QUANTITY	BOTANICAL NAME	COMMON NAME	SPECIFICATIONS	NATIVE	REQUIRED / ORNAMENTAL
TREES						
TBA	15	TABEBUIA BAHAMENSIS	DWARF WHITE TRUMPET	FG./ 16 FT. HT./ 4 IN. DBH/ 8 FT. CT./ 6 FT. SINGLE STRAIGHT TRUNK/ 7 FT. SP.	YES	(10) REQUIRED / (5) ORNAMENTAL
PRA	2	PIMENTA RACEMOSA	BAY RUM TREE	100 GAL./ 4 IN. DBH./ 16 FT. HT./ 8 FT. CT./ 6 FT. SINGLE STRAIGHT TRUNK/ 7 FT. SP.	NO	REQUIRED
GLU	12	GYMNANTHES LUCIDA	CRABWOOD TREE	100 GAL./ 4 IN. DBH./ 16 FT. HT./ 8 FT. CT./ 6 FT. SINGLE STRAIGHT TRUNK/ 7 FT. SP.	YES	(2) REQUIRED / (10) ORNAMENTAL
PALMS						
TRA	24	THRINAX RADIATA	FLORIDA THATCH PALM	FG. 8-10 FT. CT. STAGGERED HTS. (16 FT. MIN. OA. HT.) (8 FT. MIN. CT.)	YES	(5) REQUIRED / (11) ORNAMENTAL
UNDERSTORY TREES & SHRUBS						
GL	61	GYMNANTHES LUCIDA	CRABWOOD	25 GAL. 8 FT. HT.	YES	(27) REQUIRED / (34) ORNAMENTAL
GL2	61	GYMNANTHES LUCIDA	CRABWOOD	3 GAL. TO BE PLACED BETWEEN 25 GAL. SHRUBS (MIN. 2 FT. HT.)	YES	(27) REQUIRED / (34) ORNAMENTAL
PL	126	PSYCHOTRIA LIGUSTRIFOLIA	BAHAMA WILD COFFEE	7 GAL. (MIN. 2 FT. HT.)	YES	(30) REQUIRED / (96) ORNAMENTAL
ACCENTS						
ZP	111	ZAMIA PUMILA	COONTIE	7 GAL.	YES	(37) REQUIRED / (74) ORNAMENTAL
GROUNDCOVERS						
MS	635	MICROSORUM SCOLOPENDRIUM	WART FERN	3 GAL. 18 IN. O.C.	NO	(195) REQUIRED / (440) ORNAMENTAL
SI	190	MISCANTHUS SINENSIS	CHINESE SILVERGRASS	3 GAL. 24 IN. O.C.	NO	(55) REQUIRED / (135) ORNAMENTAL
MISC.						
ALL SOD AREAS TO BE REPLACED WITH ZOYSIA 'ZEON'						
LANDSCAPE ARCHITECT TO HAVE \$2000 WHOLESALE ACCENT PLANT ALLOWANCE						

MITIGATION TREES

MITIGATION TREES

MITIGATION PALMS

FOUNDATION LANDSCAPE SCHEDULE

ABR.	QUANTITY	BOTANICAL NAME	COMMON NAME	SPECIFICATIONS	NATIVE	REQUIRED / ORNAMENTAL
PALMS						
TRA	5	THRINAX RADIATA	FLORIDA THATCH PALM	FG. 8-10 FT. CT. STAGGERED HTS. (16 FT. MIN. OA. HT.) (8 FT. MIN. CT.)	YES	REQUIRED
UNDERSTORY TREES & SHRUBS						
PL	8	PSYCHOTRIA LIGUSTRIFOLIA	BAHAMA WILD COFFEE	7 GAL. (MIN. 2 FT. HT.)	YES	REQUIRED
ACCENTS						
ZP	7	ZAMIA PUMILA	COONTIE	7 GAL.	YES	REQUIRED
GROUNDCOVERS						
SI	60	MISCANTHUS SINENSIS	CHINESE SILVERGRASS	3 GAL. 24 IN. O.C.	NO	REQUIRED

MITIGATION PALMS

PLANT REFERENCE IMAGES



TABEBUIA BAHAMENSIS



QUERCUS VIRGINIANA



GYMNANTHES LUCIDA



THRINAX RADIATA



GYMNANTHES LUCIDA



PIMENTA RACEMOSA



PSYCHOTRIA LIGUSTRIFOLIA




ZAMIA PUMILA



MICROSORUM SCOLOPENDRIUM




MISCANTHUS SINENSIS



PLANTING SCHEDULE & NOTES	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2





FOUNDATION LANDSCAPE SCHEDULE (REFER TO SHEETS L701 & L702 FOR PLANT LOCATIONS)						
ABR.	QUANTITY	BOTANICAL NAME	COMMON NAME	SPECIFICATIONS	NATIVE	REQUIRED / ORNAMENTAL
<b>PALMS</b>						
TRA	5	THRINAX RADIATA	FLORIDA THATCH PALM	FG. 8-10 FT. CT. STAGGERED HTS. (16 FT. MIN. OA. HT.) (8 FT. MIN. CT.)	YES	REQUIRED
<b>UNDERSTORY TREES &amp; SHRUBS</b>						
PL	8	PSYCHOTRIA LIGUSTRIFOLIA	BAHAMA WILD COFFEE	7 GAL. (MIN. 2 FT. HT.)	YES	REQUIRED
<b>ACCENTS</b>						
ZP	7	ZAMIA PUMILA	COONTIE	7 GAL.	YES	REQUIRED
<b>GROUNDCOVERS</b>						
SI	60	MISCANTHUS SINENSIS	CHINESE SILVERGRASS	3 GAL. 24 IN. O.C.	NO	REQUIRED

**NOTE:**

---

ANY TREES OR SHRUBS PLACED WITHIN WATER, SEWER OR DRAINAGE EASEMENTS SHALL CONFORM TO THE CITY OF DELRAY BEACH STANDARD DETAILS; LD1.1 & LD 1.2. (REFER TO DETAILS 3 & 4 ON SHEET L704)




917 N.E. 8TH AVE. GARDEN



LANDSCAPE CALCULATIONS/ FOUNDATION PLANTING SCHEDULE	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2






LANDSCAPE REQUIREMENTS	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2

Landscape Requirements				
Multiple Family, Commercial, and Industrial Development				
Color-coded or hatched diagram demonstrating requirements listed in this Table, as applicable, should be provided for verification.				
Interior Landscaping LDR Sec. 4.6.16.(H)(3)(g) & (h)	Required:	186 sq.ft. 2 Trees	# (quantity) & List of Trees/Palms	# (quantity) & List of shrubs for hedge
	Provided:	208 sq.ft. 2 Trees & 4 Palms	<ul style="list-style-type: none"><li>2 Bay Rum Tree</li><li>4 Florida Thatch Palm</li></ul>	<ul style="list-style-type: none"><li>55 Chinese Silvergrass</li><li>3 Coontie</li></ul>
Landscape Strip LDR Sec. 4.6.16(H)(3)(a)	Required:	N/A	# (quantity) & List of Trees/Palms	# (quantity) & List of shrubs for hedge
	Provided:	N/A	<ul style="list-style-type: none"><li>N/A</li></ul>	<ul style="list-style-type: none"><li>N/A</li></ul>
Landscape Barrier LDR Sec. 4.6.16(H)(3)(d)	Required:	50 l.f. (25 ft. each side) / 30 = 2 trees	# (quantity) & List of Trees/Palms:	# (quantity) & List of shrubs for hedge
	Provided:	2 Trees & 2 Palms & 16 Shrubs	<ul style="list-style-type: none"><li>2 Florida Thatch Palm</li><li>2 Bay Rum Tree</li></ul>	<ul style="list-style-type: none"><li>16 Bahama Wild Coffee</li></ul>
Foundation Landscaping LDR Sec. 4.6.16 (H)(4)	Required:	70 l.f.	# (quantity) & List of Trees/Palms:	# (quantity) & List of shrubs and/or ground covers
	Provided:	75 l.f. 5 Palms	<ul style="list-style-type: none"><li>5 Florida Thatch Palm</li></ul>	<ul style="list-style-type: none"><li>8 Bahama Wild Coffee</li><li>7 Coontie</li><li>60 Chinese Silvergrass</li></ul>
Street Trees LDR Sec. 4.6.16. (H)(6)	Required:	99.8 l.f. 3 Trees	# (quantity) & List of Trees:	
	Provided:	0 Trees (Please see waiver request)	<ul style="list-style-type: none"><li>N/A (Please see waiver request for street trees)</li></ul>	
Landscape Screening Provided	Required:	N/A	# (quantity) & List of Trees/Palms	# (quantity) & List of shrubs and/or ground covers
	Provided:	99.8 l.f. 10 Trees & 3 Palms & 68 shrubs	<ul style="list-style-type: none"><li>8 Dwarf White Trumpet</li><li>3 Florida Thatch Palm</li></ul>	<ul style="list-style-type: none"><li>54 Crabwood</li><li>14 Bahama Wild Coffee</li><li>34 Coontie</li><li>195 Wart Fern</li></ul>
Landscape Island and strip for parking lot LDR Sec. 4.6.16(H)(3)(i), (j), (k)	N/A landscape islands  One shade tree, a minimum of 135 sq.ft. of planting area, at least 9 ft wd, not including a curb	N/A Trees	# (quantity) & List of Trees: <ul style="list-style-type: none"><li>N/A</li></ul>	





TREES ALONG PROPERTY LINE

REFER TO FLORIDA NATIVE PLANT SOCIETY : <https://www.fnps.org/plant/gymnanthes-lucida>

*Gymnanthes lucida*



© Shirley Denton

Photographs belong to the photographers who allow use for FNPS purposes only. Please contact the photographer for all other uses.

Crabwood, Oysterwood

Euphorbiaceae

Also known as *Ateramnus lucida*


Plant Specifics

- Form: Tree
- Size: 10-25 (30) ft
- Life Span: Long-lived perennial
- Flower Color: Yellowish-green (not showy)
- Fruit Color: Black-brown capsules
- Phenology: Evergreen. Bloms year round with a peak in spring-summer. Wind pollinate
- Noted for: Interesting foliage

Landscaping

Recommended Uses: Small tree with shiny foliage. New leaves are reddish. Columnar growt form. Suited to planting near structures and a good background plant f urban yards.

PLANTING LEGEND




NOTE:

ANY TREES OR SHRUBS PLACED WITHIN WATER, SEWER OR DRAINAGE EASEMENTS SHALL CONFORM TO THE CITY OF DELRAY BEACH STANDARD DETAILS; LD1.1 & LD 1.2. (REFER TO DETAILS 3 & 4 ON SHEET L704)

PLANTING SCHEDULE


ABR.	QUANTITY	BOTANICAL NAME
TREES		
TBA	15	TABEBUIA BAHAMENSIS
PRA	2	PIMENTA RACEMOSA
GLU	12	GYMNANTHES LUCIDA
PALMS		
TRA	24	THRINAX RADIATA

SEAL (S TYLER NIELSEN - LA6667067)




07.01.2022

TREE & PALM PLANTING PLAN	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2







PLANTING LEGEND

- PROPOSED PALM
- PROPOSED TREE
- FOUNDATION LANDSCAPING
- PROPOSED GROUNDCOVER
- PROPOSED SHRUB / ACCENT

NOTE:


ANY TREES OR SHRUBS PLACED WITHIN WATER, SEWER OR DRAINAGE EASEMENTS SHALL CONFORM TO THE CITY OF DELRAY BEACH STANDARD DETAILS; LD1.1 & LD 1.2. (REFER TO DETAILS 3 & 4 ON SHEET L704)

PLANTING SCHEDULE


ABR.	QUANTITY	BOTANICAL NAME
UNDERSTORY TREES & SHRUBS		
GL	61	GYMNANTHES LUCIDA
GL2	61	GYMNANTHES LUCIDA
PL	126	PSYCHOTRIA LIGUSTRIFOLIA
ACCENTS		
ZP	111	ZAMIA PUMILA
GROUNDCOVERS		
MS	635	MICROSORUM SCOLOPENDRIUM
SI	190	MISCANTHUS SINENSIS




UNDERSTORY PLANTING PLAN	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2









1 PALM PLANTING AND STAKING DETAIL  
SCALE: 3/32" = 1'- 0"




2 UNDERSTORY TREE PLANTING AND STAKING DETAIL  
SCALE: 3/32" = 1'- 0"




3 SHRUB PLANTING DETAIL  
SCALE: 3/32" = 1'- 0"



4 TREE PLANTING AND STAKING DETAIL  
SCALE: 3/32" = 1'- 0"



5 GROUND COVER PLANTING DETAIL  
SCALE: 3/32" = 1'- 0"



6 PLANT & SHRUB SPACING DETAIL  
SCALE: 3/32" = 1'- 0"






PLANTING DETAILS	
DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2

SCALE AS NOTED:


L704




- NOTE**
1. TO BE USED WHERE TYPICAL WOOD STAKING IS NOT APPLICABLE.
  2. FOR PURCHASE INFORMATION REFER TO WEBSITE:  
<http://www.earthanchor.com/duckbill/what-is-duckbill/applications/horticulture/>

1 PALM (DUCK BILL STAKING) DETAIL


Scale: 3/32" = 1'- 0"



Drive anchors in a triangular pattern in bottom of hole until only the D-rings remain exposed




Pass tension straps through D-ring in each anchor, and back to easy hand ratchet. Tighten and adjust tension strap for best fit. Retighten if necessary.



- NOTE**
1. EXISTING NATIVE SOIL WITHIN ALL LANDSCAPE ISLANDS, INTERIOR LANDSCAPE STRIPS AND PERIMETER LANDSCAPE STRIPS, ADJACENT TO VEHICULAR USE AREAS, SHALL BE EXCAVATED DOWN TO A DEPTH OF THIRTY (30) INCHES BELOW EXISTING GRADE, EXCEPT FOR A 12" BUFFER FROM THE INSIDE OF CURB OR PAVEMENT.
  2. A SUITABLE PLANTING SOIL MIXTURE OF FIFTY/FIFTY (50/50), SIXTY/FORTY (60/40) (SAND/TOPSOIL) OR AS OTHERWISE INDICATED BY THE REGISTERED LANDSCAPE ARCHITECT, SHALL EITHER BE BACKFILLED IN PLACE OF THE NATIVE SOIL OR EFFICIENTLY MIXED WITH THE NATIVE SOIL TO CREATE AN OPTIMUM ENVIRONMENT FOR SUCCESSFUL ROOT DEVELOPMENT.
  3. IF NATIVE SOIL IS TO BE MIXED, IT SHALL FIRST BE SCREENED TO REMOVE ROCKS AND DEBRIS LARGER THAN ONE-HALF (1/2) INCH IN DIAMETER PRIOR TO MIXING.
  4. ALL PROPERTIES UNDER THIS SECTION SHALL BE REQUIRED TO HAVE AN OPEN LANDSCAPE BED INSPECTION PRIOR TO BACKFILLING TO INSURE THE (30) INCH DEPTH HAS BEEN MET. (CITY OF DELRAY BEACH AMD. ORD. 6-12 2/21/12)

2 EXCAVATION DETAIL


Scale: 3/32" = 1'- 0"



- NOTES:**
1. ALL ROOT BARRIERS SHALL BE 4' MINIMUM FROM ALL CITY FACILITIES.
  2. THE INSTALLATION OF ROOT BARRIERS SHALL BE COORDINATED WITH CITY AND INSPECTED BY CITY PRIOR TO BACKFILLING. ALL ROOT BARRIERS SHALL EXTEND UP TO FINISHED GRADE.
  3. ROOT BARRIERS SHALL BE MINIMUM 36" DEEP. APPROVED PRODUCTS INCLUDE "DEEP ROOT" AND "ROOT SOLUTIONS". FLEXIBLE BARRIERS SHALL BE 36" PANELS MANUFACTURED BY BIOBARRIER.
  4. ALL ROOT BARRIERS SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURERS WRITTEN INSTRUCTIONS.

3 TYPICAL TREE WITH ROOT BARRIER

Scale: 3/32" = 1'- 0"



- NOTES:**
1. THIS DISTANCE SHALL BE 10' MINIMUM FROM ALL CITY FACILITIES IF NO ROOT BARRIER IS USED.

4 TYPICAL TREE WITHOUT ROOT BARRIER

Scale: 3/32" = 1'- 0"



IRRIGATION NOTES






















1. THE PLANS AND DRAWINGS ARE DIAGRAMMATIC OF THE WORK TO BE PERFORMED. INSTALL THIS IRRIGATION SYSTEM PER THE SITE CONDITIONS AND AVAILABLE FLOW/PRESSURE. SOME COMPONENTS MAY BE SHOWN OUTSIDE THE WORK AREA FOR CLARITY. THE WORK SHALL BE EXECUTED IN A MANNER TO AVOID CONFLICTS WITH UTILITIES AND OTHER ELEMENTS OF CONSTRUCTION, INCLUDING LANDSCAPE MATERIALS. ALL DEVIATIONS FROM THE PLANS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE BEFORE BEING INSTALLED.
2. THE CONTRACTOR SHALL COMPLY WITH ALL CURRENT LOCAL CODES, ORDINANCES, AND REGULATIONS.
3. ALL IRRIGATION MAINLINE AND LATERAL LINES ARE TO NOT EXCEED A VELOCITY OF 5FPS.
4. THE CONTRACTOR SHALL NOT WILLFULLY INSTALL ANY ASPECT OF THE IRRIGATION SYSTEM AS SHOWN ON THE PLANS AND DRAWINGS. WHEN IT IS OBVIOUS IN THE FIELD THAT OBSTRUCTIONS, GRADE DIFFERENCES, OR DISCREPANCIES EXIST THAT MIGHT NOT HAVE BEEN KNOWN DURING THE DESIGN OF THE IRRIGATION SYSTEM, IN THE EVENT THAT NOTIFICATION OF THE CONFLICT IS NOT APPROVED BY THE OWNER'S REPRESENTATIVE, THE CONTRACTOR WILL ASSUME FULL RESPONSIBILITY FOR ALL REVISIONS.
5. REFER TO THE LANDSCAPE PLANS WHEN TRENCHING TO AVOID TREE ROOT BALLS WHEN INSTALLING IRRIGATION EQUIPMENT. CALL 811 AND REFER TO UTILITY PLANS PRIOR TO TRENCHING.
6. IRRIGATION CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS, INCLUDING UTILITY LOCATIONS BEFORE INSTALLATION OF THE IRRIGATION SYSTEM. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATING INSTALLATION WITH ALL OTHER CONSTRUCTION ON SITE. ESPECIALLY LANDSCAPE INSTALLATION, THE IRRIGATION SYSTEM SHALL BE RELOCATED AT NO ADDITIONAL COST FOR ANY CONFLICT WITH LANDSCAPE INSTALLATION OR ANY OTHER SITE CONSTRUCTION OR EXISTING CONDITIONS.
7. VERIFY THE MINIMUM STATIC WATER PRESSURE IS AVAILABLE AT THE PROJECT SITE PRIOR TO BEGINNING THE IRRIGATION INSTALLATION. NOTIFY THE IRRIGATION DESIGN CONSULTANT AND LANDSCAPE ARCHITECT IN WRITING IF THE MINIMUM STATIC WATER PRESSURE OR WATER VOLUME IS NOT AVAILABLE.
8. WHERE EXISTING OR NEW TREES, LIGHT FIXTURES, SIGNS, ELECTRONIC CONTROLLERS AND/OR OTHER OBJECTS ARE AN OBSTRUCTION TO AN IRRIGATION SPRINKLERS PATTERN, THE COMPONENT AND PIPING SHALL BE RELOCATED AS NECESSARY TO OBTAIN PROPER COVERAGE OF AN IRRIGATION SPRINKLERS PATTERN. THE COMPONENT AND PIPING SHALL BE RELOCATED AS NECESSARY TO OBTAIN THE PROPER COVERAGE WITHOUT DAMAGING THE OBSTRUCTION.
9. 100% HEAD TO HEAD COVERAGE IS REQUIRED. ASSURE THAT ANY MODIFIED SPACING DOES NOT EXCEED THE SPACING SHOWN IN THE PLANS.
11. IRRIGATION CONTRACTOR SHALL ADJUST ALL SPRINKLERS TO AVOID OVER SPRAY ONTO IMPERVIOUS AREAS.
12. ALL MATERIALS AND EQUIPMENT SHOWN SHALL BE NEW. IF THE DRAWINGS DO NOT THOROUGHLY DESCRIBE THE TECHNIQUES TO BE USED, THE INSTALLER SHALL FOLLOW THE INSTALLATION METHODS AND INSTRUCTIONS RECOMMENDED BY THE PRODUCT MANUFACTURER.
13. THE LOCATION OF THE IRRIGATION MAINLINE SHALL BE IDENTIFIED IN THE FIELD AND APPROVED BY THE OWNER'S REPRESENTATIVE BEFORE INSTALLATION.
14. CONTRACTOR IS TO SUBMIT PRODUCT SPECIFICATION SHEETS FOR ALL IRRIGATION EQUIPMENT TO BE USED FOR APPROVAL BY THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.
15. THE QUANTITIES SHOWN IN THE LEGEND SHEETS SHALL NOT BE USED FOR BIDDING PURPOSES. THE CONTRACTOR WILL BE RESPONSIBLE FOR CONDUCTING A COMPREHENSIVE MATERIALS TAKEOFF TO DETERMINE THE ACTUAL QUANTITIES OF MATERIAL NECESSARY TO EXECUTE THE WORK DESCRIBED IN THE DOCUMENTS.
16. ALL TRENCHES SHALL BE BACKFILLED WITH CLEAN DEBRIS-FREE MATERIALS.
17. IRRIGATION CONTRACTOR IS TO INSTALL CHRISTY ZONE TAGS WITH THE CORRESPONDING CONTROLLER ZONE NUMBER AT EACH CONTROL VALVE.
18. AS BUILT DOCUMENTS ARE TO BE PROVIDED TO THE OWNER UPON COMPLETION OF THE PROJECT. THE MAINLINE, CONTROL VALVES, ISOLATION VALVES, GROUND RODS AND SPLICE BOXES SHALL BE LOCATED WITH A MEASUREMENT FROM TWO FIXED POINTS.
19. IRRIGATION CONTRACTOR SHALL SECURE ANY AND ALL NECESSARY PERMITS FOR THE WORK PRIOR TO COMMENCEMENT OF ON-SITE OPERATIONS.
20. A MAINLINE PRESSURE TEST IS TO BE CONDUCTED BEFORE BACKFILLING. ALL FINDINGS ARE TO BE REPORTED TO THE LANDSCAPE ARCHITECT WITHIN TWENTY FOUR HOURS POST TEST.
21. ALL SLEEVES ARE TO BE TWO TIMES THE SIZE OF THE PIPE. COORDINATE ALL SLEEVES WITH THE APPROPRIATE CONTRACTOR PRIOR TO CONSTRUCTION. NOT ALL NECESSARY VERTICAL SLEEVES MAY BE SHOWN ON THESE PLANS. FIELD VERIFY. ALL SLEEVE LOCATIONS ARE TO BE APPROVED BY THE OWNER PRIOR TO CONSTRUCTION.
22. THE IRRIGATION INSTALLER IS TO INSTALL THIS SYSTEM PER THE AVAILABLE FLOW AND PRESSURE AT THE SITE. FIELD ADJUST AS NECESSARY.

VALVE SCHEDULE

NUMBER	MODEL	SIZE	TYPE	GPM	PRECIP
A1	RAIN BIRD XCZPGA-100-PRF	1"	AREA FOR DRIPLINE	4.89	1.44 in/h
A2	RAIN BIRD XCZPGA-100-PRF	1"	AREA FOR DRIPLINE	6.00	1.44 in/h
A3	RAIN BIRD XCZPGA-100-PRF	1"	AREA FOR DRIPLINE	9.76	1.43 in/h
A4	RAIN BIRD XCZPGA-100-PRF	1"	AREA FOR DRIPLINE	6.72	1.44 in/h
A5	RAIN BIRD PGA GLOBE	1"	TURF SPRAY	7.14	2.29 in/h
B1	RAIN BIRD PGA GLOBE	1"	TURF SPRAY	6.15	2.61 in/h
B2	RAIN BIRD XCZPGA-100-PRF	1"	AREA FOR DRIPLINE	8.93	1.45 in/h
B3	RAIN BIRD XCZPGA-100-PRF	1"	AREA FOR DRIPLINE	7.14	1.45 in/h
C1	RAIN BIRD PGA GLOBE	1"	TURF SPRAY	7.00	1.87 in/h
C2	RAIN BIRD XCZPGA-100-PRF	1"	AREA FOR DRIPLINE	9.93	1.44 in/h
C3	RAIN BIRD XCZPGA-100-PRF	1"	AREA FOR DRIPLINE	4.85	1.43 in/h
C4	RAIN BIRD XCZPGA-100-PRF	1"	AREA FOR DRIPLINE	5.06	1.44 in/h
C5	RAIN BIRD XCZPGA-100-PRF	1"	AREA FOR DRIPLINE	10.28	1.44 in/h


\*THE IRRIGATION CONTRACTOR IS TO SET THE RUN TIMES FOR EACH ZONE TO MATCH THE PLANT WATER REQUIREMENTS, PLANTER CAPACITIES, SITE CONDITIONS AND MICRO-CLIMATE FACTORS. SEE THE LANDSCAPE PLANS FOR PLANT SPECIFICATIONS.

IRRIGATION SCHEDULE

SYMBOL	MANUFACTURER/MODEL/DESCRIPTION	QTY	PSI
	RAIN BIRD 1806-U-PRS SQ SERIES TURF SPRAY 6" POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL, SIDE AND BOTTOM INLET. 1/2" NPT FEMALE THREADED INLET. PRESSURE REGULATING.	5	30
	RAIN BIRD 1806-U-PRS U8 SERIES TURF SPRAY 6" POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL, SIDE AND BOTTOM INLET. 1/2" NPT FEMALE THREADED INLET. PRESSURE REGULATING.	10	30
	RAIN BIRD 1806-U-PRS U15 SERIES TURF SPRAY 6" POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL, SIDE AND BOTTOM INLET. 1/2" NPT FEMALE THREADED INLET. PRESSURE REGULATING.	4	30
	RAIN BIRD 1806-U-PRS HE-VAN SERIES TURF SPRAY 6" POP-UP SPRINKLER WITH CO-MOLDED WIPER SEAL, SIDE AND BOTTOM INLET. 1/2" NPT FEMALE THREADED INLET. PRESSURE REGULATING.	16	30
	RAIN BIRD 1800-1400 FLOOD FIXED FLOW RATE (0.25-2.0GPM), FULL CIRCLE BUBBLER, 1/2" FIPT.	55	30
	RAIN BIRD XCZPGA-100-PRF MEDIUM FLOW, 3-15 GPM, WITH 1" PGA VALVE AND 1" PRESSURE REGULATING RBY FILTER AND 40PSI PRESSURE REGULATOR. IT IS 2 WIRE COMPATIBLE RESIDENTIAL CONTROL ZONE KIT.	10	
	AREA TO RECEIVE DRIPLINE RAIN BIRD XFS-CV-09-12 XFS-CV SUB-SURFACE AND ON-SURFACE LANDSCAPE DRIPLINE WITH A HEAVY-DUTY 4.3 PSI CHECK VALVE. 0.9 GPH EMITTERS AT 12" O.C. DRIPLINE LATERALS SPACED AT 12" APART, WITH EMITTERS OFFSET FOR TRIANGULAR PATTERN. SPECIFY XF INSERT FITTINGS.	2,840 L.F.	
	RAIN BIRD PGA GLOBE 1", 1-1/2", 2" ELECTRIC REMOTE CONTROL VALVE, GLOBE.	3	
	ZURN 720A 1" PRESSURE VACUUM BREAKER	1	
	ZURN 720A 1" PRESSURE VACUUM BREAKER	1	
	ZURN 720A 1" PRESSURE VACUUM BREAKER	1	
	RAIN BIRD TM2-6-120V 6 STATION 120V MODEL. SUITABLE FOR INDOOR OR OUTDOOR INSTALLATIONS FACTORY-INSTALLED OUTDOOR-RATED POWER CORD. LNK WIFI READY	1	
	RAIN BIRD TM2-6-120V 6 STATION 120V MODEL. SUITABLE FOR INDOOR OR OUTDOOR INSTALLATIONS FACTORY-INSTALLED OUTDOOR-RATED POWER CORD. LNK WIFI READY	1	
	RAIN BIRD TM2-6-120V 6 STATION 120V MODEL. SUITABLE FOR INDOOR OR OUTDOOR INSTALLATIONS FACTORY-INSTALLED OUTDOOR-RATED POWER CORD. LNK WIFI READY	1	
	HUNTER WRF-CLIK RAIN/FREEZE SENSOR, INSTALL WITHIN 1000 FT OF CONTROLLER, IN LINE OF SIGHT. 22-28 VAC/VDC 100 MA POWER FROM TIMER TRANSFORMER. MOUNT AS NOTED. INCLUDES GUTTER MOUNT.	3	
	POINT OF CONNECTION 1"	1	
	POINT OF CONNECTION 1"	1	
	POINT OF CONNECTION 1"	1	
	IRRIGATION LATERAL LINE: PVC CLASS 200 SDR 21	991.1 L.F.	
	IRRIGATION MAINLINE: PVC CLASS 200 SDR 21	316.4 L.F.	
	PIPE SLEEVE: PVC SCHEDULE 40	159.6 L.F.	




\*THE QUANTITIES SHOWN IN THE LEGEND SHEETS SHALL NOT BE USED FOR BIDDING PURPOSES. THE CONTRACTOR WILL BE RESPONSIBLE FOR CONDUCTING A COMPREHENSIVE MATERIALS TAKEOFF TO DETERMINE THE ACTUAL QUANTITIES OF MATERIAL NECESSARY TO EXECUTE THE WORK DESCRIBED IN THE DOCUMENTS.




1 GROUNDING ROD  
1" = 1'-0"

FX-IR-FX-AUXEQ-01




3 PIPE BENEATH PAVEMENT  
1" = 1'-0"

FX-IR-FX-AUXEQ-05




5 IRRIGATION TRENCHING  
1 1/2" = 1'-0"

FX-IR-FX-AUXEQ-08




2 WALL MOUNT CONTROLLER  
1" = 1'-0"

FX-IR-FX-CONT-06



4 SLEEVE AT ROAD  
1 1/2" = 1'-0"


FX-IR-FX-AUXEQ-15



DIRECTION OF FLOW

6 WILKINS MODEL 720A PRESSURE VACCUM BREAKER  
N.T.S

I-01





07.01.2022  
IRRIGATION NOTES,  
SCHEDULE & DETAILS

DATE	ISSUE
10.20.2021	50% CD
12.15.2021	COORDINATION
04.22.2022	TAC REVISION 1
07.01.2022	TAC REVISION 2















NOTE:

THE MAXIMUM FOOTCANDLE OF .25 AT EDGE OF PROPERTY WILL NOT BE EXCEEDED EXCEPT WHERE EFFECTED BY THE REQUIRED STREET LIGHTING.

LUMINAIRE SCHEDULE									
Symbol	Qty	Label	Arrangement	Manufacturer	Catalog Number	Mounting	LLF	Luminaire Lumens	Luminaire Watts
▼	2	SA	Single	Spring City Electrical	DLR-LE095-X2-40-CR3-GR18	15' POST TOP MOUNT A.F.G. (top of fixture)	1.000	9015	95
●	2	SB	Single	Lithonia Lighting	RADPT P1 30K SYM	15' POST TOP MOUNT A.F.G. (top of fixture)	0.903	3189	25.4134
■	26	SC	Single	Aurora Lighting	LMG1-90-30-18-***	18" SPIKE MOUNT A.F.G.	0.855	107	3.31
■	4	SW	Single	Lithonia Lighting	WDGE1 LED P1 30K 80CRI VW	9' WALL MOUNT A.F.F. (bottom of fixture)	0.855	1164	10.0002

CALCULATION SUMMARY							
Label	Calc Type	Units	Avg	Max	Min	Avg/Min	Max/Min
DRIVEWAYS	Illuminance	Fc	1.82	2.5	1.1	1.65	2.27
DRIVEWAYS (ROW)	Illuminance	Fc	2.55	3.3	1.6	1.59	2.06
PROERTY LINE EAST (HORIZ)	Illuminance	Fc	0.00	0.0	0.0	N.A.	N.A.
PROERTY LINE NORTH (HORIZ)	Illuminance	Fc	0.07	0.6	0.0	N.A.	N.A.
PROPERTY LINE EAST (VERT)	Illuminance	Fc	0.00	0.0	0.0	N.A.	N.A.
PROPERTY LINE NORTH (VERT)	Illuminance	Fc	0.14	1.0	0.0	N.A.	N.A.
PROPERTY LINE SOUTH (HORIZ)	Illuminance	Fc	0.06	0.6	0.0	N.A.	N.A.
PROPERTY LINE SOUTH (VERT)	Illuminance	Fc	0.12	0.9	0.0	N.A.	N.A.
SIDEWALKS NORTH	Illuminance	Fc	1.98	5.6	0.5	3.96	11.20
SIDEWALKS SOUTH	Illuminance	Fc	2.04	7.4	0.5	4.08	14.80
STREET	Illuminance	Fc	2.32	3.7	1.3	1.78	2.85



NOTE:

1. ALL MOUNTING HARDWARE SHALL BE STAINLESS STEEL.  
2. STREET LIGHT CIRCUITS SHALL BE WIRED AND METERED SEPARATELY FROM BUILDINGS.

**CITY of DELRAY BEACH**  
PUBLIC WORKS DEPARTMENT  
404 SOUTH HUNTON AVENUE, DELRAY BEACH, FLORIDA 33444

**SINGLE HEAD POLE ASSEMBLY**

**LMG1-90-30-18**  
**RT 31.0**

**aurora light.**

**LMG1-90 MAGLIO**

The LMG1-90 is a versatile high-quality, high-performance path light. The Maglio features a rotational plate shield, allowing you to seamlessly adjust the aperture from 180° to 0°. Also ideal for wall-washing applications. See LMG3 and LMG1-AF for additional size and wattage options.

**Features include:**

- 3 Watts
- Cree XLAMP® (XP-G) LED
- 2200K (80 & 90 CRI) or 3000K (80 CRI), or Amber 585nm
- Thermally Integrated® LED Module
- 12V Integral Driver, Dimmable to <10% typ.
- Compatible w/ 12V AC/DC ELV or MLV Transformers
- Solid Copper and Brass Construction

**INDEPENDENTLY ADJUSTABLE LIGHT SOURCE & SHIELD**

**COPPER CORE TECHNOLOGY**

Copper Core® is a registered trademark of AuroraLight. It's a superior system with the market quality and longevity it means that our products are built upon a superior foundation of Solid Copper, ensuring every critical part functions seamlessly together. Thermally integrated® one component for the next. AuroraLight manufactures without compromise, engineered with passion, in the USA.

**12V**

**SEE NEXT PAGE FOR ORDERING INFORMATION**

**CITY of DELRAY BEACH**  
PUBLIC WORKS DEPARTMENT  
404 SOUTH HUNTON AVENUE, DELRAY BEACH, FLORIDA 33444

**LMG1-90-30-18**  
**RT 31.0**

**Radean Post Top LED Area Luminaire**

**Specifications**

EPA: 1.00 B (0.105 m)

Length: 24" (61cm)

Width: 24" (61cm)

H1 Luminaire Height: 4" (10.16cm)

H2 Luminaire Height: 20" (50.8cm)

Weight: 38lbs (17.24kg)

**Introduction**

The architecturally inspired shape of the RADEAN™ post top area luminaire embodies the grace and strength of the RADEAN family. The twin copper-core cast aluminum arms support the slender superstructure, creating a beautiful sculpture by day transforming into a beacon of comfort by night. Triangular arms reflect reflection maintaining its visually quiet appearance. With sleek lines and simple silhouettes, these LED luminaires use specialized lighting and visual comfort to transform common areas like courtyards, outdoor retail locations, universities and corporate campuses into pedestrian-friendly nighttime environments.

**Ordering Information**

EXAMPLE: RADPT LED P3 30K SYM MVOLT PT4 FIR DNAXD

Series	Performance package	Color temperature	Mounting	Voltage	Mounting hardware
RADPT LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI P4 100K 80CRI	27K 2700K 30K 3000K 35K 3500K 50K 5000K	10M Symmetrical 10M Asymmetrical 10M 4-way 10M 4-way	120V 240V 240V 240V	PT4 RADPT2 RADPT3 RADPT4

**Control options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Other options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Shipped installed**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Mounting hardware**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Shipped installed**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Mounting hardware**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Shipped separately**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Mounting hardware**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 240V 240V	PE DBXBD PE DBXBD PE DBXBD

**Options**

SE Single Pole  
SE Single Pole  
SE Single Pole

**Notes**

1. Not available with SE.  
2. Not available with SE.  
3. Not available with SE.  
4. Not available with SE.

**Ordering Information**

EXAMPLE: WDGE1 LED P2 40K 80CRI VF-MVOLT SRM PE DBXBD

Series	Package	Color temperature	CR	Mounting	Voltage	Mounting hardware
WDGE1 LED	P1 100K 80CRI P2 100K 80CRI P3 100K 80CRI	27K 2700K 30K 3000K 35K 3500K	10M VF 10M VF 10M VF	10M VF 10M VF 10M VF	120V 	