



CITY OF DELRAY BEACH
100 N.W. 1st AVENUE, DELRAY BEACH, FL 33444

Solicitation Addendum

Addendum No.: 1

Solicitation No.: 2017-044

Project No.: 16-096

Solicitation Title: Veterans Park Seawall Repair and Dock Replacement

Addendum Date: March 13, 2017

Purchasing Contact: Ryan Lingholm

THE FOLLOWING ITEMS ARE MADE AND HEREBY BECOME A PART OF THIS SOLICITATION:

ADD:

APPENDIX E SCHEDULE OF BID PRICES, ALTERNATE ITEM NO. 13

Alternate Item No. 13 has been added per this Addendum No. 1.

ADD:

APPENDIX E SCHEDULE OF BID PRICES, ALTERNATE ITEM NO. 14

Alternate Item No. 14 has been added per this Addendum No. 1.

QUESTIONS AND RESPONSES:

Q1. Bid Sheet sample in spec package does not provide items for the wood alternate or the fiber reinforcing alternate, are they deleted?

R1. No, the referenced items are not deleted. Alternate Item Nos. 13 and 14 are added per this Addendum No. 1.

- Q2. The note on Sheet No. S1.0 calls for all rebar galvanized. Sheet S4.0 specifies only the epoxied U bar galvanized. Please clarify which is correct.**
- R2. All rebar is to be galvanized for the base bid, and FRP alternate includes the U bars to be steel and to be galvanized. The FRP option has the FRP bars straight and the galvanized U bars combined.
- Q3. What concrete mix design is required for the ramp concrete?**
- R3. The same concrete used for the cap should be used for the ramp.
- Q4. Clarify the wall thickness for the 12" Super Pile.**
- R4. The wall thickness is ½ inch.
- Q5. Clarify what type of resin (Isophthalic Polyester, or Isophthalic Polyester FR, or Vinylester FR) is to be used for the FRP Wide Flange Beams and Channels.**
- R5. Resin is to be Isophthalic Polyester.
- Q6. Sheet No. S4.2 states the following: Proposed 12" diameter X 30 ft long Fiber Reinforced Polymer Piling. What is the specified wall thickness of the 12" Super Pile?**
- R6. Refer to the response for Question 4.
- Q7. Sheet No. S4.2 states the following: Proposed (3) 8" by 8" by ½" Wide Flange Polymer Beams by Fibergrate or Engineer approved equal.**
- A. What resin is required for this product? The manufacturer has multiple resins available with different characteristics for each.
- B. Is there a specified color of these structural members? (Note: We have been advised by Creative Pultrusions that they usually make the Wide Flange beams for Fibergrate)
- R7. A. Resin is to be Isophthalic Polyester.
- B. Yes, there will be a specified color. The City will notify the Successful Contractor of the specified color.
- Q8. Sheet No. S4.2 states the following: Proposed 8" by 2 3/16" by 3/8" FRP Channel (1) each side by Fibergrate or Engineer approved equal.**
- A. What resin is required for this product? The manufacturer has multiple resins available with different characteristics for each.
- B. Is there a specified color of these structural members?
- R8. A. Resin is to be Isophthalic Polyester.
- B. Yes, there will be a specified color. The City will notify the Successful Contractor of the specified color.
- Q9. Sheet No. S4.2 states the following: Proposed 2 X 6 FRP Deck Boards. What is the desired color of the deck?**
- R9. The City will notify the Successful Contractor of the specified color.

NOTE: Items that are ~~struck through~~ are deleted. Items that are underlined have been added. All other terms and conditions remain as stated in the ITBC.

End of Addendum

INSTRUCTIONS:

Receipt of this addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the disqualification of Respondent's response.

APPENDIX E, SCHEDULE OF BID PRICES
Revised per Addendum No. 1

Bidder will complete the Work for the following prices:

SCHEDULE OF BID PRICES

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
Veteran's Park, Delray Beach Florida						
GENERAL CONDITIONS						
1	MOBILIZATION / DEMOBILIZATION	LS	1	_____	\$ _____	\$ _____
				Dollars		

				Cents		
2	DEMOLITION AND REMOVAL OF EXISTING MARGINAL DOCKS AND ELEVATED CONCRETE PAD	LS	1	_____	\$ _____	\$ _____
				Dollars		

				Cents		
3	REINFORCED CONCRETE CAP	LS	1	_____	\$ _____	\$ _____
				Dollars		

				Cents		
4	REINFORCED CONCRETE RAMP (2)	LS	1	_____	\$ _____	\$ _____
				Dollars		

				Cents		

APPENDIX E, SCHEDULE OF BID PRICES

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
Veteran's Park, Delray Beach Florida						
5	MARGINAL DOCKS (2)	LS	1	Dollars	\$	\$
				Cents		
6	ALUMINUM HANDRAILS	LS	1	Dollars	\$	\$
				Cents		
7	AS BUILT RECORD DRAWINGS	LS	1	Dollars	\$	\$
				Cents		
8	VIDEO ALLOWANCE	LS	1	Two Thousand Dollars	\$ 2,000.00	\$ 2,000.00
				No Cents		

APPENDIX E, SCHEDULE OF BID PRICES

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
Veteran's Park, Delray Beach Florida						
9	UNFORSEEN CONDITION ALLOWANCE	LS	1	Twenty Thousand Dollars No Cents	\$ 20,000.00	\$ 20,000.00
10	INDEMNIFICATION	LS	1	Ten Dollars No Cents	\$ 10.00	\$ 10.00
11	PROJECT IDENTIFACATION SIGN	EA	3	Dollars Cents	\$	\$
12	NPDES PERMIT / EROSION CONTROL	LS	1	Dollars Cents	\$	\$
TOTAL EVALUATED BASE BID BID ITEMS 1 through 12 (in numbers)						\$ 22,010.00
				Dollars		
				Cents		

APPENDIX E, SCHEDULE OF BID PRICES

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
Veteran's Park, Delray Beach Florida						
Note: The City reserve the right to award all or portions of the bid amount. (Amounts are to be shown in both words and figures. In case of discrepancies, the amount shown in words will govern for each unit price. Unit price shall prevail over extended total price for bid items based upon unit price.)						
<u>ALTERNATES</u>						
13	<u>RAISED CAP & RAMP REINFORCING</u> <u>STEEL - GFRP</u>	<u>EA</u>	<u>3</u>	<u>Dollars</u> <u>Cents</u>	<u>\$</u>	<u>\$</u>
14	<u>ACQ 0.6 SYP #1 DECKING,</u> <u>FASCIA, STRINGERS AND BENTS</u>	<u>LS</u>	<u>1</u>	<u>Dollars</u> <u>Cents</u>	<u>\$</u>	<u>\$</u>