



CITY OF DELRAY BEACH
100 N.W. 1st AVENUE, DELRAY BEACH, FL 33444

Solicitation Addendum

Addendum No.: 6

Solicitation No.: 2018-018

Project No.: 16-032

Solicitation Title: Seacrest Beautification, Phase 2

Addendum Date: January 5, 2018

Purchasing Contact: Ryan Lingholm - lingholmr@mydelraybeach.com

ITBC NO. 2018-018 IS HEREBY AMENDED AS SET FORTH HEREIN BELOW. THIS ADDENDUM NO. 6 IS HEREBY INCORPORATED IN AND MADE A PART OF ITBC NO. 2018-018.

REVISE:

EXHIBIT B, SPECIFICATIONS, SECTION 01025, MEASUREMENT AND PAYMENT

Section 01025, Measurement and Payment of Exhibit B, Specifications is revised per this Addendum No. 6. Revisions to this section are denoted by yellow highlights.

REVISE:

EXHIBIT D, BID PRICES

Exhibit D, Bid Prices is revised per this Addendum No. 6.

NOTE: Unless otherwise noted, items that are ~~struck through~~ are deleted. Items that are underlined have been added. All other terms and conditions remain as stated in the ITBC.

End of Addendum

INSTRUCTIONS:

Receipt of this addendum must be acknowledged as instructed in the solicitation document. Failure to acknowledge receipt of this Addendum may result in the disqualification of Bidder's response.

SECTION 01025 MEASUREMENT AND PAYMENT

PART 1 - GENERAL

1.01 EXPLANATION AND DEFINITIONS

- A. The following explanation of the Measurement and Payment for the bid form items is made for information and guidance. The omission of reference to any item in this description shall not, however, alter the intent of the bid form or relieve the Contractor of the necessity of furnishing such as part of the Contract.

1.02 PAYMENT

- A. Payment shall be made for the items listed on the Bid Form on the basis of the work actually performed and completed, such work including but not limited to, the furnishing of all necessary labor, materials, equipment, transportation, clean up, and all other appurtenances to complete the construction and installation of the work to the configuration and extent as shown on the drawings and described in the specifications.
The City does not pay for items ordered and/or stored on site. Payment for pay items are paid once the item is installed, measured in place, completed and accepted.
- B. It is intended that all mobilization, insurance, bond, license and other miscellaneous administrative costs, and all other costs to the Contractor not specifically identified in the following item description be distributed among and included in the unit prices stated. No additional payment shall be made for transportation, communications, office maintenance, project signs, and other incidental work or services, and no further payment shall be made for remobilization unless all of the work is suspended by the Engineer for a period in excess of three months and through no fault to the Contractor.
- C. The CONTRACTOR's attention is called to the fact that the quotations for the various items of work are intended to establish a total price for completing the work in its entirety. No separate payment will be made for any item that is not specifically set forth in the Bid Schedule, and all costs therefore shall be included in the prices named in Bid Schedule for various appurtenant items of work.
- D. All required manufacturer testing and certification shall be included in the unit prices shown in the Proposal and Contract. **Density testing required for compacted backfilling, and concrete strength and materials testing required at the time of construction shall be arranged for and paid for by the Contractor.**

1.03 MEASUREMENT

- A. The quantities for payment under this Contract shall be determined by actual measurement of the completed items, in place, ready for service and accepted by the City.

PART 2 - MATERIALS

Not used.

PART 3 - EXECUTION

BASE BID

General Conditions

3.01 SITE MOBILIZATION – Bid Item No. 1

- A. Payment for mobilization/demobilization, permits, bonds, insurance, scheduling and temporary facilities and utilities will be made at the contract Lump Sum (LS) price bid for the item, which price shall be full compensation for all materials, labor, equipment, tools, excavation, masonry and all other incidentals necessary to complete this item.
- B. Payment item for mobilization shall **not exceed five percent (5%) of the base bid contract price** and shall be paid in increments in proportion to the total work completed. Should the price for Site Mobilization exceed 5% of the Contract amount, any amount over the 5% will be paid with the Contractor's final payment application.

3.02 MAINTENANCE OF TRAFFIC – Bid Item No. 2

- A. The quantity of traffic control to be considered for payment shall be equivalent to the percentage of the project determined by the Engineer to be complete as of the date of the pay request submitted. The percent completion of the project shall be based on the percent of the total project actually constructed and not on the percent of the Contract price completed.
- B. Payment for traffic control shall be made on the basis of a percentage (as determined in 'A' above) of the Lump Sum (LS) Price. The contract unit price shall include compensation for required labor, materials, and equipment necessary to keep roadways and property accesses in service during construction activities in accordance with the Contract Documents.
- C. This item includes maintenance of traffic plan, traffic control, flagman, portable changeable (variable) message signs, detour signs, barricades, advance warning arrow panels, construction and removal of temporary access driveways to businesses and/or residential properties, protection to drop offs by temporary barriers or other means, etc.

in order to provide safety and traffic access in accordance with local and state requirements.

- D. Contractor will need to have their detailed MOT Plan for City Roads approved by the City of Delray Beach. The MOT Plan(s) shall be approved prior to mobilizing on-site.
- E. Refer to Specification Section 01570.

3.03 AS-BUILT RECORD DRAWINGS – Bid Item No. 3

- A. Payment for this item shall be on a Lump Sum (LS) Basis. One set of full size design drawings on reproducible material and an electronic file of the design drawings on compact disk will be furnished to the Contractor by the City. The Contractor shall maintain full size (22" x 34") field drawings to reflect the "as-built" items of work as the work progresses. Upon completion of the work, the contractor shall prepare a record set of "as-built" drawings on full size, reproducible material and an electronic file in AutoCAD 2012 or latest version. **The As-built data shall be in State Plane Coordinates and NGVD 29.** No final payment will be made for "as-built" drawings until both the reproducible and electronic files are received and accepted by the City.
- B. This item does not include surveying work required for layout and alignment of utility improvements.
- C. The signed and sealed As-Built drawings prepared by professional surveyor are required to be submitted with each pay request. Measurement for payment for providing and furnishing As-Built drawings shall be based upon percent of project complete.
- D. All survey work shall be performed by an independent third party surveyor, licensed to practice in the State of Florida. The surveyor shall be retained by the Contractor and approved by the City.

3.04 NPDES PERMIT/EROSION CONTROL – Bid Item No. 4

- A. Payment for Contractor required NPDES Permit application (Notice of Intent and Notice of Termination), reporting and associated erosion protection measures including turbidity abatement for dewatering procedures will be made at the Contract Lump Sum (LS) Price Bid for this item. The percent completion of the project shall be based on the percent of the total project actually constructed and not on the percent of the Contract price completed.
- B. Payment for NPDES Permit/Erosion Protection Measures shall be made on the basis of a percentage (as determined in 'A' above) of the Lump Sum Price. The contract lump sum price shall include compensation for required labor, materials, and equipment necessary for complying with the NPDES Permit and providing Erosion Protection Measures during construction activities in accordance with the Contract Documents.

- C. Pay item includes NPDES Inspections per the permit conditions and all inlet protection and all silt fencing required.

3.05 INDEMNIFICATION – Bid Item No. 5

- A. Payment under this item is included in accordance with Article 6.30 of the General Conditions as a Lump Sum (LS) Basis.

3.06 PROJECT IDENTIFICATION SIGN – Bid Item No. 6

- A. Payment for project identification sign shall be made at the contract unit price per each (EA) unit where located by the City prior to construction and shall include furnishing and maintaining the sign throughout the project duration.
- B. The contractor shall schedule a field review with the City Engineer to determine the location of the Project Identification Signs.

3.07 PHOTO DOCUMENTATION/HISTORIC PHOTO INVENTORY – Bid Item No. 7

- A. Payment for photographing, developing and printing of initial site conditions shall be made at the Contractor's unit price of Lump Sum (LS) and shall include all necessary labor and materials for the photographing, processing, printing and developing photographs. The photos will be prepared in accordance with the Florida Department of Transportation requirements for Local Agency Program (LAP) and associated procedures. Photos will include all properties along the project and will include property addresses, descriptions of the conditions of the historic structures and signage along the right-of-way.
- B. This lump sum price shall also include all necessary labor, materials, and equipment to provide the photographs and to assemble and deliver one paper copy and one CD of the all the photographs.
- C. Prior to the commencement of work the contractor shall take detailed photo documentation of both Historical Locations (fabric) and write a brief summary of their current conditions.
- The Contractor shall take all necessary measures to ensure that any historical sites remain undisturbed throughout the entirety of the project.
 - Demolition of materials immediately adjacent to the Historical Site Locations shall be undertaken using non-evasive hand tools and demolition methods.
 - Contractor to provide method of demolition to be approved by the City and the Florida Department of Transportation.

- Vibratory construction methods shall not be utilized for compaction and grading of sidewalks, swales, and pavement directly adjacent to the Historical Site Locations.
- Contractor to take detailed photo documentation and provide a descriptive summary of any Historical Site Locations (fabric) prior to the final inspection.

If during the construction phase of this project and Historical Site Locations (fabric) are damaged, construction shall be halted and the contractor shall notify the Florida Department of State – Division of Historical Resources and the City of Delray Beach, immediately.

3.08 UNFORESEEN CONDITIONS ALLOWANCE – Bid Item No. 8

- A. Payment under this item shall be made as stipulated in Specifications Section 01020 - Allowances.

3.09 VIDEO ALLOWANCE – Bid Item No. 9

- A. Payment under this item shall be made as stipulated in Specifications Section 01020 – Allowances..

Demolition

3.10 CLEARING AND GRUBBING – Bid Item No. 10

- A. Payment for this item shall be made on a Lump Sum (LS) basis. The Contractor's unit price shall include full compensation for all excavation necessary within the road right of way including debris removal, grading, and any other required clearing and grubbing in accordance with the plans and specifications, except for any areas designated to be paid for separately or to be specifically included in the costs of other work under the Contract.
- B. The Contractor shall remove and dispose of all bushes, trees, stumps, roots, fill material, debris, and other such protruding objects, appurtenances, fences, or any other facilities to prepare the area within the Right-of Way for construction of the proposed improvements. This item shall include the relocation of all mailboxes, signs, removal and reinstallation of all irrigation piping, irrigation heads, walls, fencing, trees, and other such appurtenances that conflict with the proposed improvements or is shown to be relocated.

3.11 REMOVE EXISTING CONCRETE SIDEWALK (VARYING WIDTH & THICKNESS) – Bid Item Nos. 11 & 12

- A. Payment for this item shall be on a Linear Foot (LF) Basis. The Contractor's unit price shall include full compensation for labor, materials and equipment required to remove

concrete sidewalks (varying width) as indicated on the plans.

- B. The Contractor shall cut, remove and legally dispose of all concrete sidewalks as indicated on the plans.

3.12 REMOVE EXISTING DRIVEWAY (VARYING TYPES) – Bid Item No. 13

- A. Payment for this item shall be on a Square Yard (SY) Basis. The Contractor's unit price shall include full compensation for labor, materials and equipment required to remove driveways (varying types) as indicated on the plans.
- B. The Contractor shall cut, remove and legally dispose of all asphalt, concrete, gravel or any other type of driveway as indicated on the plans.

3.13 REMOVE EXISTING PAVEMENT SECTION (ASPHALT AND ROADBASE) – Bid Item Nos. 14 & 29.4

- A. Payment for this item shall be made on a Square Yard (SY) Basis. The Contractor's unit price shall include full compensation for labor, materials and equipment required for all pavement section (asphalt pavement and base material– varying thickness) removal necessary within the road right of way as indicated on the plans, except for any areas designated to be paid for separately or to be specifically included in the costs of other work under the Contract.
- B. The Contractor shall cut, remove and legally dispose of existing roadway pavement and concrete curbing (this includes removing shellrock and limestone where applicable), or any other facilities to prepare the area within the easements and rights-of-way for construction of the proposed improvements as indicated on the plans. This includes saw cuts and joints at connections to existing pavement and saw cutting the pavement at each driveway location.
- C. Also included in this item is all restoration work (sod, driveways, sidewalk, etc.) that is required due to removing pavement section.

Roadway

3.14 MILL 2" ASPHALT & OVERLAY 1" TYPE SP 9.5 ASPHALT - Bid Item Nos. 15 & 28.5

- A. Payment for 1-inch milling and installing new 2" Type SP 9.5 – 1" lift asphalt overlay, where indicated on the plans shall be made at the Contractor's unit price per Square Yard (SY) for 2-inch milling and Type SP 9.5 asphalt overlay and shall include all labor, material, and equipment required to mill 2-inch of existing asphalt and construct 2" Type SP 9.5 asphaltic concrete overlay as shown on the plan view and detail drawings. The unit price shall include compensation for multiple mobilizations, labor, materials, and equipment required to mill existing pavement and to construct the new

Type SP 9.5 asphaltic surface overlay with tack coat.

- B. This unit price shall also include all necessary labor, materials, and equipment to adjust the valve boxes, manholes, rims, inlets, or other fixtures to final grade, transitions to existing pavement, tack coating, compaction, rolling, brooming, asphalt testing, replacement of existing traffic loop detection, replacement of blue fire hydrant pavement markers, and any other work required to complete the work.

3.15 VARIABLE DEPTH MILLING - Bid Item No. 16

- A. Payment for variable depth milling where required in addition to Bid Item No. 15, to restore City minimum cross slopes shall be made at the Contractor's unit price per Square Yard (SY). This pay item shall include all labor, material, and equipment required to mill additional existing asphalt as required to restore City minimum slopes in accordance with detail drawings. The unit price shall include compensation for multiple mobilizations, labor, materials, and equipment required to mill, remove and dispose existing pavement.
- B. This unit price shall also include all necessary labor, materials, and equipment to adjust the valve boxes, manholes, rims, inlets, or other fixtures to final grade, transitions to existing pavement, tack coating, compaction, rolling, brooming, asphalt testing, and any other work required to complete the work.

3.16 8" COMPACTED LIMEROCK BASE – Bid Item Nos. 17 & 29.6

- A. Payment for installing new 8-inch compacted limerock base including primer and tack coats where indicated on the plans shall be made at the Contractor's unit price per Square Yard (SY) for limerock base installed and accepted.
- B. The Contract Unit Price shall include compensation for labor, materials, equipment and testing required to construct the new limerock base, vibration and settlement monitoring, including primer and tack coats in accordance with the plans and specifications.

3.17 ASPHALT PAVEMENT – 2" TYPE SP-9.5 ASPHALT (2 LIFTS) – Bid Item Nos. 18 & 29.5

- A. Payment for installing new 2" Type SP-9.5 asphalt pavement (two 1" lifts), including tack coat, where indicated on the plans shall be made at the Contractor's unit price per Square Yard (SY) for Type S-9.5 asphalt pavement and shall include all labor, material, and equipment required to construct 2" asphaltic concrete as required due to construction activities. The unit price shall include compensation for labor, materials, and equipment required to construct the new asphaltic surface.
- B. This unit price shall also include all necessary labor, materials, and equipment to adjust

the valve boxes, manholes, rims, inlets, or other fixtures to final grade, transitions to existing pavement, tack coating, compaction, vibration and settlement monitoring, rolling, brooming, asphalt testing and any other work required to complete the work.

- C. This item also includes installing an asphalt taper around all structures in roadway, if both 1" lifts are not installed within 24 hours.

3.18 12" STABILIZED SUBGRADE – Bid Item Nos. 19 & 30.7

- A. The unit price bid per Square Yard (SY) for the stabilized subgrade (12" thick, LBR 4) shall include all labor, material, and equipment required to construct the subgrade as shown on the detail drawings. The unit price shall include all excavation, line cutting of existing pavement, preparation of subgrade, fine grading, placement of subgrade material, compaction, vibration and settlement monitoring, rolling, brooming, and other miscellaneous work required to complete the work in accordance with Florida Department of Transportation Standard Specifications for Road and Bridge Construction, latest edition and City of Delray Beach specifications.

3.19 COLORED ASPHALT COATING – Bid Item No. 20

- A. Payment for installing new Colored asphalt coating – bike lane where indicated on the plans shall be made at the Contractor's square yard (SY) Basis for colored asphalt coating applied a minimum of 36 dry mills, installed and accepted.
- B. The Contract lump sum price shall include compensation for labor, materials, and equipment required to apply new colored asphalt coating in accordance with the manufactures surface preparation installation and clean-up. No deduction will be made for area(s) occupied by manholes, inlets, drainage structures, bollards or by any public appurtenances within the area.
- C. Contractor to use approved materials stated in the FDOT Section 523 and the FDOT Qualified Products List **AND** have FHWA Approval.
- D. The Contractor shall match the existing bike lane color used in FM 431650-1-58-01 & FM 435080-1-58-01.

3.20 CONCRETE CURBS & GUTTER – Bid Items Nos. 21 & 29.3

- A. The quantity of curbs and/or gutter shall be determined by measurement of the units Linear Foot (LF) installed and accepted.
- B. Payment for furnishing and installing concrete curbs and gutters shall be made at the contract unit price per linear foot of each type concrete curb and/or gutter, including flared ends and transitions, rebar (as applicable) installed and accepted. The contract

unit price shall include all labor, materials, and equipment necessary to prepare and test the sub-base and install the concrete curbs and/or gutter in accordance with the plans and specifications.

C. Refer to “CURB AND GUTTER SECTIONS” detail on sheet C-28.

3.21 6' WIDE (4" & 6" THICK) CONCRETE SIDEWALK – Bid Item Nos. 22 & 23

- A. Payment for sidewalks where indicated on the plans and specifications per City Detail – RT 5.1, shall be made at the Contractor's unit price per Linear Foot (LF) of sidewalk installed and accepted. The Contract Unit Price shall include full compensation for labor, material, equipment and testing required to install the sub-base and sidewalk in accordance with the plans and specifications.
- B. Payment shall be made for sidewalks constructed or replaced by authorization of the Engineer. Any sidewalk that is broken incidental to construction shall be replaced at the Contractor's expense.

3.22 CONCRETE DRIVEWAY APRON (6" THICK) – Bid Item No. 24

- A. The quantity of concrete drive aprons shall be determined by measurement of the units per Square Yard (SY) installed and accepted.
- B. Payment for furnishing and installing 6-inch thick concrete drive aprons shall be made at the contract unit price per square foot of apron installed and accepted. The contract unit price shall include full compensation for all labor, materials, equipment and testing necessary to install the sub-base and concrete drive aprons in accordance with the plans and specifications.
- C. Concrete driveway apron replacement beyond the limits established by the project construction drawings will not be considered for payment.

3.23 PAVER BRICK AT CURB RAMPS INCLUDING TACTILE SURFACE PAVERS – Bid Items No. 25

- A. Payment for this item shall be made at the Contractor's unit price per Square Yard (SY) of curb ramp installed and accepted. The Contractor's unit price shall include full compensation for furnishing and installing the curb ramps including the provision of “brick red” truncated dome paver brick located at tactile surface locations. Ramp slopes and dimensions shall be constructed per FDOT Index 304 at the locations shown on the Drawings. The curb ramps shall be in accordance with the plans, details, and specifications.

- B. The paver brick color selection shall be “brick red” as indicated on the plans and as approved by the City during the shop drawing process.
- C. The Contract Unit Price shall also include adjustment of existing paver bricks to proposed grades including provision of additional sand or adjustments to the subgrade in order to match proposed back of curb elevations or in order to relocate curb ramps, and any sub-base or concrete testing.
- D. Refer to “DETECTABLE WARNING RAMP IN PAVER SIDEWALK TYPICAL DETAIL” on sheet C-28.

3.24 SWALE GRADING AND SODDING – Bid Item No. 26

- A. Payment for this item shall be made on a Square Yard (SY) basis. The Contractor's unit price shall include full compensation for all swale grading and sodding within the road right of way as indicated on the plans.
- B. The Contractor's unit price shall constitute full compensation for all labor, materials, and equipment required for excavation, grading, hauling, placing, compacting, and dressing of the surface of the swales in preparation for sodding, placement, and maintenance of the Bahia sod or St. Augustine sod.

3.25 PEDESTRIAN SIGNAL, LED, COUNTDOWN, 1 DIRECTION “Complete” – Bid Item No. 27

- A. Payment shall be made on a unit price per each (EA) pedestrian signal installed and accepted by the City. Payment shall include the design and installation of a complete and operable system, including the furnishing of all labor, equipment, material and supervision necessary to construct the signals. Contractor will be responsible for installing a complete and operational system including but not limited to control wire, connection to existing controllers, modifying existing pedestrian signals, pedestals, foundations, transformer bases, signs, connection to existing poles, modifying existing control boxes, traffic loops, pull boxes, etc. and signal testing.
- B. A professional Signal Contractor with proper licenses will be required to do the work.
- C. Signal materials and design specifications shall be in accordance with the local and/or state agencies. Refer to the FDOT Standard Specifications for Road and Bridge Construction for Traffic Control and Signal Devices. See **Appendix B**

3.26 SIGNING AND PAVEMENT MARKINGS – Bid Item No. 28

- A. The Lump Sum (LS) bid price shall include all labor, material, and equipment required for all thermoplastic pavement markings, pedestrian and traffic control signs, and symbols and reflective markers that are to be replaced in areas of roadway resurfacing. This includes all stop conditions. All pavement marking shall be thermoplastic. The lump sum prices shall include all materials, equipment, preparation, and other miscellaneous work required to complete the work in accordance with Florida Department of Transportation Section 711, the MUTCD, Palm Beach County requirements and City of Delray Beach specification.
- B. The unit price includes all temporary (traffic paint) pavement markings required until the permanent thermoplastic pavement markings are installed.
- C. This pay item shall also include removal, storage and replacement of all existing signs to be relocated outside of the clear zone.

3.27 PAVER CROSS-WALK @ INTERSECTIONS - Bid Item Nos. 29.1 & 29.2

- A. Payment for installing new paver brick crosswalks where indicated on the plans shall be made at the Contractor's unit price per Square Foot (SF) of crosswalk installed and accepted. The Contract Unit Price shall include compensation for labor, material, equipment and testing required to furnish and install the new paver brick surface course, including 6 inches 3,000 psi Portland cement concrete base and sand leveling courses, in accordance with the plans and specifications
- B. Paver brick color, laying pattern and manufacturer selection shall be as specified on the plans and as approved by the City during the shop drawing process.
- C. Refer to "PAVERBRICK CROSSWALK DETAIL" on sheet C-29.

3.28 3" MILLING - Bid Item No. 30.1

- A. Payment for 3-inch milling, where indicated on the plans shall be made at the Contractor's unit price per Square Yard (SY) for 3-inch milling and shall include all labor, material, and equipment required to mill 3-inch of existing asphalt as shown on the plan view and detail drawings. The unit price shall include compensation for multiple mobilizations, labor, materials, and equipment required to mill existing pavement and any other work required to complete the work.

3.29 ASPHALT RUBBER MEMBRANE INTERLAYER (ARMI) INCLUDES No. 6 AGGREGATE - Bid Item No. 30.2

- A. Payment for installing ARMI layer where indicated on the plans shall be made at the Contractor's unit price per Square Yard (SY) of ARMI installed and accepted. The Contract Unit Price shall include compensation for labor, material, equipment and testing required to furnish and install the ARMI Layer in accordance with the plans and FDOT Specification 341.
- B. Payment shall also include clean No. 6 aggregate in accordance with the FDOT Flexible Pavement Design Manual. See *Appendix D*

END OF SECTION

4. Bidder will complete the Work for the following prices:

SCHEDULE OF BID PRICES

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
BASE BID						
GENERAL CONDITIONS						
1	Site Mobilization	LS	1	_____	\$ _____	\$ _____
				Dollars		

				Cents		
2	Maintenance of Traffic	LS	1	_____	\$ _____	\$ _____
				Dollars		

				Cents		
3	As-Built Record Drawings	LS	1	_____	\$ _____	\$ _____
				Dollars		

				Cents		
4	NPDES Permit / Erosion Control	LS	1	_____	\$ _____	\$ _____
				Dollars		

				Cents		
5	Indemnification	LS	1	Ten	\$ 10.00	\$ 10.00
				Dollars		
				Zero		
				Cents		
6	Project Identification Signs	LS	1	_____	\$ _____	\$ _____
				Dollars		

				Cents		

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
7	Photo Documentation/Historic Photo Inventory	EA	2	Dollars	\$	\$
				Cents		
8	Unforeseen Condition Allowance	LS	1	Fifty-five thousand	\$ 55,000.00	\$ 55,000.00
				Dollars		
				Zero		
				Cents		
9	Video Allowance	LS	1	Three thousand	\$ 3,000.00	\$ 3,000.00
				Dollars		
				Zero		
				Cents		
DEMOLITION						
10	Clearing and Grubbing	LS	1	Dollars	\$	\$
				Cents		
11	4" Thick Sidewalk Removal	LF	1,064	Dollars	\$	\$
				Cents		
12	6" Thick Sidewalk Removal	LF	555	Dollars	\$	\$
				Cents		

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
13	6" Thick Driveway Apron Removal	SY	950	Dollars	\$	\$
				Cents		
14	Pavement Removal	SY	1,300	Dollars	\$	\$
				Cents		
ROADWAY						
15	2" Milling and Resurfacing	SY	8,281	Dollars	\$	\$
				Cents		
16	Variable Milling and Resurfacing 2" Max Variable Depth Milling	LS SY	4 250	Dollars	\$	\$
				Cents		
17	8" Compacted Limerock Base Incl. Prime Coat	SY	1,990	Dollars	\$	\$
				Cents		
18	2" Type SP 9.5 Asphalt Surface Course 2-1" lifts Incl. Tack Coat	SY	1,780	Dollars	\$	\$
				Cents		
19	12" Compacted Subgrade	SY	2,220	Dollars	\$	\$
				Cents		

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
20	Colored Asphalt Coating	SY	2,673	Dollars	\$	\$
				Cents		
21	Type "F" Curb	LF	1,410	Dollars	\$	\$
				Cents		
22	4" Thick Concrete Sidewalk	LF	3,767	Dollars	\$	\$
				Cents		
23	6" Thick Concrete Sidewalk	LF	908	Dollars	\$	\$
				Cents		
24	6" Thick Concrete Driveway Apron	SY	957	Dollars	\$	\$
				Cents		
25	Curb Ramps with Tactile Surface Pavers	SY	258	Dollars	\$	\$
				Cents		

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
26	Swale Grading and Sodding	SY	5,433		\$	\$ -
				Dollars		
				Cents		
27	Pedestrian Signal, LED, Countdown, 1 Direction "Complete"	EA	8		\$	\$ -
				Dollars		
				Cents		
28	Stop Conditions/Striped Crosswalks/Pavement Markings Traffic Signage at Intersections	LS	1		\$	\$ -
				Dollars		
				Cents		
TOTAL EVALUATED BASE BID BID ITEMS 1 through 28 (in numbers)						\$ 58,010.00
TOTAL EVALUATED BASE BID BID ITEMS 1 through 28 (in words)						
				Dollars		
				Cents		

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
ADD ALTERNATES						
29	DECORATIVE PAVER BRICK CROSSWALKS					
29.1	Brick Pavers	SY	440		\$	\$
				Dollars		
				Cents		
29.2	12" Header Curb	LF	1,440		\$	\$
				Dollars		
				Cents		
29.3	Type "D" Curb	LF	90		\$	\$
				Dollars		
				Cents		
29.4	Pavement Removal (DEDUCTION)	SY	336		\$	\$
				Dollars		
				Cents		
29.5	2" Milling and Resurfacing (DEDUCTION)	SY	582		\$	\$
				Dollars		
				Cents		
29.6	8" Compacted Limerock Base (DEDUCTION) Incl. Prime Coat	SY	75		\$	\$
				Dollars		
				Cents		
29.7	2" Type SP 9.5 Asphalt Surface Course (DEDUCTION) 2-1" lifts Incl. Tack Coat	SY	60		\$	\$
				Dollars		
				Cents		

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
29.8	12" Compacted Subgrade (DEDUCTION)	SY	94	<div></div> <div>Dollars</div> <div></div> <div>Cents</div>	<div>\$</div> <div></div>	<div>\$</div> <div></div>
TOTAL EVALUATED ADD ALTERNATE BID ITEM 29 (in numbers)						<div>\$</div> <div></div> <div>-</div>
TOTAL EVALUATED ADD ALTERNATE BID ITEM 29 (in words)				<div></div> <div>Dollars</div> <div></div> <div>Cents</div>		

REMAINDER OF PAGE INTENTIONALLY LEFT BLANK

ITEM NO.	DESCRIPTION	UNIT	EST. QTY.	UNIT PRICE (in words)	UNIT PRICE	EXTENDED TOTAL PRICE
30	ASPHALT RUBBER MEMBRANE INTERLAYER (ARMI)					
30.1	3" Milling	SY	3,780		\$	\$
				Dollars		
				Cents		
30.2	1" ARMI Layer Incl. No. 6 Aggregate	SY	3,780		\$	\$
				Dollars		
				Cents		
30.3	2" Type SP 9.5 Asphalt Surface Course 2-1" lifts Incl. Tack Coat	SY	3,780		\$	\$
				Dollars		
				Cents		
30.4	2" Milling and Resurfacing (DEDUCTION)	SY	3,780		\$	\$
				Dollars		
				Cents		
TOTAL EVALUATED ADD ALTERNATE BID ITEM 30 (in numbers)						\$ -
TOTAL EVALUATED ADD ALTERNATE BID ITEM 30 (in words)						
				Dollars		
				Cents		

(Amounts are to be shown in both words and figures. In case of discrepancies, the amount shown in words will govern for each bid item, unit price, and total bid. Extended unit price shall prevail over total price for bid items based upon unit price.)