



Development Services: Planning and Zoning Department

BOARD ACTION REPORT – APPEALABLE ITEM

Project Name: 7-Eleven

Project Location: 16000 S. Military Trail

Request: Class V Site Plan, Architectural Elevations, and Landscape Plans

Board: Site Plan Review and Appearance Board

Meeting Date: February 27, 2019

Board Action:

Approved with a 7-0 vote on each of the following requests: Class V Site Plan, Architectural Elevations and Landscape Plans.

Project Description:

The 0.93 acre subject parcel is Tract C of Linton Oaks Square, an 8.8 acre shopping center as recorded in Plat Book 51, Page 118 of the public records of Palm Beach County. The property is zoned Planned Commercial (PC) with a Future Land Use Map designation of General Commercial (GC). The Class V Site Development plan proposes to construct a Convenience Mart type gasoline station. On July 10, 2018, a waiver for minimum structure size in the PC zoning district was granted by City Commission. On August 20, 2018, the Planning Board recommended approval for the Modification of the Conditional Use to demolish the existing facilities to construct a larger convenience mart and increase the number of fueling stations. The modification was subsequently approved by City Commission on October 2, 2018.

The proposed site improvements include the demolition of the existing convenience mart and fuel canopy and the construction of a new 2,538 sf convenience mart with 8 fueling stations (16 fueling positions) and associated parking. The proposed convenience mart will operate 24 hours a day, seven days a week, as it does currently. LDR Section 4.3.3(VV)(3), 24 hour Businesses, contains additional regulations for new 24 hour Businesses, including the provision of a conditional use approval; however, these additional standards do not apply to 24-hour businesses that were in operation at the time of the adoption of Ordinance No. 41-01. Per Section 1.3.7, any use which is currently allowed as a conditional use in a zoning district but which, prior to September 1, 1990, was an established permitted use shall not be deemed a nonconforming use but shall, without further action be considered a conforming conditional use. As this Mobil Station was established in November 1985 and has been operating 24 hours, the 24-hours of operation is considered a conforming conditional use.

The elevations are generally in good taste and will not materially depreciate the surrounding environment. Additional detailing has been added to the facades that face the right-of-ways to give the building some visual interest from that perspective. The canopy has been designed to blend with the façade of the proposed structure utilizing like colors, materials and textures.

A proposed landscape plan has been evaluated by the Senior Landscape Planner and found to be in compliance. A tree disposition plan was included with the landscape plans. Removal, relocation and mitigation has been determined for the existing trees. Mitigation was found to be in compliance. To retain a cohesive feel with the shopping center, proposed tree species in the planting islands that border the center used selections that are being used throughout the shopping center.

Appealable Item Report

Board Comments:

Board comments supportive of the requests.

Public Comments:

No members of the public spoke for or against the project.

Associated Actions:

N/A

Next Action: The Site Plan Review and Appearance Board action is final unless appealed by the City Commission.



SITE PLAN REVIEW AND APPEARANCE BOARD STAFF REPORT

DEVELOPMENT SERVICES DEPARTMENT

100 NW 1ST AVENUE, DELRAY BEACH, FLORIDA 33444

PLANNING & ZONING DIVISION: (561) 243-7040 • BUILDING DIVISION: (561) 243-7200

SITE PLAN REVIEW AND APPEARANCE BOARD

Meeting: February 27, 2019

File No.: 2018-071-
SPF-SPR-CL 5

Application Type: Class V Site Plan, Landscape Plan,
Architectural Elevations– 7-Eleven

General Data:

Agent/Applicant: Shane Laakso, Keith and Associates

Owner: 7-Eleven, Inc.

Location: 16000 S. Military Trail, Linton Oaks Square

PCN: 12424625100030000

Property Size: 0.93 Acres

FLUM: GC (General Commercial)

Zoning: PC (Planned Commercial)

Adjacent Zoning:

- North: PC
- South: CF (Community Facilities)
- East: POC (Planned Office Center)
- West: PC

Existing Land Use: 24-hour Convenience Mart

Proposed Land Use: 24-hour Convenience Mart

Item before the Board:

The action before the Board is the consideration of a Class V Site Plan application for the **7-Eleven located at 16000 S. Military Trail** pursuant to LDR Section 2.4.5 (F), including the following:

- ☐ Site Plan
- ☐ Landscape Plan
- ☐ Architectural Elevations



Staff Recommendations

By separate motions:

Site Plan:

Move approval of the Class V Site Plan Modification (2018-071) for **7-Eleven located at 16000 S. Military Trail**, by adopting the findings of fact and law contained in the staff report and finding that the request is consistent with the Comprehensive Plan and meets criteria set forth in Section 2.4.5(F)(5) and Chapter 3 of the Land Development Regulations with the following Condition of Approval:

1. Prior to building permit issuance, the portion of Utility Easement PB 51, PG 118, located under the proposed building must be abandoned.

**Note: If the site plan is denied, no further action shall be taken on the landscape plan or architectural elevations due to potential inconsistencies.*

Landscape Plan:

Move approval of the Landscape Plan for **7-Eleven located at 16000 S. Military Trail**, by adopting the findings of fact and law contained in the staff report and finding that the request and approval thereof is consistent with the Comprehensive Plan and meets criteria set forth in LDR Section 4.6.16.

Project Planner:

Christine Stivers, Senior Planner;
stiversc@mydelraybeach.com,
561-330-6056

Review Dates:

GIAB: 7-19-18

Attachments:

1. Site Plans
2. Elevations
3. Landscape Plan

**Architectural Elevations:**

Move approval of the Architectural Elevations for **7-Eleven located at 16000 S. Military Trail**, by adopting the findings of fact and law contained in the staff report and finding that the request meets criteria set forth in LDR Section 4.6.18(E).

Background:

The 0.93 acre subject parcel is Tract C of Linton Oaks Square, an 8.8 acre shopping center as recorded in Plat Book 51, Page 118 of the public records of Palm Beach County. The property is zoned Planned Commercial (PC) with a Future Land Use Map designation of General Commercial (GC). In early 1985, the vacant site was annexed into the City. In March of 1985, the City approved a land use amendment changing the designation from single family to commercial. Concurrently, a Conditional Use to allow a service station (convenience mart per current code) and the shopping center site plan was reviewed and approved. A service station with no mechanical repairs was approved as a conditional use. The approved site plan for the shopping center consisted of 62,080 sf of retail space and three outparcels, including a service station, financial establishment and a restaurant.

In November of 1985, a site plan modification was approved to accommodate development of the corner outparcel, the subject parcel (Tract C) as a Mobile Station. In association with the site plan modification approval, a Shopping Center Easement Agreement was recorded providing the subject parcel use of, and mutual benefit from, common parking, parking lot lighting, access over and across all paved drives and parking areas, sidewalks and other pedestrian areas within the Linton Oaks Square. The subject parcel, as well as the entire shopping center, has no residential zoning directly adjacent. PC zoning is located to the north across W. Linton Boulevard; Planned Office Center (POC), is to the east of the shopping center; Community Facilities (CF) is located to the south of the center; PC is to the west across S. Military Trail; and, at the northwest corner of the intersection of S. Military Trail and West Linton Boulevard, there is a residentially zoned development, Multi-family residential (RM) within unincorporated Palm Beach County. Although the distance from the subject parcel to the residentially zoned property is approximately 200 feet, the distance to the closest residential lot is just over 500 feet.

On July 10, 2018, a waiver for minimum structure size in the PC zoning district was granted by City Commission. On August 20, 2018, the Planning Board recommended approval for the Modification of the Conditional Use to demolish the existing facilities to construct a larger convenience mart and increase the number of fueling stations from 4 stations (8 fueling positions) to 8 stations (16 fueling positions). The modification was subsequently approved by City Commission on October 2, 2018.

Project Description:

The applicant has submitted a Class V Site Development plan to construct a Convenience Mart type gasoline station. Pursuant to LDR Section 4.3.3(J)(2), this type of gasoline station falls under the category of Convenience Mart (gasoline station with food sales), which is defined as a gasoline station which also sells foods and convenience items and does not accommodate repair or installation services and where the sale of food and convenience items is secondary to the use as a gasoline station.

The proposed site improvements include the demolition of the existing convenience mart and fuel canopy and the construction of a new 2,538 sf convenience mart with 8 fueling stations (16 fueling positions). The existing connection to the shopping center will be slightly modified to provide parallel parking to replace the existing 90 degree parking along the rear property line that will be removed during construction. 8 parallel spaces are proposed with the remaining parking along the front of the convenience mart. The proposed site plan also depicts an air pump and vacuum as well as a bike rack.

The proposed convenience mart will operate 24 hours a day, seven days a week, as it does currently. LDR Section 4.3.3(VV)(3), 24 hour Businesses, contains additional regulations for new 24 hour Businesses, including the provision of a conditional use approval; however, these additional standards do not apply to 24-hour businesses that were in operation at the time of the adoption of Ordinance No. 41-01. Per Section 1.3.7, any use which is currently allowed as a conditional use in a zoning district but which, prior to September 1, 1990, was an established permitted use shall not be deemed a nonconforming use but shall, without further action be considered a conforming conditional use. As this Mobil Station was established in November 1985 and has been operating 24 hours, the 24-hours of operation is considered a conforming conditional use.

Site Plan Analysis:

The following items identified in the Land Development Regulations shall specifically be addressed by the Site Plan Review and Appearance Board (SPRAB) for final action on the site and development applications/requests, as presented.



The subject property is zoned within the PC Zoning District. A Convenience Mart use has several development standard requirements that supersede the development standards within the PC zoning district. The following table illustrates the required standards for the PC zoning district for this parcel.

	Required	Provided
PC Zoning District, Development Standards		
Lot Depth	100-feet	168-feet
Max Lot Coverage	75%	6%
Min Open Space	25%	30%
Floor Area (Minimum square feet)	6,000 sf	2,538 sf*
Special Landscape Setback-Military Trail and Linton Blvd.(4.3.4(H)(6)(b)(6))	18.24'(Linton),16.98' (S. Military)	18.24' min.(Linton),16.98' min. (S. Military)
PC-Special landscape area	10-feet	10-feet min.

* Waiver granted 7/10/2018 by CC.

Section 4.3.3, Special requirements for specific uses-Convenience Mart:

Pursuant LDR Section 4.3.3(J), a gasoline station is any establishment at which the sale and delivery of fuel to a motor vehicle occurs. Gasoline stations are also classified as to other commercial activities which may occur on the site of the establishment.

Pursuant to LDR Section 4.3.3(J)(2), this gasoline station falls under the category of Convenience Mart (gasoline station with food sales), which is defined as a gasoline station which also sells foods and convenience items and does not accommodate repair or installation services and where the sale of food and convenience items is secondary to the use as a gasoline station.

Pursuant LDR Section 4.3.3(J)(5), the following development standards depicted on the table below apply to sites upon which a Convenience Mart gasoline station is to be located.

Standard	Convenience Mart	Provided
Minimum Lot Area	15,000 Square Feet	40,559 sf (0.93 Ac.)
Minimum Frontage	150 Feet	222.50-feet
Parking Requirements	4.5 / 1,000 Square Feet of Gross Floor Area (12 sp)	21 Spaces
Driveways	There shall be no more than two (2) curb-cuts to any abutting street with a minimum distance of twenty-five feet (25') between curb-cuts. Curb-cuts shall not have a width exceeding thirty-five feet (35'), exclusive of transitions. Curb-cuts shall not be located closer than twenty-five feet (25') to the intersection of the ultimate right-of-way lines at a corner nor closer than fifteen feet (15') from any abutting property line or alley.	The subject parcel is located interior to the shopping center, therefore, the driveway requirement does not apply in this situation.

Pursuant LDR Section 4.3.3(J)(6),the following standards apply to gasoline stations:

- (a) Gasoline dispensers, tanks, dispenser islands, and canopies shall not be located closer than fifteen feet (15') from any property line. When property directly abuts residentially zoned property, gasoline dispensers, tanks, dispenser islands and canopies, signs, or vents shall not be located closer than 40 feet from the property line abutting the residentially zoned property.

The proposed tanks, canopies and dispensers islands exceed 15 feet from the nearest property line. The tanks are approximately 20 feet from the property line and the canopy is approximately 35 feet from the property line. The subject parcel does not abut any residentially zoned property.

- (b) All storage tanks shall be underground.

The existing storage tanks will be removed and replaced with new tanks that will be located underground.



- (c) Lift and repair facilities shall be located within a structure. There are no proposed lift and repair facilities for this use.
- (d) Vending machines are to be located under roof and screened on three sides. Racks containing cans of lubricating oil may be displayed on service islands. Racks or pedestals used for the display of tires shall be located along any side (as opposed to front) of a structure.

No vending machines or tire sales are proposed and oil sales will be conducted inside only. However, CO2 and Propane tanks stored in cages are proposed along the northeast face of the building, which faces West Linton Boulevard. Per LDR Section 4.6.6(C)(2), Outside Storage, materials and equipment stored outside must be screened from view from public rights-of-ways in a manner approved by the Site Plan Review and Appearance Board. The tanks and cages will be screened from Linton Boulevard by the provided landscaping.

Lighting:

The proposed lighting consists of wall fixtures on the building and freestanding poles within the parking area and within the fuel canopy. The fuel canopy faces in towards the existing shopping center away from residential zoning across Linton Boulevard. The proposed values are within the permitted minimum and maximum ranges, which comply with the requirements of LDR Section 4.6.8(B)(3), Illumination Standards.

Minimum Parking Requirements/Loading:

Pursuant to LDR Section 4.3.3, convenience marts shall provide 4.5 parking spaces per 1,000 square feet of gross floor area. Currently, 9 parking space are located along the southern property line of the existing facility. These spaces are part of a shared parking agreement for the Linton Oaks Square shopping center. The applicant is required to provide 12 parking spaces for the proposed 2,538 sf convenience mart, but has provided 21 parking spaces, including one ADA parking space. The total spaces reflect the original approved amount of spaces for Linton Oaks Square plus the additional spaces needed for the expansion of the convenience mart. Anticipated deliveries to the convenience mart will be via box truck and gas tanker. As the structure size of the mart is less than the square footage that requires a loading area, loading will be done within one of the parking spaces. The gas tankers will unload near the tanks. Although the tanker may block one entrance to the mart, two additional entrances will be available for patrons to utilize.

Refuse Enclosure:

Pursuant to LDR Section 4.6.6(C)(1), dumpsters, recycling containers and similar service areas must be enclosed on three sides with vision obscuring gates on the fourth side, unless such areas are not visible from any adjacent public rights-of-way. The refuse enclosure does not face a public right of way but faces the interior of the subject parcel. The area is enclosed on three sides and provides gates, meeting the code requirements.

Landscape Analysis:

Pursuant to LDR section 4.6.16(C)(1)(a), prior to the issuance of a building permit for a structure or a paving permit, compliance with the requirements of Section 4.6.16 shall be assured through the review and approval of a landscape plan submitted pursuant to Section 2.4.3(C). A proposed landscape plan has been submitted and evaluated by the Senior Landscape Planner and found to be in compliance. A tree disposition plan was included with the landscape plans. Removal, relocation and mitigation has been determined for the existing trees. Mitigation was found to be in compliance. To retain a cohesive feel with the shopping center, proposed tree species in the planting islands that border the center used selections that are being used throughout the shopping center.

Architectural Elevations Analysis

Pursuant to LDR Section 4.6.18(E), Criteria for Board Action, the following criteria shall be considered by the Site Plan Review and Appearance Board (SPRAB) in the review of plans for building permits. If the following criteria are not met, the application shall be disapproved:

1. The plan or the proposed structure is in conformity with good taste, good design, and in general contributes to the image of the City as a place of beauty, spaciousness, harmony, taste, fitness, broad vistas, and high quality.
2. The proposed structure, or project, is in its exterior design and appearance of quality such as not to cause the nature of the local environment or evolving environment to materially depreciate in appearance and value.
3. The proposed structure, or project, is in harmony with the proposed developments in the general area, with the Comprehensive Plan, and with the supplemental criteria which may be set forth for the Board from time to time.



The elevations are generally in good taste and will not materially depreciate the surrounding environment. The existing center is dated but the earth tones and wall material of the proposed structure are consistent with the existing buildings. Additional detailing has been added to the facades that face the right-of-ways to give the building some visual interest from that perspective. The canopy has been designed to blend with the façade of the proposed structure utilizing like colors, materials and textures. Therefore, positive findings can be made with regard to the criteria listed in LDR Section 4.6.18(E).

Pursuant to **LDR Section 3.1.1 (Required Findings)**, prior to the approval of development applications, certain findings must be made in a form which is part of the official record. This may be achieved through information on the application, the staff report, or minutes. Findings shall be made by the body which has the authority to approve or deny the development application. These findings relate to the following four areas.

FUTURE LAND USE MAP: The use or structures must be allowed in the zoning district and the zoning district must be consistent with the land use designation.

The subject property has a Future Land Use Map designation of General Commercial (GC) and is zoned Planned Commercial (PC). The PC zoning district is consistent with the GC Future Land Use Map (FLUM) designation. Based upon the above, a positive finding can be made with respect to consistency with the Future Land Use Map.

CONCURRENCY: Facilities which are provided by, or through, the City shall be provided to new development concurrent with issuance of a Certificate of Occupancy. These facilities shall be provided pursuant to levels of service established within the Comprehensive Plan.

A positive finding of concurrency was made including a positive concurrency finding for streets and traffic by the Palm Beach County Traffic Division.

CONSISTENCY: Compliance with performance standards set forth in Chapter 3 and required findings in Section 2.4.5(G)(5) for the request shall be the basis upon which a finding of overall consistency is to be made. Other objectives and policies found in the adopted Comprehensive Plan may be used in making a finding of overall consistency.

As described in Appendix A, a positive finding of consistency can be made as it relates to Development Standards for Site Plan Actions.

COMPLIANCE WITH THE LAND DEVELOPMENT REGULATIONS (LDRs): Items identified in the Land Development Regulations shall specifically be addressed by the body taking final action on the site and development application/request.

As described under the Site Plan Analysis section of this report, a positive finding of compliance with the LDRs is made.

LDR Section 2.4.5(G) (5) - Compatibility (Site Plan Findings): the approving body must make a finding that development of the property pursuant to the site plan will be compatible and harmonious with adjacent and nearby properties and the City as a whole, so as not to cause substantial depreciation of property values.

The following table indicates the zoning and land use of the properties surrounding the subject parcel:

	Adjacent Zoning	Adjacent Land Use
North	Planned Commercial (PC)	Shopping Center/Financial institutions
South	Community Facilities (CF)	South County Mental Health Center
East	Planned Office Center (POC)	Linton Medical Park
West	PC	Delray Medical Center



The subject parcel is located at the northwest portion of the shopping center. It is immediately bordered on the north by a Lake Worth Drainage District Canal then West Linton Avenue, and to the west, Military Trail. The existing shopping center borders the south and east property lines of the subject parcel. The reconstruction of the convenience mart is not abutting any residential properties, but allowable uses within the PC district. Thus, a finding can be made that the use will not have a detrimental effect upon the stability of the neighborhood, nor will it hinder the development or redevelopment of nearby properties. Therefore, a positive finding can be made with regard to LDR Section 2.4.5(F)(5) that the site plan will be compatible and harmonious with adjacent and nearby properties.

Comprehensive Plan Policies: A review of the goals, objectives and policies of the adopted Comprehensive Plan was conducted, and the following applicable objectives or policies were noted.

Future Land Use Element Objective A-1 - Property shall be developed or redeveloped in a manner so that the future use and intensity is appropriate and complies in terms of soil, topographic, and other applicable physical considerations, is complimentary to adjacent land uses, and fulfills remaining land use needs.

7 Eleven is proposing a 2,538 sf convenience mart and fueling area with 8 fueling stations. (16 fueling positions). The existing convenience mart is 840 sf with 4 fueling stations. The PC zoning district requires a standalone building to be a minimum of 6,000 square feet. Any expansion of the approved conditional use to obtain this minimum square footage is encouraged. The mart in addition to the canopy is approximately 6,800 sf. This size was the vision of the PC district creation, therefore the site is being redeveloped in a manner appropriate and complementary to the adjacent land uses.

Transportation Element - Policy A-6.2: The approval of a modification to an existing site development plan and/or conditional use shall be conditioned upon the upgrading of its points of access to meet adopted standards.

Pursuant to LDR Section 6.1.4(C)(1-2), the minimum width of a two way driveway is 24 feet. The convenience mart (gasoline station with food sales) parcel has internal access to the shopping center; therefore, access points to the shopping center must meet this minimum width. Both access points to S. Military Trail and West Linton Boulevard are a minimum of 24 feet wide. This access is consistent with the Transportation Element of the Comprehensive Plan and associated policies.

Transportation Element - Policy D-2.2: Bicycle parking and facilities shall be required on all new development and redevelopment.

As mentioned in the project description, the site plan includes the installation of a bicycle rack. The provision of a bicycle rack is consistent with the Transportation Element of the Comprehensive Plan and associated policies.

Review by Others:

The development proposal is not in a geographic area requiring review by the Pineapple Grove Main Street (PGMS), West Atlantic Redevelopment Coalition (WARC), Historic Preservation Board (HPB), Downtown Development Authority (DDA) or the Community Redevelopment Agency (CRA).

Courtesy Notice:

Courtesy notices have been provided to the following homeowner's associations and/or civic groups:

- Shadywoods

Letters of objection or support, if any, will be presented at the Site Plan Review and Appearance Board (SPRAB) meeting.

Assessment and Conclusion:

The proposed development is consistent with the policies of the Comprehensive Plan and can be found consistent the Land Development Regulations. Also, a positive finding can be made with respect to LDR Section 2.4.5(F)(5), Findings, as the proposed development does not significantly affect surrounding properties. The proposed development is an expansion of an existing use that provides additional fueling stations to negate long wait times, the pedestrian circulation within the subject parcel is safer than what is existing. Improvements are appropriate and will not impact the Center's previously found compatibility with the surrounding area. The use is permitted by an existing conditional use and harmonious with the surrounding shopping center.



Alternative Actions:

- A. Continue with direction.
- B. Move approval of the Class V Site Plan (2018-071), Landscape Plan, and Architectural Elevations Modification for **7-Eleven located at 16000 S. Military Trail**), as amended, by adopting the findings of fact and law contained in the staff report, and finding that the request is consistent with the Comprehensive Plan and meets criteria set forth in Sections 2.4.5(F)(5), 2.4.5(I)(5), 4.6.16, 4.6.18(E) and Chapter 3, Performance Standards, of the Land Development regulations.
- C. Move denial of the Class V Site Plan (2018-071), Landscape Plan, and Architectural Elevations Modification for **7-Eleven located at 16000 S. Military Trail**), by adopting the findings of fact and law contained in the staff report, and finding that the request is inconsistent with the Comprehensive Plan and does not meet criteria set forth in 2.4.5(F)(5), 2.4.5(I)(5), 4.6.16, 4.6.18(E), and Chapter 3, Performance Standards, of the Land Development regulations.

Staff Report Prepared by: *Christine Stivers, Senior Planner*



APPENDIX "A"-CONCURRENCY FINDINGS:

Pursuant to **LDR Section 3.1.1(B)** Concurrency as defined pursuant to Objective B-2 of the Land Use Element of the Comprehensive Plan must be met and a determination made that the public facility needs of the requested land use and/or development application will not exceed the ability of the City to fund and provide, or to require the provision of, needed capital improvements for the following areas:

Water and Sewer: The site will connect to an existing 6" water main which transverses through the property and connects within the S. Military Trail right-of-way.

Pursuant to the Comprehensive Plan, treatment capacity is available at the City's Water Treatment Plant and the South Central County Waste Water Treatment Plant for the City at build-out. Based upon the above, positive findings can be made with respect to this level of service standard.

Streets and Traffic: A traffic study has been submitted that indicates that the proposed development will generate 1,847 daily trips, whereas the original approval provided for 845 daily trips, therefore, there is an increase of 1,002 daily trips. A finding of concurrency has been received from the Palm Beach County Traffic Division.

Parks and Recreation Facilities: Park dedication requirements do not apply to non-residential uses. Thus, the proposed development will not have any impact with respect to this standard.

Solid Waste: The existing convenience mart use (845 sf), generated 15.5 tons of solid waste per year. The proposed improvements (2,538 sf) will generate 46.6 tons of solid waste per year. The development proposal will result in a 31.1 ton decrease. The Solid Waste Authority has indicated that its facilities have sufficient capacity to accommodate all development proposals until 2048.

Drainage: Drainage will be accommodated on site. There are no problems anticipated to bring the site into compliance with South Florida Water Management District (SFWMD) requirements in efforts to obtain a surface water permit.

Drainage will be accommodated on site. No problems for adjacent properties are anticipated with respect to drainage as it relates to this standard.





APPENDIX "B" - STANDARDS FOR SITE PLAN ACTIONS Sec. 3.2.3 (A) through (J)

- A. Building design, landscaping and lighting (glare) shall be such that they do not create unwarranted distractions or blockage of visibility as it pertains to traffic circulation.
- ☐ Not applicable
☒ Meets intent of standard
☐ Does not meet intent
- B. Separation of different forms of transportation shall be encouraged. This includes pedestrians, bicyclists and vehicles in a manner consistent with policies found under Objectives D-1 and D-2 of the Transportation Element.
- ☐ Not applicable
☒ Meets intent of standard
☐ Does not meet intent
- C. Open space enhancements as described in Policies found under Objective B-1 of the Open Space and Recreation Element are appropriately addressed.
- ☒ Not applicable
☐ Meets intent of standard
☐ Does not meet intent
- D. The City shall evaluate the effect that any street widening or traffic circulation modification may have upon an existing neighborhood. If it is determined that the widening or modification will be detrimental and result in a degradation of the neighborhood, the project shall not be permitted.
- ☒ Not applicable
☐ Meets intent of standard
☐ Does not meet intent
- E. Development of vacant land which is zoned for residential purposes shall be planned in a manner which is consistent with adjacent development regardless of zoning designations.
- ☒ Not applicable
☐ Meets intent of standard
☐ Does not meet intent
- F. Property shall be developed or redeveloped in a manner so that the future use and intensity are appropriate in terms of soil, topographic, and other applicable physical considerations; complementary to adjacent land uses; and fulfills remaining land use needs.
- ☐ Not applicable
☒ Meets intent of standard
☐ Does not meet intent
- G. Redevelopment and the development of new land shall result in the provision of a variety of housing types which shall continue to accommodate the diverse makeup of the City's demographic profile and meet the housing needs identified in the Housing Element. This shall be accomplished through the implementation of policies under Objective B-2 of the Housing Element.
- ☒ Not applicable
☐ Meets intent of standard
☐ Does not meet intent



- H. The City shall consider the effect that the proposal will have on the stability of nearby neighborhoods. Factors such as noise, odors, dust, traffic volumes and circulation patterns shall be reviewed in terms of their potential to negatively impact the safety, habitability and stability of residential areas. If it is determined that a proposed development will result in a degradation of any neighborhood, the project shall be modified accordingly or denied.
- ☐ Not applicable
☒ Meets intent of standard
☐ Does not meet intent
- I. Development shall not be approved if traffic associated with such development would create a new high accident location, or exacerbate an existing situation causing it to become a high accident location, without such development taking actions to remedy the accident situation.
- ☐ Not applicable
☒ Meets intent of standard
☐ Does not meet intent
- J. Tot lots and recreational areas, serving children from toddler to teens, shall be a feature of all new housing developments as part of the design to accommodate households having a range of ages. This requirement may be waived or modified for residential developments located in the downtown area, and for infill projects having fewer than 25 units.
- ☒ Not applicable
☐ Meets intent of standard
☐ Does not meet intent



LEGEND:

- BLDG
BM
CB
C.B.S.
CMP
CO
CONC.
E.H.
ELEV.
F.M.
FND.
HDPE
INV.
LB
O.R.B.
P.B.
P.B.C.R.
PG.
PVC
RCP
STY.
TYP.
C
- BUILDING
BENCHMARK
CATCH BASIN
CONCRETE BLOCK STRUCTURE
CORRUGATED METAL PIPE
CLEAN OUT
CONCRETE
ELECTRIC HAND HOLE
ELEVATION
F.M.
FOUND
HIGH DENSITY POLYETHYLENE PIPE
INVERT
LICENSED BUSINESS NUMBER
OFFICIAL RECORDS BOOK
PLAT BOOK
PALM BEACH COUNTY RECORDS
PAGE
POLYVINYL CHLORIDE PIPE
REINFORCED CONCRETE PIPE
STORY
TYPICAL
CENTERLINE
CATCH BASIN
COLUMN BEAM
ELECTRIC HAND HOLE
PAY PHONE
STORM DRAIN MANHOLE
SANITARY SEWER MANHOLE
CROSS WALK LIGHT POLE
WOOD UTILITY POLE
FIRE HYDRANT

- NOT TO SCALE
- BENCHMARK
BOLLARD
GUY ANCHOR
TRAFFIC DIRECTION ARROWS
WATER VALVE
WATER METER
IRRIGATION CONTROL VALVE
CONCRETE LIGHT POLE
WOOD LIGHT POLE
METAL LIGHT POLE
FUEL PUMP
GAS MAHOLE
PALM TREE
SHADE TREE
SINGLE POST SIGN
SANITARY SEWER CLEANOUT
HANDICAP PARKING
TOP OF SLOPE
TOP OF BANK
METAL HAND RAIL
WOOD FENCE
OVERHEAD LINES

SURVEY NOTES:

1. THE LAND DESCRIPTION SHOWN HEREON WAS SUPPLIED BY THE CLIENT.
2. UNLESS OTHERWISE NOTED, RECORD VALUES AND FIELD MEASURED VALUES ARE IN SUBSTANTIAL AGREEMENT.
3. NOT VALID WITHOUT THE SIGNATURE AND ORIGINAL RAISED SEAL OF A FLORIDA LICENSED SURVEYOR AND MAPPER.
4. THIS SURVEY DOES NOT IDENTIFY THE LIMITS OR EXTENTS OF POTENTIAL JURISDICTIONAL BOUNDARIES.
5. BEARINGS SHOWN HEREON ARE ASSUMED AND ARE BASED ON A REFERENCE BEARING OF SOUTH 88°40'12" WEST ON THE NORTH LINE OF TRACT "C", LINTON OAKS SQUARE, AS RECORDED IN PLAT BOOK 51, PAGE 118, OF THE PUBLIC RECORDS OF PALM BEACH COUNTY FLORIDA.
6. IT IS A VIOLATION OF THE STANDARDS OF PRACTICE RULE 5J-17 OF THE FLORIDA ADMINISTRATIVE CODE TO ALTER THIS SURVEY WITHOUT THE EXPRESS PRIOR WRITTEN CONSENT OF THE SURVEYOR. ADDITIONS AND/OR DELETIONS MADE TO THE FACE OF THIS SURVEY WILL MAKE THIS SURVEY INVALID.
7. THIS SURVEY IS CLASSIFIED AS COMMERCIAL/HIGH RISK AND EXCEEDS THE MINIMUM RELATIVE DISTANCE ACCURACY OF 1 FOOT IN 10,000 FEET AS REQUIRED BY THE STANDARDS OF PRACTICE (5J-17, F.A.C.). THE ACCURACY OBTAINED BY MEASUREMENT AND CALCULATION OF A CLOSED GEOMETRIC FIGURE WAS FOUND TO EXCEED THIS REQUIREMENT.
8. THE INTENDED DISPLAY SCALE OF THIS SURVEY IS 1" = 20' OR SMALLER.
9. THE EXPECTED VERTICAL ACCURACY OF THE INFORMATION SHOWN HEREON IS +/- 0.02' FOR HARD SURFACE ELEVATIONS AND 0.1' FOR SOFT SURFACE ELEVATIONS. THE EXPECTED HORIZONTAL LOCATION ACCURACY IS +/- 0.1'.
10. HORIZONTAL FEATURE LOCATION IS TO THE CENTER OF THE SYMBOL WHICH MAY HAVE BEEN ALTERED FOR CLARITY. ALL MAPPED FEATURES SHOWN HEREON WERE OBTAINED BY KEITH & ASSOCIATES, INC. FOR THE PURPOSE OF THIS SURVEY. DISTANCES SHOWN HEREON ARE IN U.S. FEET.
11. THE HORIZONTAL DATUM FOR THIS SURVEY IS THE NORTH AMERICAN DATUM OF 1983 WITH THE NATIONAL SPATIAL REFERENCE SYSTEM 2011 ADJUSTMENT APPLIED (83/NSRS2011), TRANSVERSE MERCATOR, FLORIDA EAST ZONE.
12. ELEVATIONS SHOWN HEREON ARE BASED ON THE NORTH AMERICAN VERTICAL DATUM OF 1988 (NAVD 1988). SAID ELEVATIONS ARE BASED ON PALM BEACH COUNTY BENCHMARKS IMAGE, A PALM BEACH COUNTY BRASS DISK IN CONCRETE MONUMENT, TO REACH THE STATION, PROCEED TO ITS LOCATION 1/2 MILE SOUTH OF LINTON BOULEVARD ON THE WEST SIDE OF MILITARY TRAIL. THE STATION IS A PALM BEACH COUNTY BRASS DISK SET IN CONCRETE STAMPED "IMAGE". THE STATION IS LOCATED 370 FEET NORTH OF THE CENTERLINE ENTRANCE TO BEL AIRE SUBDIVISION, 49.8 FEET SOUTH OF A JOG IN THE WALL FOR SAID SUBDIVISION, 23.0 FEET EAST OF SAID WALL AND 5.0 FEET EAST OF A CABBAGE PALM WITH A WITNESS SIGN. ELEVATION=17.907' AND BENCHMARK L-38 MIL, A PALM BEACH COUNTY BRASS DISK IN CONCRETE MONUMENT, TO REACH THE STATION, PROCEED TO ITS LOCATION AT THE INTERSECTION OF MILITARY TRAIL AND THE L-38 CANAL IN BOCA RATON. THE STATION IS A PALM BEACH COUNTY BRASS DISK STAMPED "L-38 MIL", SET IN THE NORTH END OF THE CONCRETE PARAPET ON THE WEST SIDE OF THE SOUTHBOUND LANES OF THE MILITARY TRAIL BRIDGE OVER THE L-38 CANAL. ELEVATION=22.253'
13. THE OWNERSHIP OF FENCES AND WALLS SHOWN HEREON ARE NOT KNOWN AND THUS ARE NOT LISTED AS ENCROACHMENTS.
14. THE SUBJECT PROPERTY DOES NOT LIE WITHIN SPECIAL FLOOD HAZARD AREAS AS DEFINED BY THE FEDERAL EMERGENCY MANAGEMENT AGENCY. THE ENTIRE PROPERTY LIES WITHIN FLOOD HAZARD ZONE X AREA OUTSIDE OF 0.2% ANNUAL CHANCE FLOOD HAZARD, AS SHOWN ON FLOOD INSURANCE RATE MAP NO. 12099C0978F WITH A DATE OF IDENTIFICATION OF OCTOBER 5, 2017, FOR COMMUNITY NO. 125102, IN CITY OF POMPAHO BEACH, BROWARD COUNTY, STATE OF FLORIDA, WHICH IS THE CURRENT FLOOD INSURANCE RATE MAP FOR THE COMMUNITY IN WHICH THE SUBJECT PROPERTY IS SITUATED.
15. LANDS SHOWN HEREON WERE ABSTRACTED FOR RIGHTS OF WAY, EASEMENTS, OWNERSHIP, OR OTHER INSTRUMENTS OF RECORD BY STEWART TITLE GUARANTY COMPANY, TITLE POLICY NUMBER 72526-20150326, DATE AND TIME OF RECORDING OF DEED.
16. THE INSTRUMENT RECORDED IN OFFICIAL RECORDS BOOK 4677, PAGE 4, BROWARD COUNTY PUBLIC RECORDS GRANTS A NON-EXCLUSIVE EASEMENTS FOR ACCESS, UTILITIES AND STORM SEWER LINE FOR THE BENEFIT OF TRACT "C", HOWEVER THESE EASEMENTS ARE UNABLE TO BE SHOWN HEREON AS THE RECORD DOCUMENT IS NOT LEGIBLE.

CERTIFICATION:

I HEREBY CERTIFY THAT THE ATTACHED BOUNDARY AND TOPOGRAPHIC SURVEY OF THE HEREON DESCRIBED PROPERTY IS DEPICTED TO THE BEST OF MY KNOWLEDGE AND BELIEF AND THE INFORMATION AS SURVEYED UNDER MY DIRECTION ON NOVEMBER 22, 2017 MEETS THE STANDARDS OF PRACTICE RULE 5J-17 OF THE FLORIDA ADMINISTRATIVE CODE, PURSUANT TO SECTION 472.027, FLORIDA STATUTES, SUBJECT TO THE QUALIFICATIONS NOTED HEREON.

KEITH & ASSOCIATES, INC.
CONSULTING ENGINEERS

LEE POWERS
PROFESSIONAL SURVEYOR AND MAPPER
REGISTRATION NO. 6805
STATE OF FLORIDA

LEGAL DESCRIPTION:

TRACT "C", LINTON OAKS SQUARE, ACCORDING TO THE MAP OR PLAT THEREOF AS RECORDED IN PLAT BOOK 51, PAGE 118, OF THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA.

SAID LANDS LYING IN THE CITY OF DELRAY BEACH, PALM BEACH COUNTY, FLORIDA AND CONTAINING 40,559 SQUARE FEET OR 0.931 ACRES MORE OR LESS.



301 East Atlantic Boulevard
Pompano Beach, Florida 33060-6643

2160 NW 82nd Avenue
Doral, Florida 33122

O: (954) 788-3400 F: (954) 788-3500

Florida Certificate of
Authorization # - 6860

BID / CONTRACT NO. :

REVISIONS

NO.	DESCRIPTION	DATE
1	TITLE WORK	12/5/17
2	ADD VAULT & VALVE	02/12/18
3	ADD CITY TO LEGAL	05/23/18

PRELIMINARY PLAN
NOT FOR CONSTRUCTION

THESE PLANS ARE NOT FULLY PERMITTED AND ARE SUBJECT TO REVISIONS MADE DURING THE PERMITTING PROCESS. RESPONSIBILITY FOR THE USE OF THESE PLANS PRIOR TO OBTAINING PERMITS FROM ALL AGENCIES HAVING JURISDICTION OVER THE PROJECT WILL FALL SOLELY UPON THE USER.



#34798
16000 S. MILITARY TRAIL
DELRAY BEACH, FLORIDA
33484

SCALE: 1"=20'

DATE ISSUED: NOVEMBER 22, 2017

DRAWN BY: DDB

DESIGNED BY: N/A

CHECKED BY: LP




SHEET TITLE

BOUNDARY &
TOPOGRAPHIC
SURVEY

SHEET NUMBER

SHEET 1 of 1

PROJECT NO. 09725.24



SITE DATA TABLE

PROJECT ADDRESS 16000 S. MILITARY TRAIL, DELRAY BEACH			
PROJECT INFORMATION			
LAND USE DESIGNATION		COMMERCIAL (C)	
ZONING DESIGNATION		PLANNED COMMERCIAL (PC)	
OVERLAY ZONE		MEDICAL ARTS OVERLAY	
TYPE OF USE		CONVENIENCE MART (GASOLINE STATION WITH FOOD SALES)	
HOURS OF OPERATION		24-HOUR OPERATION	
FOLIO NUMBER		12-42-46-25-10-003-000	
GROSS SITE AREA		40,559 SFT	0.93 AC
ROW TAKING AREA		2,033 SFT	0.04 AC
NET SITE AREA		38,526 SFT	0.89 AC
ZONING DISTRICT REQUIREMENTS			
PROPOSED BUILDING HEIGHT		REQUIRED 48' MAX.	PROVIDED 20 FT
PERVIOUS AREA		25%	30%
FLOOR AREA (LOT COVERAGE)		6,000 SF	2,538 SF
* - Waiver requested for reduction in floor area requirement			
SETBACK REQUIREMENTS			
PROPOSED BUILDING		REQUIRED	PROVIDED
FRONT YARD (Linton Blvd.)		10 FT	40.92 FT
INTERIOR SIDE YARD (East)		0 FT	134.74 FT
STEET SIDE YARD (S. Military Tr.)		10 FT	22 FT
REAR YARD (South)		10 FT	117.67 FT
FUEL CANOPY AND TANK			
FUEL CANOPY SETBACK		15 FT	34.67 FT
FUEL TANK SETBACK		15 FT	21.85 FT
LANDSCAPE BUFFERS			
		REQUIRED	PROVIDED
FRONT YARD (Linton Blvd.)		18.24 FT	18.24 FT
INTERIOR SIDE YARD		10 FT	10 FT
STEET SIDE YARD (S. Military Tr.)		16.98 FT	17 FT
REAR YARD		10 FT	10 FT
SITE AREA CALCULATIONS			
		SQ. FT.	% ACRE
NET SITE AREA		38,526	100% 0.88
PERVIOUS AREA/OPEN SPACE		11,666	30% 0.27
IMPERVIOUS AREA (Lot coverage + paved areas)		26,860	70% 0.62
TOTAL		38,526	100% 0.88
PARKING REQUIREMENTS			
SERVICE STATION REQUIREMENT		4.5 PER 1000 S.F. OF GROSS FLOOR AREA	
TOTAL PARKING REQUIRED		12	
PROPOSED PARKING PROVIDED		21 (INCLUDES 1 ADA)	

LEGAL DESCRIPTION:

TRACT "C", LINTON OAKS SQUARE, ACCORDING TO THE MAP OR PLAT THEREOF AS RECORDED IN PLAT BOOK 51, PAGE 118, OF THE PUBLIC RECORDS OF PALM BEACH COUNTY, FLORIDA.

SAID LANDS LYING IN THE CITY OF DELRAY BEACH, PALM BEACH COUNTY, FLORIDA AND CONTAINING 40,559 SQUARE FEET OR 0.931 ACRES MORE OR LESS.

NOTES:

- THIS SITE PLAN IS BASED ON A SURVEY BY KEITH AND ASSOCIATES
- REFER TO SURVEY FOR EXISTING SPOT ELEVATIONS
- REFER TO SHEET CP-101 FOR PROPOSED SPOT ELEVATIONS
- REFER TO ARCHITECTURAL PLANS FOR CONSTRUCTION AND OCCUPANCY CLASSIFICATION



301 East Atlantic Boulevard
Pompano Beach, FL 33060

PH: (954) 788-3400

Florida Certificate of
Authorization # - 7928

BID / CONTRACT NO. :

REVISIONS

NO.	DESCRIPTION	DATE
1	RESUBMITTAL	1/11/2019

**PRELIMINARY PLAN
NOT FOR CONSTRUCTION**
THESE PLANS ARE NOT FULLY PERMITTED
AND ARE SUBJECT TO REVISIONS MADE
DURING THE PERMITTING PROCESS.
RESPONSIBILITY FOR THE USE OF THESE
PLANS PRIOR TO OBTAINING PERMITS
FROM ALL AGENCIES HAVING JURISDICTION
OVER THE PROJECT WILL FALL SOLELY
UPON THE USER.



#34798
16000 S. MILITARY TRAIL
DELRAY BEACH, FL 33484

SCALE: AS NOTED
DATE ISSUED: FEBRUARY 2018
DRAWN BY: AM
DESIGNED BY: AM
CHECKED BY: TD

THOMAS F. DONAHUE, P.E.
FLORIDA REG. NO. 60529
(FOR THE FIRM)

SHEET TITLE



SITE PLAN

SHEET NUMBER

SP-101

PROJECT NO. **09725.24**

BIM 360://34798 DELRAY BEACH FL @ 1600 S Military Trail (18033)/18033 Delray Beach FL_A_R16.rvt 1/9/2019 10:32:34 AM



1 FLOOR PLAN
R0.01 1/4" = 1'-0"

bates

106 N 37TH STREET, SUITE C
ROGERS, ARKANSAS 72756
WWW.BATESARCHITECTS.COM
TEL: 479.633.8165

Florida Certificate of Authority #AA26003602

Copyright 2019 Bates & Associates, Architects

Drawings and Specifications as instruments of service are and shall remain the property of the Architect. They are not to be used on other projects or extensions to this project except by agreement in writing and with appropriate compensation to the Architect.

Contractor is responsible for confirming and correlating dimensions at job site. The Architect will not be responsible for construction means, methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the project.

STORE #:

34798

CONSTRUCTION MANAGER

CREIGHTON CONSTRUCTION & MANAGEMENT, LLC
900 SW PINE ISLAND ROAD, SUITE 202
CAPE CORAL, FL 33991

TENANT


7-ELEVEN INC.
3200 HACKBERRY ROAD, IRVING, TX 75063

PROTO:08/21/17

7-ELEVEN STORE
1600 S. MILITARY TRAIL
DELRAY BEACH, FL 33496

CREIGHTON CONSTRUCTION & MANAGEMENT, LLC

900 SW PINE ISLAND ROAD, SUITE 202
CAPE CORAL, FL 33991



Ryan M. Faust, License # AR97905
Expiration Date: February 28, 2019
01/09/2019

Architect Name - RYAN M FAUST

Architect Number - AR97905

THE SEAL AND SIGNATURE APPLY ONLY TO THE DOCUMENT TO WHICH THEY ARE AFFIXED AND WE EXPRESSLY DISCLAIM ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER DOCUMENTS OR INSTRUMENTS RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT.


REVISIONS
NO. DATE DESCRIPTION

PROJECT NUMBER: 18033
RELEASE DATE: 01/09/2019


REVIEW BOARD FLOOR PLAN

R0.01


1/9/2019 10:51:31 AM
E
D
C
B
A
BIM 360://34798 DELRAY BEACH FL @ 1600 S Military Trail (18033)/18033 Delray Beach FL_A_R16.rvt




7 FUEL CANOPY - SHORT ELEVATION
3/16" = 1'-0"




6 FUEL CANOPY - LONG ELEVATION
3/16" = 1'-0"



5 ELEVATION - FACING NORTH
3/16" = 1'-0"



4 ELEVATION - FACING WEST
3/16" = 1'-0"




3 ELEVATION - FACING NORTHEAST
3/16" = 1'-0"


2 ELEVATION - FACING SOUTH EAST
3/16" = 1'-0"

NOTE: ALL CANOPY & BUILDING DOWNSPOUTS SHALL BE PIPED THRU/UNDER SIDEWALKS AS REQUIRED. PROVIDE CONTROL JOINT TO MINIMIZE CRACKING.

1 ELEVATION - FACING NORTHEAST 2
3/16" = 1'-0"



9 SIDE ELEVATION - DUMPSTER ENCLOSURE
3/16" = 1'-0"



8 FRONT ELEVATION - DUMPSTER ENCLOSURE
3/16" = 1'-0"

EXTERIOR MATERIALS SCHEDULE		
NO.	MATERIAL	MANUF.-COLOR
MR - 1	MEMBRANE ROOFING	DUROLAST - WHITE
ST-1	PAINTED STUCCO	BALANCED BEIGE - SW 7037
ST-2	PAINTED STUCCO	AESTHETIC WHITE - SW 7035
V-1	VENEER STONE	EQUAL TO CORAL STONE BY CULTURED STONE - FOSSIL REEF
P-3	EXTERIOR HM DOORS, FRAMES, TRASH ENCLOSURE GATE, GRAVEL GUARDS, AND LIGHT POLES	SHERWIN WILLIAMS - SEAL SKIN SW 7675
P-6	EXTERIOR BOLLARDS	SHERWIN WILLIAMS - SEAL SKIN SW 7675
S-1	ALUMINUM STOREFRONT GLAZING, CAP FLASHING, DOWNSPOUTS & SCUPPERS	DARK BRONZE
C-1	PREFINISHED ALUMINUM CANOPY	AWNING WORKS OR THOMPSON AWNING - BRONZE BAKED ENAMEL W/ REAR GUTTER CONNECTIONS
FC-1	FUEL CANOPY FASCIA	REYNOLBOND CORP. - EASTMAN WHITE - PY - 25

NOTE: ALL SIGNS TO BE PROVIDED BY SIGN CONTRACTOR UNDER SEPARATE PERMIT AND REVIEW.

bates

106 N 37TH STREET, SUITE C
ROGERS, ARKANSAS 72756
WWW.BATESARCHITECTS.COM
TEL: 479.633.8165

Florida Certificate of Authority #AA23603602

Copyright 2019 Bates & Associates, Architects

Drawings and Specifications as Instruments of Service are and shall remain the property of the Architect. They are not to be used on other projects or extensions to this project except by agreement in writing and with appropriate compensation to the Architect.

Contractor is responsible for confirming and correlating dimensions at job site. The Architect will not be responsible for construction means, methods, techniques, sequences, or procedures, or for safety precautions and programs in connection with the project.

STORE #:

34798

CONSTRUCTION MANAGER

CREIGHTON CONSTRUCTION & MANAGEMENT, LLC
900 SW PINE ISLAND ROAD, SUITE 202
CAPE CORAL, FL 33991


TENANT

7-ELEVEN INC.

3200 HACKBERRY ROAD, IRVING, TX 75063

PROTO:08/21/17

7-ELEVEN STORE
1600 S. MILITARY TRAIL
DELRAY BEACH, FL 33496
CREIGHTON CONSTRUCTION & MANAGEMENT, LLC
900 SW PINE ISLAND ROAD, SUITE 202
CAPE CORAL, FL 33991



Ryan M Faust, License # AR97905

Expiration Date: February 28, 2019

01/09/2019

Architect Name - RYAN M FAUST

Architect Number - AR97905

THE SEAL AND SIGNATURE APPLY ONLY TO THE DOCUMENT TO WHICH THEY ARE AFFIXED AND WE EXPRESSLY DISCLAIM ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER DOCUMENTS OR INSTRUMENTS RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT.


REVISIONS
NO. DATE DESCRIPTION

PROJECT NUMBER: 18033
RELEASE DATE: 01/09/2019

REVIEW BOARD ELEVATIONS

R0.02

1/9/2019 10:32:47 AM
BIM 360://34798 DELRAY BEACH FL @ 1600 S Military Trail (18033)/18033 Delray Beach FL_A_R16.rvt



Ordinance Data:

	Max (FC)	Min (FC)	Max/Min	Avg/Min
Building Entrance	10.0	1.0	---	3:1
Canopy/Overhangs	30.0	3.0	10:1	2.5:1
Commercial Parking	12.0	1.0	12:1	3:1

Lighting solution should be designed in such a way to limit light spillage

Calculation Summary

Label	CalcType	Units	Avg	Max	Min
Air Pump	Illuminance	Fc	3.1	3.4	2.8
Building Entrance	Illuminance	Fc	6.5	9.4	3.6
Dumpster	Illuminance	Fc	2.5	3.9	1.4
Entry 1	Illuminance	Fc	3.4	3.5	3.1
Entry 2	Illuminance	Fc	2.1	2.6	1.6
Entry 3	Illuminance	Fc	2.3	2.4	2.1
Gas Canopy	Illuminance	Fc	21.7	26.3	16.3
General Approach	Illuminance	Fc	5.1	10.1	2.0
Parking 1	Illuminance	Fc	4.2	13.1	1.2
Parking 2	Illuminance	Fc	3.6	5.1	1.3
Property Line	Illuminance	Fc	0.3	2.5	0.0
Sidewalk	Illuminance	Fc	6.3	14.4	0.7

Luminaire Schedule

Symbol	Qty	Label	Arrangement	LLF	Description	Arr. Watts	Arr. Lum. Lumens
	2	EM	SINGLE	0.010	LEDPRS-BR-CL (Phillips)	20	32
	1	8ft Batten	SINGLE	1.000	GE 96 4100K Batten Strip GEWI109641BAT-SY	33	3073
	2	2ft Batten	SINGLE	1.000	GE 24 4100K Batten Strip GEWI102441BAT-SY	8.34	768
	2	EWS3-C7D	SINGLE	1.000	EWS3_C7D150____-120-277V	41	5000
	3	EWS3-A7D	SINGLE	1.000	EWS3_A7D150____-120-277V	25	2900
	16	ECBBB	SINGLE	1.000	ECBB0B5F5501AWHTE	64	8110
	1	EASC-H4_B	SINGLE	1.000	EASC_H4F550____ WITH ELS-EASX-FBN-BLCK	199	20600
	2	EASC-B3_B	SINGLE	1.000	EASC_B3F550____ WITH ELS-EASX-DBL-BLCK	62	7000
	1	EASC-B2_B	SINGLE	1.000	EASC_B2F550____ WITH ELS-EASX-ABL-BLCK	62	6200
	1	EASC-A4_B	SINGLE	1.000	EASC_A4F550____ WITH ELS-EASX-RBL-BLCK	44	4000
	1	SF4_R	SINGLE	1.000	1-EASA0F4F5579C Color ELS-EASX-FS2-BLCK Double Module Right	199	10767

bates

106 N 37TH STREET, SUITE C
ROGERS, ARKANSAS 72756
WWW.BATESARCHITECTS.COM
TEL: 479.633.8165

Florida Certificate of Authority #AA32603602

Copyright 2019 Bates & Associates, Architects

Drawings and Specifications as Instruments of service are and shall remain the property of the Architect. They are not to be used on other projects or extensions to this project except by agreement in writing and with appropriate compensation to the Architect.

Contractor is responsible for confirming and correlating dimensions at job site. The Architect will not be responsible for construction means, methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the project.

STORE #:

34798

CONSTRUCTION MANAGER

CREIGHTON CONSTRUCTION & MANAGEMENT, LLC
900 SW PINE ISLAND ROAD, SUITE 202
CAPE CORAL, FL 33991

TENANT


7-ELEVEN INC.
3200 HACKBERRY ROAD, IRVING, TX 75063

PROTO:08/21/17

7-ELEVEN STORE
1600 S. MILITARY TRAIL
DELRAY BEACH, FL 33496

CREIGHTON CONSTRUCTION & MANAGEMENT, LLC

900 SW PINE ISLAND ROAD, SUITE 202
CAPE CORAL, FL 33991



Ryan M Faust, License # AR97905
Expiration Date: February 28, 2019
01/09/2019

Architect Name - RYAN M FAUST
Architect Number - AR97905


THE SEAL AND SIGNATURE APPLY ONLY TO THE DOCUMENT TO WHICH THEY ARE AFFIXED AND WE EXPRESSLY DISCLAIM ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER DOCUMENTS OR INSTRUMENTS RELATING TO OR INTENDED TO BE USED FOR ANY PART OR PARTS OF THE PROJECT.

REVISIONS
NO. DATE DESCRIPTION

PROJECT NUMBER: 18033
RELEASE DATE: 01/09/2019


PRELIMINARY PHOTOMETRICS

R0.03




TREE DISPOSITION LEGEND:	
	EXISTING TREE/PALM TO REMAIN WITHOUT DISPOSITION SYMBOL
	EXISTING TREE/PALM TO RELOCATE
	REFER TO LANDSCAPE PLAN FOR NEW LOCATION
	EXISTING TREE/PALM TO REMOVE
	REMOVE ALL CAT 1 INVASIVE EXOTICS (EX: BRAZ. PEPPER)
	EXISTING TREE/PALM NUMBER
	REFER TO TREE DISPOSITION AND TREE SURVEY LISTS

- TREE DISPOSITION NOTES:**
- EXISTING TREES TO REMAIN SHALL BE TRIMMED PER ANSI-A300 STANDARDS, REMOVING WEAKEST RUBBING BRANCHES AND DEAD BRANCHES, BUT RETAINING 80% OF FOLIAGE. LARGE TREES SHALL HAVE LOWER BRANCHES CLEARED UP TO 8'.
 - SYMBOLS MAY BE SHOWN OFFSET FROM ACTUAL TREE LOCATION FOR CLARITY.
 - CONTACT LANDSCAPE ARCHITECT / ISA CERTIFIED ARBORIST FOR CLARIFICATION ON ANY DISCREPANCIES.
 - TRIMMING AND ANY NECESSARY ROOT PRUNING SHALL BE PERFORMED OR SUPERVISED BY A CERTIFIED ARBORIST.
 - ALL TREE WORK REQUIRE PERMITTING BY A REGISTERED COUNTY TREE TRIMMER.
 - BUBBLERS SHALL BE PROVIDED FOR ALL RELOCATED TREES AND PALMS.
 - REMOVAL OF ANY TREES OR PALMS WILL REQUIRE A WRITTEN "TREE REMOVAL PERMIT" FROM THE LOCAL GOVERNING AGENCY PRIOR TO REMOVAL. CONFIRM WITH LOCAL GOVERNING AGENCY THAT TREES CLASSIFIED AS NUISANCE/EXOTIC INVASIVE MAY BE EXEMPT.
 - ALL TREES AND PLANT MATERIAL TO REMAIN SHALL BE PROTECTED DURING CONSTRUCTION. REFER TO TREE PROTECTION DETAIL ON SHEET LP-501. THE CONTRACTOR SHALL TAKE EXTRA CAUTION TO PREVENT ANY DAMAGE TO THE TRUNK, ROOT ZONES AND GRADE.



LOCATION SKETCH


NOT TO SCALE



SCALE: 1"=20'

NOTE: PRINTED DRAWING SIZE MAY HAVE CHANGED FROM ORIGINAL. VERIFY SCALE USING BAR SCALE ABOVE.

PROJECT # 09725.24			PROJECT NAME: 7 ELEVEN #34798, 16000 S. MILITARY TRAIL, DELRAY BEACH, FL						
TREE #	COMMON NAME	SCIENTIFIC NAME	DBH IN.	HT. FT.	CNPY. FT.	TREE % CONDITION	TREE DISPOSITION	COMMENTS	
1	Queen Palm	"Arecastrum romanzoffianum"		24	16	40	REMOVE	CON, penciling, weak head	
2	Queen Palm	"Arecastrum romanzoffianum"		20	16	40	REMOVE	CON, penciling, weak head	
3	Queen Palm	"Arecastrum romanzoffianum"		18	16	50	REMOVE	penciling, leaning/curved, weak head	
4	Mahogany	"Swietenia mahagoni"	16			50	REMAIN	OHE, CO-D, IB, B DMG, exposed roots	
5	Cabbage Palm	"Sabal palmetto"		20	10	50	REMAIN	CON	
6	Cabbage Palm	"Sabal palmetto"		20	10	60	REMAIN		
7	Cabbage Palm	"Sabal palmetto"		20	10	50	REMAIN	CON	
8	Cabbage Palm	"Sabal palmetto"		20	10	60	REMAIN		
9	Mahogany	"Swietenia mahagoni"	13	24	20	50	REMOVE	OHE, CO-D, IB, poor branching, exposed roots	
10	Gumbo Limbo	"Bursera simaruba"	3	10	6	50	REMOVE	CO-D, WCPY	
11	Mahogany	"Swietenia mahagoni"	21	35	28	50	REMOVE	CO-D, IB, B DMG, large broken branches	
12	Cabbage Palm	"Sabal palmetto"		20	10	65	RELOCATE		
13	Cabbage Palm	"Sabal palmetto"		22	10	65	RELOCATE		
14	Cabbage Palm	"Sabal palmetto"		18	10	50	RELOCATE	narrow base	
15	Mahogany	"Swietenia mahagoni"	10	30	20	50	REMOVE	OHE, CO-D, IB, WCPY, vertical/narrow branching	
16	Mahogany	"Swietenia mahagoni"	19	20	40	45	REMOVE	OHE, utility pruned, CO-D, IB, WCPY, poor form	
17	Mahogany	"Swietenia mahagoni"	18	20	30	45	REMOVE	CO-D, IB, B DMG, partial canopy, shaded by larger tree	
18	Mahogany	"Swietenia mahagoni"	23	35	40	60	REMAIN	OHE, w ater line, exposed roots, close to paving, B DMG	
19	Mahogany	"Swietenia mahagoni"	20	35	22	50	REMAIN	OHE, CO-D, IB, w ater line, exposed roots, close to paving, poor branching	
20	Mahogany	"Swietenia mahagoni"	13	30	20	50	REMAIN	OHE, w ater line, close to paving, T DMG, CO-D, IB, B DMG	
21	Mahogany	"Swietenia mahagoni"	12	25	18	45	REMAIN	OHE, w ater line, T DMG, close to paving, CO-D, IB, poor branching	
22	Silver Trumpet	"Tabebuia caribaea"	13	20	20	40	REMOVE	OHE, w ater line, close to paving, B DMG	
23	Silver Trumpet	"Tabebuia caribaea"	15	16	22	50	REMOVE	OHE, w ater line, close to paving	
24	Mahogany	"Swietenia mahagoni"	14	28	20	40	REMOVE	OHE, w ater line, CO-D, IB, B DMG, WCPY, poor branching	
25	Bottle Brush	"Callistemon viminalis"	8	8	4	30	REMOVE	poor branching, no canopy (shaded), broken trunk	
26	Mahogany	"Swietenia mahagoni"	18	32	25	40	REMOVE	B DMG, poor branching	
27	Mahogany	"Swietenia mahagoni"	5	14	6	30	REMOVE	CO-D, IB, WCPY, poor form, (shaded)	
28	Mahogany	"Swietenia mahagoni"	6	15	7	30	REMOVE	T DMG, B DMG, WCPY, poor form, (shaded)	
29	Mahogany	"Swietenia mahagoni"	14	22	25	40	REMOVE	T DMG, B DMG, WCPY, poor branching	
30	Bottle Brush	"Callistemon viminalis"	4	10	4	30	REMOVE	poor branching, no canopy (shaded)	
31	Queen Palm	"Arecastrum romanzoffianum"		20	12	20	REMOVE	T DMG, severe leaning, weak head	
32	Christmas Palm	"Veitchia merillii"		16	10	80	REMAIN	triple trunk	
33	Christmas Palm	"Veitchia merillii"		16	10	80	REMAIN	triple trunk	
34	Christmas Palm	"Veitchia merillii"		16	10	80	REMAIN	triple trunk	
35	Black Olive	"Bucida buceras"	17	40	20	60	REMOVE	T DMG, B DMG, partial canopy	
36	Black Olive	"Bucida buceras"	10	18	18	50	REMOVE	CO D, IB, T DMG, sucker growth, partial canopy	
37	Black Olive	"Bucida buceras"	21	28	35	45	REMOVE	CO D, IB, T DMG, B DMG, partial canopy	
38	Black Olive	"Bucida buceras"	20	30	35	50	REMOVE	CO D, IB, T DMG, B DMG, partial canopy	
39	Live Oak	"Quercus virginiana"	22	25	35	50	REMOVE	CO D, IB, small root area, close to paving, B DMG, shared canopy	
40	Live Oak	"Quercus virginiana"	21&17	28	35	60	REMOVE	CO D, B DMG, low lateral branch, fungal conks, shared canopy	
41	Queen Palm	"Arecastrum romanzoffianum"		24	15	50	REMOVE	T DMG, leaning	
Tree Mitigation Table									
55 "			Total DBH to be removed (greater than 50% condition rating)						
19			Total Trees to be removed (50% condition rating or less)						
Replacement Trees									
55 "			Total Caliper inches proposed (10 - 4" caliper trees)						



TEMPORARY TREE PROTECTION DETAIL

PLAN / SECTION

NOT TO SCALE



301 East Atlantic Boulevard
Pompano Beach, FL 33060

PH: (954) 788-3400

Florida Certificate of
Authorization # - 7928

BID / CONTRACT NO. :

REVISIONS

NO.	DESCRIPTION	DATE
1	SITE PLAN REVISION	01/11/19

**PRELIMINARY PLAN
NOT FOR CONSTRUCTION**
THESE PLANS ARE NOT FULLY PERMITTED
AND ARE SUBJECT TO REVISIONS MADE
DURING THE PERMITTING PROCESS.
RESPONSIBILITY FOR THE USE OF THESE
PLANS PRIOR TO OBTAINING PERMITS
FROM ALL AGENCIES HAVING JURISDICTION
OVER THE PROJECT WILL FALL SOLELY
UPON THE USER.



#34798
16000 S. MILITARY TRAIL
DELRAY BEACH, FL 33484

SCALE: AS NOTED
DATE ISSUED: FEBRUARY 2018
DRAWN BY: SR
DESIGNED BY: MP
CHECKED BY: MP



MICHAEL J. PHILLIPS, RLA
FLORIDA REG. NO. LA0001540
(FOR THE FIRM)

SHEET TITLE
**TREE DISPOSITION
PLAN**


SHEET NUMBER
LD-101

SHEET of 27

PROJECT NO. 09725.24




GRAPHIC SCALE



SCALE: 1"=20'

NOTE: PRINTED DRAWING SIZE MAY HAVE CHANGED FROM ORIGINAL. VERIFY SCALE USING BAR SCALE ABOVE.



LOCATION SKETCH

NOT TO SCALE

PLANT LIST

TREES AND PALMS		
KEY	QUANTITY	PLANT NAME AND SPECIFICATION
** BB	6	Bucida buceras 'Shady Lady' (Black Olive) 16' ht., 7' spr., 4" c., full canopy
** LIG	2	Ligustrum japonicum (Japanese Privet) 12' ht., 5' spr., 3" c., full canopy
** PE	11	Ptychosperma elegans (Solitaire Palm) 12'-14' c.t. hts., staggered, single
** N QV	4	Quercus virginiana (Live Oak) 16' ht., 7' spr., 4" c., full canopy
** N SP	6	Sabal palmetto (Cabbage Palm) 12'-26' staggered d. hts.
** N Spr	3	Sabal palmetto (Cabbage Palm) Relocated from site
** TI	3	Tabebuia impetiginosa (Purple Trumpet) 12' ht., 6' spr., 3" c., full canopy

SHRUBS & GROUNDCOVERS		
KEY	QUANTITY	PLANT NAME AND SPECIFICATION
** N CHR	35	Chrysobalanus icaco (Cocoplum) 24" ht., 24" spr., full, 2' o.c.
CRI	6	Cinnam. asiaticum (Cinnam. Lily) 36" ht., 36" spr., full, triple
CSP	99	Codiaeum v. 'Sloppy Painter' (Yellow Croton) 20" ht., 20" spr., full, 2' o.c.
** FGI	260	Ficus m. 'Green Island' 12" ht., 14" spr., full, 18" o.c.
** N FOR	30	Foresiera segregata (Florida Privet) 9' ht., 30" spr., full, 2' o.c.
** JAS	155	Jasminum volubile (Wax Jasmine) 18" ht., 18" spr., full, 18" o.c.
** LAM	125	Lantana montivdensis (Trailing Lantana) 10" ht., 16" spr., full, 18" o.c.
** N MUH	185	Muhlenbergia capillaris (Muhly Grass) 24" ht., 24" spr., full, 3' o.c.
** N MYF	3	Myrcianthes fragrans (Simpson's Stopper) 8' ht., 5' spr., full canopy, multi-stem
** N NEP	220	Nephrolepis exalta (Sword Fern) 12" ht., 14" spr., 2' o.c.
TAB	76	Tabernaemontana spp. (Pinwheel Jasmine) 24" ht., 24" spr., full, 2' o.c.
** TRA	150	Trachelospermum asiaticum 'minima' (Asiatic Jasmine) 12" ht., 14" spr., 12" o.c.

- N DENOTES NATIVE SPECIES
** DENOTES HIGH DROUGHT TOLERANT SPECIES
* DENOTES MODERATE DROUGHT TOLERANT SPECIES

NOTES

Sod to be St. Augustine 'Floratum', contractor to determine quantity.

All sod and landscape to receive 100% coverage with 50% overlap from an automatic irrigation system using an approved water source.

Bubblers to be provided for large trees and palms.

Contractor is responsible for all conditions and landscape specification attached to this plan and plant list. Plan and specifications shall be considered Contract Documents.

Pre-Construction meeting is required before any plant material is installed on site.

All road rock, concrete, asphalt and other non-natural material be removed and be replaced with planting soil prior to landscape installation.

Any trees or shrubs placed within water, sewer or drainage easements shall conform to the City of Delray Beach Standard Details; LD 1.1 and LD 1.2.

CITY OF DELRAY BEACH - LANDSCAPE REQUIREMENTS			
[DELRAY BEACH, LAND DEVELOPMENT REGULATIONS, SECTION 4.6.16 LANDSCAPE REGULATIONS]			
[SEC. 4.6.16.H.3 - MULTI-FAMILY, COMMERCIAL, INDUSTRIAL]			
PERIMETER LANDSCAPE AREA [Sec. 4.6.16.H.3.a]		REQUIRED	PROVIDED
ADJACENT TO PUBLIC AND PRIVATE RIGHTS OF WAY			
REQUIRED LANDSCAPE:			
GREEN SPACE REQUIRED:		10,526	14,644
(DEPTH OF BUFFERS x LENGTH)			
1 TREE REQUIRED PER 30 L.F.		623	18
PROVIDED BREAKDOWN:			
5 EXISTING TREES			
9 SHADE TREES			
0 COCONUT / ROYAL PALMS			
0 EXISTING PALM GROUPS			
4 PROPOSED PALM GROUPS			
29% % PALM TREES (50% MAX)			
Interior Landscape Area [Sec. 4.6.16.H.3.g]		REQUIRED	PROVIDED
REQUIRED LANDSCAPE:			
TOTAL PAVED AREA:		16,657	
MIN. 10% TO BE LANDSCAPING		1,666	2,919
1 TREE REQUIRED PER 125 S.F. REQUIRED INTERIOR LANDSCAPE		13	13
PROVIDED BREAKDOWN:			
0 EXISTING TREES			
9 SHADE TREES			
0 COCONUT / ROYAL PALMS			
3 EXISTING PALM GROUPS			
1 PROPOSED PALM GROUPS			
30% % PALM TREES (25% MAX)			
XERISCAPE CALCULATIONS:		REQUIRED	PROVIDED
REQUIRED LANDSCAPE:			
REQUIRED SHRUBS AND GROUNDCOVERS:		3,657	6,001
(30% REQUIRED INTERIOR + PERIMETER GREEN SPACE)			
REQUIRED NATIVE SHRUB MATERIALS:		914	2,220
(25% REQUIRED SHRUBS & GROUNDCOVERS)			
REQUIRED NATIVE TREES:		17	17
(50% REQUIRED TREES)			
* INCLUDES EXISTING TREES			



301 East Atlantic Boulevard
Pompano Beach, FL 33060

PH: (954) 788-3400

Florida Certificate of
Authorization # - 7928

BID / CONTRACT NO. :

REVISIONS

NO.	DESCRIPTION	DATE
1	SCREEN LP STORAGE	08/14/18
2	SITE PLAN REVISION	01/11/19
3	DUMPSTER RELOCATION	02/15/19

PRELIMINARY PLAN
NOT FOR CONSTRUCTION

THESE PLANS ARE NOT FULLY PERMITTED
AND ARE SUBJECT TO REVISIONS MADE
DURING THE PERMITTING PROCESS.
RESPONSIBILITY FOR THE USE OF THESE
PLANS PRIOR TO OBTAINING PERMITS
FROM ALL AGENCIES HAVING JURISDICTION
OVER THE PROJECT WILL FALL SOLELY
UPON THE USER.



#34798

16000 S. MILITARY TRAIL
DELRAY BEACH, FL 33484

SCALE: AS NOTED

DATE ISSUED: FEBRUARY 2018

DRAWN BY: SR

DESIGNED BY: MP

CHECKED BY: MP

MICHAEL J. PHILLIPS, RLA
FLORIDA REG. NO. LA0001540
(FOR THE FIRM)

SHEET TITLE

LANDSCAPE
PLAN

SHEET NUMBER

LP-101

SHEET of 27

PROJECT NO. 09725.24