

SECTION 129300 SITE FURNISHINGS

PART 1 - GENERAL

1.1 SUMMARY

- A. Section Includes:
 - 1. Site furnishings.

1.2 SUBMITTALS

- A. Product Data: For products indicated.
- B. Samples for Verification: For exposed finish required for site furnishings indicated, prepared on Samples of size indicated below.
 - 1. Size: Not less than 4-inch- square sheet components.
- C. Product Schedule: For site furnishings. Use same designations indicated on Drawings.
- D. Maintenance Data: For site furnishings.

1.3 QUALITY ASSURANCE

- A. Source Limitations: Obtain each type of site furnishing(s) through one source from a single manufacturer.

PART 2 - PRODUCTS

2.1 SITE FURNISHINGS

- A. Products and Manufacturer

Benches (w/ Back and Deterrent Bar); **RLS Lighting** 635 NW 4th Avenue Fort Lauderdale, FL 33311 ph: 954-458-0345 e-mail: info@RLSlighting.com

Bike Rack: **The Park Catalog**
ph: 888-447-7758 e-mail: Carrie.G@highlandproductsgroup.com

2.2 FABRICATION

- A. Factory Assembly: Assemble components in the factory to greatest extent possible to minimize field assembly. Clearly mark units for assembly in the field.

2.3 FINISHES, GENERAL

- A. Appearance of Finished Work: Variations in appearance of abutting or adjacent pieces are acceptable if they are within one-half of the range of approved Samples. Noticeable variations in the same piece are not acceptable. Variations in appearance of other components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas and conditions, with Installer present, for compliance with requirements for correct and level finished grade, mounting surfaces, installation tolerances, and other conditions affecting performance.
 - 1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

- A. Comply with manufacturer's written installation instructions unless more stringent requirements are indicated. Complete field assembly of site furnishings where required.
- B. Unless otherwise indicated, install site furnishings after landscaping and paving have been completed.
- C. Install site furnishings level, plumb, true, and securely anchored and positioned at locations indicated on Drawings.
- D. Install site lighting in accordance with manufacturer's instructions and recommendations.

3.3 CLEANING

- A. After completing site furnishing installation, inspect components. Remove spots, dirt, and debris. Repair damaged finishes to match original finish or replace component.

END OF SECTION 129300