

- 2. Contractor is responsible to verify all plant quantities and contact Landscape Architect if discrepancy exists.
- 3. Drought tolerance is per "SFWMD Waterwise -South Florida Edition" or University of Florida IFAS Extension Service, as applicable.

Copies of FDOT permits for landscape improvements within the FDOT right of way must be submitted to the city prior to the commencement of construction of said improvements.

- Rootbarrier as manufactured by (or equal)-DeepRoot Green Infrastructure, LLC 101 Montgomery Street, Suite 2850 San Francisco, CA 94104
- info@deeproot.com Tel: 415 781 9700 2. Root barrier shown is in addition to those that may be required pursuant to City of Delray Beach requirements-Any trees or shrubs placed within water, sewer, or drainage easements shall conform to the City of Delray Beach
- Standard Details; LD1.1 & LD 1.2 (see LP-8). 3. All prohibited plant species shall be eradicated from the development site and reestablishment of prohibited species shall not be permitted.


Plant Key

TREES RELOCATED FROM PHASE II AREA See also plan "TREES & PALMS FOR RELOCATION TO PHASE I"

Plan Symbol	Botanic Name / Common Name Specification	
#19	Adonidia merrillii / Christmas Palm 5 trunks	
#31	Wodyetia birfurcata / Foxtail Palm triple trunk	

⚠ Sheet Revision Summary Added Trees to be relocated from PH II area

- Updated S. Atlantic plantings to match final FDOT permit
- updated & added additional plantings around Bldg 1



Sheet Key



Ssing Florida Plan <u>S</u> andscap Atlantic

06-25-13 Scale As Noted c12103 PN#



