

## **General Notes**


plants on all sides. Size of plants shall be the same as specified in the Plant List. provided to the contractor of appropriate soil mixture specification to be used. occupancy.

Certificate of Occupancy. Tree in the Right Place' on new (proposed) plantings. Uniform Fire Code Florida Edition 18.3.4.1 Hydrants. between three (3) feet and six (6) feet measured above the grade level. 10. Refer to the specifications for planting soil requirements.

## Irrigation Statement


PLANT LIST							
QTY TREES	SYM	SPECIES	COMMON NAME/DESCRIPTION	SIZE	SPACING	REMARKS	WATER
40	CD*	COCCOLOBA DIVERSIFOLIA	PIGEON PLUM	16' x 7', 3" CAL	A.S.	FULL CANOPY, 8' C.T. MIN.	LOW
8	CR*	CLUSIA ROSEA	PITCH APPLE	16' x 7', 3" CAL	A.S.	FULL CANOPY, 8' C.T. MIN.	LOW
34	CS*	CONOCARPUS ERECTUS VAR. SERICEUS	SILVER BUTTONWOOD	10' x 6', 3" CAL	A.S.	FULL CANOPY, LIMB UP 4', MULTI-STEM	LOW
8	CU*	COCOLOBA UVIFERA	SEAGRAPE	16' x 7', 3" CAL	A.S.	FULL CANOPY, 8' C.T. MIN.	LOW
44	PE*	PINUS ELLIOTTI	SLASH PINE	16' x 7', 3" CAL	A.S.	FULL CANOPY, 4.5' C.T. MIN.	LOW
21	QV*	QUERCUS VIRGINIANA	LIVE OAK	16' x 7', 3" CAL	A.S.	FULL CANOPY, 8' C.T. MIN.	LOW
SMALL A	ACCENT	TREES					
8	TG	TIBOUCHINA GRANULOS	TIBOUCHINA STANDARD	8' x 4', 1" CAL	A.S.	FULL CANOPY, LIMB UP 3'	LOW
PALMS							
3	PC	PHOENIX CANARIENSIS	CANARY ISLAND DATE PALM	12' C.T.	A.S. C	LEAN SYMMETRICAL FAT STRAIGHT TRUNKS, MATCHED	LOW
3	PS	PHOENIX SYLVESTRIS	WILD DATE PALM/SYLVESTER	12' C.T.	A.S. C	LEAN SYMMETRICAL FAT STRAIGHT TRUNKS, MATCHED	LOW
3	BN	BISMARCKIA NOBILIS	BISMARCK PALM	16' C.T.	A.S.	FAT STRAIGHT TRUNKS, MATCHED	LOW
10	RE*	ROYSTONEA ELATA	FLORIDA ROYAL PALM	16' C.T.	A.S.	FAT STRAIGHT TRUNKS	LOW
46	SP*	SABAL PALMETTO	SABAL PALM	SEE PLAN	A.S.	SLICK TRUNKS	LOW
LARGE	HEDGE						
31	СМ	CARYOTA MITIS	FISHTAIL PALM	15' O.A.	5' O.C.	FULL TO BASE	MEDIU
SHRUBS	6 / GROU	ND COVERS	GA	ALLONS/HEIGHT/SPF	READ		
433	CES*	CONOCARPUS ERECTUS VAR. SERICEUS	SILVER BUTTONWOOD	#3, 2' x 2'	2' O.C.	FULL & THICK	LOW
1,033	CHI*	CHRYSOBALANUS ICACO	COCOPLUM	#3, 2' x 2'	2' O.C.	FULL & THICK	LOW
6 520	CUP DUR	CUPRESSUS SEMPERVIRENS DURANTA ERECTA	ITALIAN CYPRESS GOLDEN DEWDROP	#35, 14' x 2' #3, 1' x 1.5'	A.S. 2' O.C.	FULL & THICK, MATCHED, SPECIMENS FULL & THICK	LOW MEDIL
875	FGI	FICUS MICROCARPA 'GREEN ISLAND'	GREEN ISLAND FICUS	#3, 1 x 1.5 #3, 1' x 1.5'	2 0.C. 2' 0.C.	FULL & THICK	MEDI
315		HAMELIA PATENS	FIREBUSH	#3, 2' x 2'	2' O.C.	FULL & THICK	LOW
505	ILV*	ILEX VOMITORIA	DWARF YAUPON HOLLY	#3, 1' x 1.5'	2' O.C.	FULL & THICK	LOW
185	MUC*	MUHLENBERGIA CAPILARIS	MUHLY GRASS	#3, 2' x 2'	2' O.C.	FULL & THICK	LOW
28 310	MYR* NEB*	MYRICANTHES FRAGRANS NEPHROLEPIS EXALTATA	SIMPSON STOPPER BOSTON FERN	#7, 4' x 2' #1, 1' x 1'	2' O.C. 2' O.C.	FULL & THICK FULL & THICK	LOW LOW
310	SOD	STENOTAPHRUM SECUNDATUS	ST. AUGUSTINE SOD	#1, I A I	2 0.0.	SEE SPECS.	MEDIL
		* = FLORIDA NATIVE					

Tree Replacement Note




- 1. All utility boxes and structures, air conditioners, etc., not currently known or shown on the plan, shall be screened with Cocoplum 2. Contractor to include drainage testing for all trees and palms in bid. If drainage is inadequate and the soil specification in item #8 of the landscape specifications is not appropriate for site conditions, the soil mixture shall be revised for this site's conditions. The Contractor shall notify the Owner and Landscape Architect of the poor drainage conditions in writing and written direction will be
- 3. All prohibited, exotic and invasive species shall be removed from the entire site area of site prior to issuance of certificate of
- 4. All required landscape improvements must be inspected and approved by the City of Delray Beach prior to the issuance of a
- 5. This plan has been designed to meet with the tree planting requirements contained within the FPL document entitled 'Plant the Right 6. Planting adjacent to fire hydrants shall have a minimum clear radius of 7.5' front and sides and 4' in the rear as required by the NFPA
- 7. No plant substitutions can be made without Owner's and the City of Delray Beach's approval. 8. Trees and palms shall have limbs or foliage trimmed in such a manner that no limbs or foliage extend into the sight visibility triangle
- 9. Existing native soil within all landscape islands, interior landscape strips and perimeter landscape strips, adjacent to vehicular use areas, shall be excavated down to a depth of thirty (30) inches below existing grade, except for a 12" buffer from the inside of curb or pavement. A suitable planting soil mixture of fifty/fifty (50/50), sixty/forty (60/40) (sand/topsoil) or as otherwise indicated by the Registered Landscape Architect (see specifications), shall either be backfilled in place of the native soil or efficiently mixed with the native soil to create an optimum environment for successful root development. If native soil is to be mixed, it shall first be screened to remove rocks and debris larger than one-half (1/2) inch in diameter prior to mixing. All properties under this section shall be required to have an open landscape bed inspection prior to backfilling to insure the thirty (30) inch depth has been met. See detail below.
- 11. Any trees or shrubs placed within water, sewer or drainage easements shall conform to the City of Delray Beach Standard Details LD1.1 & LD 1.2. See details on detail sheet.

The irrigation source shall be reclaimed water if available; if not it will either be potable water or a well. All planting areas shall be irrigated to provide 100% coverage and provide adequate irrigation of landscape areas for the first full growing season and continue thereafter only as necessary to maintain required vegetation in good and healthy condition. The irrigation system shall be continuously maintained in working order. An automatic Rain sensor shall be placed on-site as part of the required irrigation system. Shop drawings shall be submitted by the irrigation contractor for approval prior to installation.



All trees which are to be preserved and do not survive shall be replaced by a tree of equal size or an equivalent number of trees based on trunk



JWS

SCALE

FILE No.

HEET

JS

DESIGN DRAWN CHKD

JOB No. CDG 16-1003 BOWMAN 010463-01-00

L-1 <sup>OF</sup> 3

DATE : 11/8/2016

JWS