




"ANY TRESS OR SHRUBS PLACED WITHIN WATER, SEWER OR DRAINAGE EASEMENTS SHALL CONFORM TO THE CITY OF DELRAY BEACH STANDARD DETAILS LD 1.1 AND LD."

"EXISTING NATIVE SOIL WITHIN ALL LANDSCAPE ISLANDS, INTERIOR LANDSCAPE STRIPS AND PERIMETER LANDSCAPE STRIPS, ADJACENT TO VEHICULAR USE AREAS, SHALL BE EXCAVATED DOWN TO A DEPTH OF THIRTY (30) INCHES BELOW EXISTING GRADE, EXCEPT FOR A 12" BUFFER FROM THE INSIDE OF THE CURB OR PAVEMENT. A SUITABLE PLANTING SOIL MIXTURE OF FIFTY/FIFTY (50/50), SIXTY/FORTY (60/40) (SAND/TOPSOIL) OR AS OTHERWISE INDICATED BY THE REGISTERED LANDSCAPE ARCHITECT, SHALL EITHER BE BACKFILLED IN PLACE OF THE NATIVE SOIL OR EFFICIENTLY MIXED WITH THE NATIVE SOIL TO CREATE AN OPTIMUM ENVIRONMENT FOR SUCCESSFUL ROOT DEVELOPMENT. IF NATIVE SOIL IS TO BE MIXED, IT SHALL FIRST BE SCREENED TO REMOVE ROCKS AND DEBRIS LARGER THAN ONE-HALF (1/2) INCH IN DIAMETER PRIOR TO MIXING. ALL PROPERTIES UNDER THIS SECTION SHALL BE REQUIRED TO HAVE AN OPEN BED INSPECTION PRIOR TO BACKFILLING TO INSURE THE THIRTY (30) INCH DEPTH HAS BEEN MET."

"ALL PROHIBITED PLANT SPECIES SHALL BE ERADICATED FROM THE DEVELOPMENT SITE AND REESTABLISHMENT OF PROHIBITED SPECIES SHALL NOT BE PERMITTED."







SCALE: 1'' = 20'

landscape architects and planners

LC - 0000396 2300 Corporate Blvd. NW. Suite 214 Boca Raton, Florida 33431 Ph: 561.955.8623

Fax: 561.362.4749 email: landscapearchitects@dsboca.com

06-25-21 GMP 07-08-21 SPRAB Review

> MAY 17, 2021 G.C.

DRAWN BY: M.J.

APPROVED BY:

This drawing is the property of Design Studio Boca, and is an reproduced in whole or in part without the express written permission of same.

SHEET

PERMIT